

CITY OF GAINESVILLE

NEW PUBLIC SAFETY FACILITIES



3911 W Newberry Road Gainesville, Florida 32607 o. 352.363.6070 f. 352.363.6071 scorpioco.com



PROPOSAL COVER PAGE (CCNA)

City of **Procurement Division** Gainesville (352) 334-5021(main) Issue Date: 6/9/23 REQUEST FOR PROPOSALS: #PWDA-230055-DH Public Safety Facilities Construction Manager at Risk PRE-PROPOSAL MEETING: □ Non-Mandatory ☐ Mandatory ⊠ N/A ☐ Includes Site Visit DATE TIME: LOCATION: Legal ad (Gainesville Sun) publish date: June 15, 2023 QUESTION SUBMITTAL DUE DATE: July 6, 2023 **DUE DATE FOR UPLOADING PROPOSAL:** July 14, 2023 at 3:00PM SUMMARY OF SCOPE OF WORK: City of Gainesville is seeking proposals from licensed contractor (hereinafter, referred to as proposer) to provide construction manager at risk services for public safety facilities. For questions relating to this solicitation, contact: Diane Holder (holderds@gainesvillefl.gov) Proposer is <u>not</u> in arrears to City upon any debt, fee, tax or contract: Proposer is NOT in arrears Proposer IS in arrears Proposer is not a defaulter, as surety or otherwise, upon any obligation to City: 🐹 Proposer is NOT in default 🔲 Proposer IS in default Proposer who receive this solicitation from sources other than City of Gainesville Procurement Division or DemandStar.com MUST contact the Procurement Division prior to the due date to ensure any addenda are received in order to submit a responsible and responsive offer. Uploading an incomplete document may deem the offer non-responsive, causing rejection. ADDENDA ACKNOWLEDGMENT: Prior to submitting my offer, I have verified that all addenda issued to date are considered as Addenda received (list all) #_ADD#1 part of my offer: Legal Name of Proposer: Domenic Scorpio DBA: DE Scorpio Corporation DBA Scorpio Authorized Representative Name/Title: Domenic Scorpio - President and CEO E-mail Address: domenic@scorpioco.com FEIN: 46-2621773 Street Address: 3911 West Newberry Rd. Gainesville, FL 32607 Mailing Address (if different): Telephone: (352) 363-6070 Fax: (352) 363-6071 By signing this form, I acknowledge I have read and understand, and my business complies with all General Conditions and requirements set forth herein; and, Proposal is in full compliance with the Specifications. X ated and attached hereto. X Proposal is in full compliance with the Specifications SIGNATURE OF AUTHORIZED REPRESENTATIVE: 7-14-23 SIGNER'S PRINTED NAME: Domenic Scorpio DATE:

This page must be completed and uploaded to DemandStar.com with your Submittal.

E-Bidding Document - RFQ (CCNA) - Page 1 of 113





3911 W Newberry Road Gainesville, Florida 32607

p: 352.363.6070 f: 352.363.6071

scorpioco.com

July 14, 2023

City of Gainesville Attn: Diane Holder Procurement Division Gainesville, FL 32601



RFQ # PWDA-23005-DH Public Safety Facilities Construction Manager at Risk

Dear Ms. Holder,

We are pleased to submit this proposal to the City of Gainesville for the Public Safety Facilities Construction Manager at Risk. Scorpio was established to bring community-centered buildings to life, for life. There is no denying that the ability to partner with the City of Gainesville and its Public Safety and Public Works agencies, who are committed at the highest level to advancing our communities, speaks to the heart of our organization.

Our priority during each project is protecting the public, staff, and visitors. Second to that is treating those we partner with integrity and fairness. We promote teamwork, professionalism, excellence, and respect in everything we do. We believe these shared values will create the foundation for a successful partnership with the City, the Police and Fire Departments, and Public Works.

Scorpio has an excellent record of delivering successful projects for the City of Gainesville and other local organizations, government entities, and institutions. Our team members know how to deliver work in and for the City of Gainesville. To adequately serve the City's need for multiple new facilities, we propose two exceptional teams with the specific experience necessary to deliver each project on time and budget.

Additionally, Scorpio acknowledges and supports the role of the community in a project like this. With decades of delivering work in Gainesville, this team has forged strong relationships with the local subcontractor community, and we are committed to maximizing the amount of work contracted to local and diverse subcontractors.

At Scorpio, we look beyond. Beyond the project. Beyond the owner. We must look to the people who will use the buildings we create – and beyond even that to the impact we will have on the community. People need buildings that frame and enhance their lives. Owners need a return on investment. We deliver both through dedication to detail and enhancement of your budget. We call this approach community-centered construction. And there is no community we are more dedicated to than our own.

After reviewing our qualifications proposal and understanding how our values align with yours, we hope you will find these Scorpio teams exceptionally qualified. We look forward to once again serving the City of Gainesville with our construction management services and bringing your buildings to life, for life.

Sincerely,

Domenic ScorpioPresident and CEO



Table of Contents

 Tab 1
 Project Understanding and Approach

 Tab 2
 Proposed Project Staff

Tab 3 Qualifications of Firm

Tab 4 Forms


Tab 5 Unique Capabilities







Understanding Your Project



PROJECT UNDERSTANDING:

We understand that the City of Gainesville intends to award two construction management contracts to assist with a Master Plan of Public Safety and Public Works Facilities for the city that will span multiple years. We believe the city is looking to engage a true community partner who will work to identify opportunities to save time and money while working alongside city staff and the selected design firms of Monarch/DLR and The Lunz Group, both of which Scorpio has a successful history of delivering high-quality projects.

Scorpio is ready to provide services for all or a portion of the facilities listed below. We understand that these services may be provided under a single task assignment or multiple task assignments and may include all or a portion of services. We acknowledge that the sites may be at their current locations, new

locations, or are still to be determined and that buildings may be collocated on the same site or within the same facility.

Construct, renovate, or expand eight fire stations:

- Fire Station 2 2210 SW Archer Road
- Fire Station 3 900 NE Waldo Road
- Fire Station 4 10 SW 36th Street
- Fire Station 5 1244 NW 30th Ave
- Fire Station 7 5601 NW 43rd Street
- Fire Station 9 4213 SW 30th Ave
- Fire Station 10 Waldo Rd at NE 39th Ave
- Fire Station 11 Weyerhaeuser North SR 121











Construct, renovate, or expand the following public safety facilities:

- Fire Training Facilities 1025 NE 13th Street
- Community Resources Paramedic Program Facilities 1025 NE 13th St
- Public Safety Hub Facilities (Headquarters) 1025 NE 13th Street
 Potentially includes Emergency Operations Center
- New Potential Headquarters Site
- Police HQ Administration 545 NW 8th Ave Potentially includes
 Emergency Operations Center, Evidence Storage, and Parking Garage.
- Southwest Public Safety Annex Administration and Briefing Room

Construct, renovate, or expand upon the following Public Works Facilities:

- Public Works HQ Administration 405 NW 39th Avenue
- Southwest Annex Administration and Equipment & Material Storage.


It is our understanding that the following projects have received priority funding and are likely to be the first to move into design and construction:

- 1. Eastside Fire Station
- 2. Fire Department Headquarters
- 3. Southwest Public Safety Annex
- 4. Public Works Admin Hurricane Hardening and possible Parking Garage
- 5. Police HQ Administration Evidence Expansion





Approach and Method



SCORPIO APPROACH + METHOD

KNOW THE JOB. MANAGE THE RISK. DELIVER ON THE PLAN.

Decades of experience have tested and refined the processes by which Scorpio successfully delivers a project. We become fully integrated project team members implementing our proven approach and method to deliver success. Scorpio's methods break down hierarchies and encourage teamwork such that all essential players collaborate to optimize delivery, ultimately reducing conflicts and project challenges. We emphasize process optimization to provide better client value and more cost-efficient production. Collaborating closely with the City of Gainesville and the appropriate user groups, the Scorpio team will provide an established and proven process for maximizing value without compromising program scope, budget, or schedule.

Our dedicated professionals will provide expertise with planning, estimating cost, value engineering, constructability reviews, systems and material detail analysis, planning and scheduling, site logistics, subcontractor procurement, and ultimately the day-to-day management in delivering these Public Safety Projects.

Once selected, we will fully engage the City of Gainesville and the Fire Department to understand each project program fully. What are the conditions of satisfaction that will make this project a success? We have an outstanding reputation for delivering projects on time and (or under) budget, and our level of repeat business illustrates this. Our clients know that we work as their partners on every project. Most of our clients are public entities with strict budgets and set timelines. We work side-by-side to determine the most efficient and cost-effective ways to deliver their projects.

EXTREME OWNERSHIP

Scorpio operates under a philosophy of extreme ownership, which extracts the highest level of commitment from every team member and fosters leadership at every level. Several teams within our organization work cohesively on all our projects. This approach allows team members to apply their expertise to your project, creating high quality in our delivery, efficiencies in our processes, and ultimately reducing the cost of our services. Scorpio's "Team of Teams" approach to managing the building of Gainesville's New Public Safety Facilities consists of the following:



Administrative Team

President and CEO Domenic Scorpio leads our Team of Teams with decades of experience, long-standing relationships, and creative problem-solving. Jessica MacLaren, Finance and Administration Team Leader, ensures budgets and ODP are monitored, pay applications are reviewed, proper insurance and lien releases are secured, and financial risks to your project are mitigated.

Preconstruction Team

Chris Gregory, Preconstruction Team Leader, is responsible for cost estimating and leading our 6S process for bidding on a job. In addition to estimating, he assists the operations team in procuring subcontractors and materials. He drives the entire project team through design and pre-con, focusing on managing budget and program requirements.

Project Operations Team

For these projects, we have identified two teams that will be dedicated to the City of Gainesville. Team 1 will consist of Senior Project Manager Ryan Stroh, and Team 2 will be led by Senior Project Manager Tracy Koller. Ryan and Tracy will utilize Best Practices and monitor the jobs for consistency and compliance. They will work collaboratively with each of the Design Team members and oversee all aspects of the project. At the onset of each project, Ryan and Tracy will work closely with Chris Gregory, our Preconstruction Team Leader, to ensure potential risks are mitigated, budgets and specifications are accurate, and schedules are realistic. Ryan and Tracy will each be supported by Assistant Project Jenna Hollingsworth and Maverick Maensivu, respectively. Don Kellogg, our Project Operations Team Leader, will provide the oversight necessary to ensure each project stays on time and within budget, supporting Ryan and Tracy as needed.

Field Operations Team

Field Managers Matthew Clark and Rick Solana have been selected based on their previous experience and success in constructing New Public Safety Facilities and other municipal facilities. Each will manage our craft and trade partners and lead the on-site team daily. Matthew and Rick will be the lead point of contact on their sites during and after construction to address any post-occupancy or warranty issues. Aaron Rogers, Field Operations Team Leader, will ensure the quality and schedule are maintained and provide a second set of eyes and additional support for Matthew and Rick.







Preconstruction: Know the Job



COORDINATION

Our process begins with communication. Clear and consistent communication is at the center of every successful project. The members of this Team have an outstanding track record of providing precisely that from Preconstruction through Warranty. Our team is committed to consistent communication with all stakeholders, clearly articulating the project needs and then focusing on the details necessary for delivering a high-quality project on time and budget.

DESIGNING TO BUDGET

The pricing of each of the City of Gainesville's Public Safety Facilities will be a team effort led by Chris Gregory, Preconstruction Team Leader, working in collaboration with the Design Teams and with the Project Manager and Field Manager assigned. They are tasked with developing an elevated level of understanding of the project requirements, existing conditions, and, most notably, the City's priorities and goals.

As designs evolve, estimate updates will occur in real-time and continuously build upon the team's decisions. This approach drives the decision-making process of "Designing to Budget." Preconstruction Team Leader, Chris Gregory, will employ all his resources to review the project and provide a comprehensive value analysis. How do we build it better for less?

Our cost estimating, analysis, and control methodologies will be integrated into the overall design process and utilize BIM models

to ensure accurate and timely results. Our primary goal is to offer a balance of functionality, durability, and efficiency to maximize the scope of work and varied needs for the available budget. The process begins with the broadest view and continues with the smallest details.

As our team seeks to collaborate with all stakeholders to "Design to Budget," individual budget responsibility for each project system will be assigned to a design team member at the project's onset. The component is assigned a cost per square foot based on project or industry benchmarks. As the project moves through design, these systems' costs will be monitored to ensure the budget is held. For example, suppose a program or system complexity drives a change in the price assigned. In that case, this will be immediately identified, and a decision will be made involving the City, the Fire Department, the Design Team, and Scorpio regarding the identified changes' impact on the overall budget. This highly detailed estimating process provides information to track changes as they occur and forces design evolution discussion across the team.

Categories are created for all major systems and materials, and each category is priced at the Program Conceptual Design, Schematic Design, etc., until the design reaches 100% Conformed Construction Documents. This iterative pricing sequence will allow the team to discuss changes affecting the overall project budget, and the team, as a unit, will decide where to make scope and cost adjustments.




UPDATING THE ESTIMATE

A milestone design estimate will be provided with a detailed list of notable changes from the last milestone estimate (i.e., Schematic Design, Design Development, and Construction Documents). These will be accompanied by Cost Event Logs used to manage decisions and changes as they occur. A Variance Report is generated between deliverables to offer a look back on a prior decision or change should it require revisiting. Our role is to provide accurate data, managed in an easy-to-understand format, to simplify decision-making throughout estimating.


VALUE ANALYSIS

Value analysis is a deliberate and organized approach to obtaining the optimum value for each dollar spent. The goal is to analyze the functional requirements of a project component and determine the best way to achieve the essential function at the lowest total cost without sacrificing Quality. For the City of Gainesville's New Public Safety Facilities, we will use a proven process that draws on the entire Team's expertise, creativity, and desired outcomes: staff, designers, engineers, and subcontractors.



An example of our process for Lifecycle Analysis is provided as a supplement Work Product Book.

A complementary tactic that is used in tandem is Lifecycle Analysis. This examines a specific product or system, its cost, and the likely length of use. This information is used to determine the best course of action when choosing a product that will meet the desired outcome for the owner and the budget in the short or long term. A product that may be less expensive to implement initially but requires replacement or maintenance more often will cost the owner more over the life of the building. However, purchasing a more expensive option with a longer "lifespan" may reduce costs over the long term. This can also be used when selecting energy-efficient appliances and MEP systems and the impact on utility bills. All of these factors must weigh into the final decision-making.



SCORPIO'S 6S PROCESS

In everything we do, Scorpio executes as a team. Over the years, we have developed a specialized and detailed approach to project delivery called the 6S Process. The 6S Process assigns everyone on our team to one of six main categories (Site, Structure, Systems, Skin, Surfaces, and Specialties) with a designated "Captain" for each. Each Captain leads a team comprised of Division Experts. Division Experts routinely engage with the various subcontractors and suppliers in a specific trade to strengthen communication, an improved understanding of market conditions, and further relationships. This has proven a critical component in cost estimating for Scorpio, generating only the most accurate and trustworthy numbers.

At each milestone stage of design (i.e., Schematic Design, Design Development, etc.), a milestone design estimate will be provided with a detailed list of notable changes that occurred from the last milestone estimate and accompanied by a Cost Event Log that is used to manage decisions and changes as they occur. A variance report will be generated between deliverables to offer another look back in case a prior decision or change requires revisiting. Our estimating role is to provide accurate data, managed in an easily understood format, to simplify decision-making.



CONSTRUCTABILITY REVIEW

A thorough Constructability Review will involve analyzing the entirety of the project(s) from a very broad perspective down to evaluating the smallest details. This review will determine those items that fall outside of the lines on the drawings but are critical in ensuring each of the City's projects is successful.

During the intensely collaborative process of the Constructability Review, we will establish exactly how the Team will build the project. Site constraints, systems coordination, and material and equipment availability are just a few items explored and discussed. How can we build it safer, faster, better, and more cost-effectively? The Constructability Review will drive the development of project schedules and validate the budgets and quality goals.

EXISTING CONDITIONS

Initially, we will spend ample time verifying field issues and existing conditions and planning for the infrastructure costs that impact the budget. Our Team has the experience necessary to assist in recognizing issues that could affect the budget and the problem-solving skills to tackle any issue.

DOCUMENT REVIEW

The goal of Document Review will be to save the City time and money by uncovering problems or potential problems that otherwise would be encountered during construction, such as errors, omissions, ambiguities, and conflicts within the plans. Better instructions equal fewer mistakes.

During the design and bidding phase of the New Public Safety Facilities, multiple members of Scorpio will provide thorough reviews of the design documents ensuring that all the details tie together. Our Team will confirm that the work requirements are precise and the documents are well-coordinated, providing accurate bidding and project administration. As we promote a team approach to every aspect of a project we manage, this is an area in which we demonstrate exceptional ability.









3 PHASES OF PRECONSTRUCTION

The primary objectives of Preconstruction Services are to ensure potential risks are mitigated; budgets are accurate, schedules are realistic; but most importantly, that stakeholders are heard. Scorpio's number one goal during Preconstruction Services is to listen and understand the goals (and the concerns) of every team member at the table. In doing so, we can identify innovative solutions, provide accurate cost and schedule information, and ultimately deliver a project that meets the needs and exceeds the expectations of its owners and end users.

PHASE 1

Initial project evaluation involves creating a budget estimate and anticipated construction schedule based on the site use and necessary improvements, as well as selecting materials and building systems at the schematic design phase provided by the architect and reflecting the Team's understanding of the project. During this phase, discussion with potential trade and craft partners begins to generate interest and information. Additionally, one of the most critical aspects of this project will be our assistance with local agencies and authorities having jurisdiction. Here, our relationships and experience will bring valuable assistance to identifying and meeting these requirements.

- Evaluate existing infrastructure capacity, location, & proposed routing
- Validate structural system and building envelope costs and schedule implications
- Determine budget targets for Mechanical, Electrical, Plumbing, and Fire Protection systems

PHASE 2

Engage the Team for project value analysis to align the budget with the design and construction criteria. This includes evaluating the design as it progresses and evaluating site implications, systems and equipment specifications, life cycle data, and constructability. The availability of materials and labor is discussed with trade and craft partners. The Team is then presented with all cost-saving alternative solutions with detailed estimates and budgets. All suggestions are reflected with any potential impact to the project schedule.

- Site permitting
- Prepare detailed project estimates utilizing industry-leading estimating systems
- Analyze conceptual estimate vs. budget requirements
- Provide life cycle cost analysis of specified materials
- Provide alternative solutions, including cost, schedule, and quality impact
- Review design documents for inaccuracies, oversights, and thoroughness
- Evaluate proposed materials, systems, and product delivery
- Identify long-lead delivery materials and equipment
- Target areas of concern
- Solicit subcontractors and supplier input
- Obtain team consensus

PHASE 3

Establish a Guaranteed Maximum Price (GMP) for the project. Once the design has been modified to reflect decisions made during Phase 2 Services, Scorpio will provide a detailed analysis of the documents to ensure accuracy and provide a detailed project schedule and GMP to build the project. Our firm will procure subcontractors in a competitive bid process to ensure maximum value is achieved.

- Building permits
- Develop GMP
- Review in detail the cost estimate with the design team and project stakeholders
- Solicit subcontractor input relative to market conditions
- Prepare final project costs
- Provide cash flow management
- Pre-qualify equipment and material vendors
- Develop comprehensive bid packages for each trade
- Hold prequalification subcontractor interviews
- Distribute bidding documents and receive proposals
- Perform a detailed quality analysis to develop a baseline for comparison
- Verify compliance with SREF, federal, state, and local regulations
- Provide a project-specific logistics plan
- Reinforce team concept at every opportunity
- Maintain an open-book policy







a schedule is a plan, a plan for success.

PLANNING + SCHEDULING

Scorpio will work with the City of Gainesville to review timelines and the opportunity to phase projects. One phasing strategy often utilized is an early release package (ERP). This typically involves utility and infrastructure work that can be completed while the design team finishes the 100% construction documents. The ERP can include structural and/or equipment elements with long lead procurement times. In both cases, the net result is twofold:

1. Construction starts sooner, reducing the volatile labor and materials market risks.

2. Overall project schedule can be reduced.

The entire team will collaborate early to develop a construction schedule that is meaningful and effective in communicating and managing the work. Once construction begins, the schedule will be monitored for planned versus actual events daily, continuously updated, and routinely shared up and downstream. The Team will always plan and adjust when there are shifts or disruptions to the schedule. Decades of experience have ensured that our projects are prepared with the "expect the unexpected" philosophy. This is why we have never failed to deliver a project on time.







Project Operations - Manage the Risk



Consistent and effective communication is the cornerstone to the success of any project. Identifying expectations produces a roadmap for the delivery of that project. Both impact every aspect of a project's management plan, from organization and record-keeping to job site management. Our team manages every project with an eye for communication, continuity, efficiency, accurate record-keeping, and reporting. We schedule routine meetings with the design team, owners, and user groups to ensure timely information sharing. Continuous exchange of information occurs daily to move open items through the process, ensuring schedule and budget adherence.

DATA MANAGEMENT- SYSTEM AND SOFTWARE SUPPORT

The ability of each stakeholder in the City to have up-to-date access to information is paramount. Our team will administer this project with a commitment to continuity, record-keeping, and reporting. The software Scorpio utilizes to support project management is Procore. An industry-leading, secure, cloudbased data management software accessible to all project stakeholders. It is simple to navigate and provides instant access to project data from any computer or mobile device. The number of users is limitless, allowing us to collaborate in real-time with architects and their consultants, the owner's representatives, and the project manager, as well as any others requesting access. Utilizing this tool is essential in maintaining organization, maximizing efficiency, and ensuring project documents are updated in real-time and readily available. This powerful software, combined with strict adherence to mandatory company procedures, ensures seamless and accurate coordination with the City of Gainesville.

As with every aspect of project management, our goal is to keep the entire experience centered on the New Public Safety Facilities. Therefore, we are dedicated to making the management and sharing of information as user-friendly as possible.

MONTHLY REPORTING

Construction in the technology age is a fast-moving process that provides a seemingly endless number of ways to deliver information. Procore, with readily available access for all stakeholders, provides information about a project at your fingertips at a moment's notice. However, owners often require a more traditional report each month to track the job's progress in a format that can be shared with project stakeholders who may not be involved in the daily conversations or weekly meetings. Knowing this, Scorpio provides a customizable report that contains all the predetermined information in a single source format.

Documents such as Requests for Information (RFI) and submittal logs printed from the project management software, along with schedule updates, financial status, and pictures can provide a quick snapshot of the project you can hold in your hand or view on a screen. We will adjust these reports to meet the City's specific needs in format and frequency.


COMPETITIVE BIDDING FOR SUBCONTRACTS

Scorpio prides itself on our team members' relationships with subcontractors over the past 35 years. With over 3,000 active subcontractors and vendors in our directory, we offer an unsurpassed depth of knowledge related to craft professionals' capabilities in North Central Florida.

PREQUALIFICATION AND PROCUREMENT

The first step is publicly advertising the work and promoting interest to the broader community. We always look to work with small and diverse local businesses. In a parallel effort, vendors already in our comprehensive database are electronically notified of the upcoming work. Subcontractors interested in the project are then asked to submit qualification criteria ensuring their experience matches the services needed.






Once the qualified firms are identified, an electronic link is offered for the bidders to access information specific to the project. Bidders can download plans, specifications, scopes of work, and bid instructions through this directory. A project-specific portal allows a safe exchange of potentially sensitive project information (such as security systems, etc.) to a controlled group. Our portal also provides for an exchange of information, such as pre-bid RFIs, further ensuring that all bidders have equal access to the information necessary to submit a responsive bid.

At any time in the process, our team can view which bidders have downloaded information, how many times they have accessed the site, and their intent on bidding on the work. Participating bidders are invited to a pre-bid meeting, where the project expectations are communicated, and the site is walked through, allowing bidders to familiarize themselves with potential challenges in delivering the work. As the bid date nears, bidders are sent email reminders at intervals of seven, three, and one day before bidding, greatly enhancing bidder participation. When receiving bids, all team members will strictly adhere to the City of Gainesville procurement standards.

Keep It Local

We offer a depth of knowledge on the capabilities of craft professionals, both small and large, working in the City of Gainesville and the surrounding areas that are unsurpassed. Our team members have lived and/or worked in the City of Gainesville for decades, and we currently have two active projects there. In addition to our firm's extensive database, each team member has many personal re-lationships from working on previous projects in the area. Our commitment to the City will be to maximize the participation of small and local businesses on each of the New Public Safety Facilities.









- Integrated into company plan
- Maintaining a network of firms
- Regular engagement
- Mentoring + partnering with smaller firms
- Workshops/Information Sessions
- Packaging Work Scope
- Maintain cash-flow: Pay on the 10th of the month

The Scorpio Guarantee

A key to Scorpio's success in the industry is our commitment to payment on the 10th of the month. Regardless of whether we have been paid, Scorpio guarantees payment to our subcontractors for the work they have performed. This gives our firm a remarkable advantage when recruiting subcontractors and soliciting competitive pricing. The best subcontractors prefer to work with Scorpio knowing their payment is secure. They give us the lowest bids on bid day and focus on Scorpio projects when their resources may be strained.

OWNER DIRECT PURCHASE

We take an aggressive approach to Owner Direct Purchase (ODP). A key to providing cost control for a tax-exempt entity

is maximizing Owner Direct Purchase (ODP), which we believe should be maximized to the best of its ability.

ODP is a valuable cost-saving tool but can increase work for an owner. Scorpio provides valuable insight into the most cost and time-effective ways to manage these purchases, many of which can be very large. Our management and accounting teams have years of experience working with projects that heavily utilize ODP.

Upon acceptance of the GMP, Senior Project Managers Ryan Stroh and Tracy Koller will prepare a list of items that may be desirable for ODP. Proposed items will be purchased in a single order from a single Contractor with a value greater than \$10,000. Ryan and Tracy, along with Scorpio's Project Administration and Accounting Jessica MacLaren, will work closely together to eliminate the burden of this program while ensuring all logical avenues for the cost savings associated with sales tax savings are explored. It is our goal to achieve the most savings possible.

COST MANAGEMENT THROUGHOUT CONSTRUCTION

Nothing can cause more conflict or disruption to a project than the mismanagement of budgets. Established very early in preconstruction, budgets will be determined based on a project's goals and will create a framework for all decision-making. We will work closely with the City of Gainesville to ensure accurate information is used to maintain the budget.

Our team ensures that well-documented scopes of work, established standards of quality, and approved schedules will deliver each of the New Public Safety Facilities with little to no cost adjustments. Once the final budget is established and construction begins, our operations team will lead in delivering the final vision. Subcontractors pay applications, insurance, lien waivers, and change requests are continually reviewed for accuracy before releasing funds. Costs will be monitored continuously for actual versus projections. Scorpio's diligence and commitment to creating a true partnership are why we consistently deliver projects on or below budget.

During project construction, the team will focus on opportunities to maximize value by incorporating cost-saving strategies throughout the process without sacrificing quality.







Schedule of Values and Workflow

Throughout construction, team members from Scorpio will monitor the project for its adherence to the Schedule of Values and Workflow. The Project Manager and Field Manager will ensure that "we bill the job as we build the job." Vigilance in this area safeguards the budget and creates an early detection of potential issues related to a subcontractor's performance and schedule.

Monthly Pay App Reviews

To ensure that the work being billed matches the work that has been put into place, our team will conduct thorough Pay Application Reviews. This helps to eliminate potential conflict later in the process and ensures that the City has received exactly what is being paid for.

Change Order Management

Added or reduced scopes of work will occur during the construction of any project. When they do arise, we will manage the process and complete an internal review to validate a subcontractor's proposal for accuracy. This provides you with a level of comfort and clarity, knowing that changes presented

are being scrutinized at the same level as the original documents and opportunities for cost savings are being captured.

Manage Scope Creep & Compliance Methodology

Scope creep refers to the tendency for a project's requirements, goals, or objectives to gradually expand or change beyond their original scope. This is something that our team works to limit or prevent on every project. First and foremost, it is our responsibility to ensure the intent of the project, as well as all site conditions, are identified thoroughly at the onset of the project. Our team is experienced and routinely trained to identify areas that may lead to scope creep and bring them to the attention of the owners and the design team.

While some scope changes may be necessary for the success of the project, uncontrolled scope creep can result in delays and cost overruns. This team is dedicated to ensuring that does not occur. Regularly reviewing and updating the scope throughout the project's lifecycle is essential. Utilizing our Change Management Process that outlines how scope changes will be requested, evaluated, approved, and implemented, as well as how they will impact the project's schedule and budget is a critical component. By managing scope changes proactively, we ensure our projects stay on track and deliver the expected results.



Field Operations - Deliver On The Plan



SAFETY ON THE SITE

Safety is the number one priority on all of our projects. Scorpio has a "zero tolerance" policy as our safety standard. Each project will have its own Project Specific Safety Plan. Our safety program addresses the safety of construction workers, the public, employees, and visitors through circulation, separation, and isolation. Circulation is addressed in several methods, such as signage, road crews, and roadblocks. Separation is achieved with fencing, barricades, and partitions. Isolation addresses a specific work scope that must tie into an existing building system or utility infrastructure that must be "isolated" not to affect the activity the system or utility supports.

SAFETY OF THE PEOPLE

Oversight

The entire team is responsible for safety oversight, but the job site-specific management is the responsibility of each of the Field Manag-ers. As a team, we identify the potential hazards of a given project, followed by a Project Specific Safety Plan that ensures constant circulation, separation, and isolation between work and the building occupants. Our safety plan addresses noise and dust considerations, traffic flow requirements, and timed material deliveries.

Education

Our Field Managers maintain Occupational Health and Safety Administration (OSHA) Certifications as a minimum education requirement. The Field Managers educate project stakeholders by communicating regularly. Construction workers must participate in a pre-job safety orientation that concludes with an easily identifiable hard hat sticker branding their completion of orientation. "Safety Talks" and "Tool Box Meetings" occur each morning before work commences to address general safety topics and specific daily work activities, explicitly citing safety awareness of such actions.

Enforcement

Everyone associated with the project is required to adhere to OSHA and Scorpio Safety Standards. There is no such thing as a second chance 'regarding safety enforcement on the job site. Safety standards and protocol violations are addressed by dismissing the construction worker from the project site immediately if deemed appropriate. They must participate in the safety orientation program again before returning to work on the project.



ON TIME ON BUDGET 100% OF TIME



SCHEDULE - ON TIME. EVERY TIME.

The two fixed resources on every project we manage are time and money. Our team understands that once these critical components are established, our primary responsibility is to hold everyone accountable for reaching the goal of being on time and on budget. We have done this time and time again through our client-oriented approach, which involves the client and stakeholders from the onset of the project through its completion. Our constant communication and collaboration engage the entire team so that we can complete projects efficiently. Whether for ADA studies or brand-new facility design, all receive the same scrutiny for budget savings, oversight for timeline adherence, and rapid problem-solving by principals and project managers. We provide single-source leadership and established procedures for all phases of a building project, including tracking mechanisms that ensure the alignment of all project goals, schedules, and budgetary requirements.

CREATING AND MANAGING THE SCHEDULE

Schedules are the scaffolding for every project we manage. They are an essential management tool that enhances the decision-making process throughout a project. Tracy and Ryan will work with Matthew and Rick and collaborate early in the Preconstruction Phase with Preconstruction Team Leader Chris Gregory to create a construction schedule that is meaningful and effective in communicating and managing the work. Each of the New Public Safety Facilities' schedule will be built with industry-leading scheduling software and presented in critical path methods (CPM) and bar chart formats.

The schedules will be updated every two weeks. We will involve potential subcontractors for their feedback in developing preliminary schedules when critical. During the bidding process, subcontractors can review and comment on the durations and sequencing of work activities, as the schedules are ultimately incorporated into the subcontractor agreements.

Progress

During construction, schedules will be used to continually compare actual progress to planned progress. Regularly performing these comparisons, deviations will be identified early, and a modified plan can be formulated before it affects actual construction. Matthew and Rick, working closely in the field and understanding the project progress better than anyone else, are the clear owners of the schedule once construction begins. Matthew and Rick will create regular updates and will be reviewed in detail with Ryan and Tracy, who regularly look to the bigger picture of the schedules and how those intricate details tie into the larger goals.

Performance

Because of this continual updating, the plan is workable and realistic. Schedules are communicated formally during weekly meetings. Two-week look-ahead schedules are utilized to communicate the upcoming workflow with the subcontractors by Matthew and Rick. If potential delays are identified, our team will work to recover the lost time by re-sequencing work activities, adjusting the durations of future activities, extending workdays, and supplementing workforces.

Weather is always a factor in a construction project schedule. North Central Florida has its share of weather that can delay a project if not anticipated and planned for accordingly. The project leaders of this team are both local to North Central Florida and understand the seasons and how they impact construction. Guided by Field Operations Team Leader Aaron Rogers, an activity's duration is considered not just for how long it should take and how it ties into other activities but for the time of year it falls. Critical activities that can easily be affected by rain, such as foundations, will be given more time to complete if they must occur in the typically wetter times of the year.

A schedule is a plan, a plan for success. In construction, as in life, plans must be fluid to adjust to how things will transpire.



Unforeseen events regularly occur that affect a project's schedule. Corporate restructuring of a material supplier may shutdown a factory and impact the manufacturing of components just as easily as a hurricane that misses Florida may impact a precast plant in another state and thereby affect delivery to a project. Scorpio's experienced and skilled professionals plan for and adjust for these occurrences because we know to expect the unexpected. This is why we have never failed to deliver a project on time.

OUALITY CONTROL


Quality Control begins during preconstruction. Our approach ensures that construction documents are complete and well-coordinated. To support these objectives, we have developed a rigorous quality management process focusing on all aspects of the project delivery to ensure the documents clearly articulate the work through to completion. This effort is well-established and successfully executed by our team of experts. For each of the New Public Safety Facilities, we will hold ourselves and our subcontractors to the highest standards and continually strive to exceed your expectations. This will undoubtedly be crucial when planning and implementing our standards for our Quality Control Program.

ACCOUNTABILITY IS KEY

Quality Control is a key facet of each team member's job, and accountability is built into every team member's performance measures. Scorpio's Quality Control Program outlines the personnel and procedures utilized in maintaining the highest standards from project to project. Quality Control measures include organization, inspections and testing, documentation, remedial work, and warranty procedures for us and our subcontractors. Our team routinely collaborates to review and adjust the Quality Control Program to become more efficient and effective every day.

FROM BEGINNING TO END

Openly communicating and providing access to information are best practices for proactively managing subcontractors and vendors and, thereby, quality. Our methodology includes specific milestone reviews during the design process, soliciting external peer reviews when necessary, and conducting ongoing training in quality-related issues. We work closely with architects and engineers to maximize value in program scope, budget, quality, and schedule as it relates to meeting the needs of utility relocation and maximizing building design.









SUBMITTAL AND SHOP DRAWING REVIEWS

During preconstruction, our approach ensures that construction documents are complete and well-coordinated. To support these objectives, we have developed a rigorous quality management process focusing on all aspects of the project delivery to ensure the documents clearly articulate the work through to completion. This effort is well-established and successfully executed by our team of experts.

Once construction documents are final, they are issued to prequalified subcontractors demonstrating the availability of resources to carry out the work. The project is competitively bid, followed by scope reviews with the apparent low bidders, and finally, the issuance of subcontracts as construction beings, Project Managers provide continuous oversight with the meticulous review of submittals and shop drawings. Our team is trained to look for inconsistency in the smallest details and clarify the desired outcome with the design team and/or the subcontractors.

PRE-INSTALLATION MEETINGS AND MOCKUPS

An integral component of our Quality Control Program is our Pre-Installation Meetings. A Pre-Installation Meeting is performed to verify that the work accomplished in preparation for an installation meets the tolerances specified. These are conducted with the subcontractors to review the approved submittal data, manufacturer recommendations for material installation, mockup requirements, and third-party review of mockups. Mockups have become an invaluable tool to ensure that a specific product's look, quality, and installation meets everyone's expectations.

MAINTAINING HIGH STANDARDS

As work commences, Matthew and Rick will perform Quality Assurance Inspections to ensure quality workmanship from all subcontractors. Any known deficiencies will be communicated on the spot and documented in the daily log for correction by the subcontractor. Corrections will be made as they are



identified before significant time is lost, and the cost of rework errors affects a subcontractor's ability to complete the project successfully. Matthew and Rick will also tour the active construction sites with the City of Gainesville team as work is done. Each part of the project is seen in real-time so that there are no surprises at completion. We find this to be crucial in delivering high-quality workmanship. For critical scopes of work, mockups will be field built to validate the quality standard. Once approved, these will be used as the benchmark for the remaining work.

In addition to daily communication between subcontractors and Matthew and Rick, formal weekly meetings will be conducted to address updates in contract documents, review progress, and communicate two and three-week schedule lookaheads. Formal meeting minutes will be published for all project stakeholders. This process will be adhered to until the project is 100% complete. A well-communicated project ensures that everyone is successful in delivering quality work.

ROUTINE INSPECTIONS

Overall management of the Scorpio Quality Control Program is the responsibility of the Field Team Leader, Aaron Rogers. He regularly visits every project to review documentation, including constructability reviews and inspection reports, at which time he assesses questions or concerns with the client. Aaron has nearly 30 years of experience as Field Manager. He has developed relationships based on his high standards and mutual trust and respect.



POST OCCUPANCY AND WARRANTY

Our commitment to a project continues long after the final cleaning and handing over the keys. We know how important it is for our clients to feel comfortable in their new space, understand how each system integrates, and be confident that should they need our help, we are only a phone call away. The peace of mind comes with a thorough warranty program, but more important is the realization that a partnership with Scorpio remains consistent so our clients get the most out of their building.

Properly operating and maintaining a new or renovated building is incredibly important. Our team coordinates training sessions so the right people know how to use and maintain the equipment and materials. We document and record training as a resource; as always, we are ready to help if there are questions.

The process for making a warranty claim was created to be simple and direct, as access to Tracy, Ryan, Rick and Matthew will be maintained with routine scheduled follow-up inspections. We can always take your calls, answer questions, and help. This is the level of customer service a true community partner offers, and Scorpio has built its reputation upon.

WARRANTY AND SERVICE SUPPORT

Material, Equipment, and Systems Warranties are provided after projects. The warranty on a project delivered by Scorpio takes effect when the facility is officially turned over to the owner and its user groups. It remains in effect for one year.

We ask clients to notify our office of the potential warranty item with as much information available, including the person we will need to coordinate with regarding further action. Upon notification, a Warranty Claim Ticket is opened, and our warranty protocol is activated. This ensures that each request is assigned to the appropriate person(s) and acted upon within 24 hours (sooner if it is an urgent request). Upon satisfactory resolution of the item, we provide the client with a copy of the warranty claim form to document the issue and solution.

As part of the close-out procedures and documentation for each project, Scorpio provides the client/user groups with the following:

- Contractor Warranty
- Subcontractor Warranties
- Material Supplier Guarantees
- Inspections
- Test Reports
- Operation and Maintenance (O&M) Manuals
- Owner Training
- As-Built Drawings
- Approved Submittals
- Keys

1

PHYSICAL COMPLETION OF WORK

- Substantial completion
 - Cleanup
 - Punchlist
 - Demobilization
 - Final completion

2

COMMISSIONING

- Material or Equipment Testing
 - Owner Training
- Submission of Training Reports
- Testing and balancing (HVAC)
 - Indoor Air Quality Testing

3

HANDOVER OF PROJECT DOCUMENTS / WARRANTIES

- As-built documentation
- As-built specifications / equipment manuals
 - Project guarantees
 - Material warrantees
 - Final testing reports
 - Final lien waivers
 - Attic stock or spare parts

4

FINANCIAL CLOSEOUT OF DOCUMENTS

- Final review of project costs
- Submission of final requisition
- Reduction in retainage to 0% (or as governed by the contract)
 - Final payments (as governed by the contract)
- Reconciliation of Owner Direct Purchase Program

5

INSPECTION & SIGNOFF

- Warrantee inspections
- Architect's & Owner's punchlist inspection
 - Special Inspections
 - Technical Reports
- Building inspections
- Certificate of Occupancy



Community Engagement



YOUR COMMUNITY PARTNER

Before and during construction, the team, with your close involvement, will also be focused on your project's community engagement and marketing. Scorpio's Marketing Team will create a community engagement plan for the project, tailored to the unique needs and characteristics of the community it serves. This team comprises creative and strategic members engaged in design, marketing, media, and event planning for the last 20+ years. We offer these innovative communication services to our owners and clients, furthering the experience of working with Scorpio.

Community engagement on a construction project involves actively involving and collaborating with the local community throughout the various stages of the project. We aim to create a positive and inclusive experience where community members can provide input, express concerns, and feel heard and connected to the project. The ways we ensure engagement is through our proven processes:

- 1. Stakeholder identification: Identifying critical stakeholders within the community who may be directly or indirectly affected by the construction project. This can include residents, local businesses, community organizations, schools, and other relevant groups.
- **2.** Communication: Establishing effective communication channels with the community is essential. This can include holding public meetings, establishing dedicated project

websites or social media platforms, distributing newsletters, or organizing information sessions to inform the community about the project's progress, timelines, and potential impacts.

- **3.** Mitigation strategies: Developing and implementing strategies to mitigate any potential negative impacts of the construction project on the community. This may involve noise reduction measures, traffic management plans, minimizing dust and air pollution, ensuring pedestrian and cyclist safety, and addressing concerns about access to local amenities.
- **4.** Community involvement: Encouraging community involvement in the project by offering opportunities for volunteering, apprenticeships, or employment. This can help foster a sense of ownership and pride within the community and provide economic benefits.
- **5.** Education and awareness: Providing educational materials or conducting workshops to raise awareness about the construction project's purpose and potential benefits. This can help dispel misconceptions, address concerns, and ensure the community clearly understands the project's objectives.
- **6.** Ongoing engagement: Maintaining regular communication and engagement with the community throughout the project's lifespan. This involves responding to inquiries, promptly addressing concerns, and keeping the community updated on any changes or developments.



Dedicated Community Liason

- Informal Meetings
- Project Newsletters
- Construction Progress Webpage
- Open House Events
- Regular Email or Text Updates
- Visual Communications Signage
- Social Media Engagement
- Feedback and Issue Resolution



Our team understands the value a diverse workforce brings to the betterment of communities. The tone for Scorpio's vendor diversity policies and goals is established at the top by Domenic Scorpio and executed at every company level, from our paper supplier to our steel providers.

Scorpio is committed to a 30% minimum goal of DBE participation on each of our projects. We have successfully achieved and exceeded this goal by utilizing several strategies to generate interest and attract diverse companies to our projects.

Some of which include:

- Partnering with smaller diverse CM firms
- Using the State of Florida's Office of Supplier Diversity
- Working with various City and County Small Business and Vendor Diversity Offices
- Participating in Mentor Protégé Programs
- Creating Information Sessions, Matchmaker Events, and Technical Assistance Workshops

For the New City of Gainesville New Public Safety Facilities, our Communication and Community Outreach team member Jennifer Denault and the project team will ensure we engage with as many small and diverse businesses as possible. Jennifer will create and execute a specific plan to maximize DBE participation on each project. The following strategies are just a few that have proven successful on past projects:

- **1.** Participation in local outreach programs at the city, county, and regional levels to attract Small, Minority, Disadvantaged, Veteran, and Woman-owned businesses.
- 2. Partnering with supplier diversity organizations and their members attendwing events and chapter meetings which, in the past, has led to many introductions to skilled minority trades.
- 3. Attending supplier diversity trade shows and conferences.
- 4. Participating on panels at technical assistance workshops to assist businesses with bidding opportunities, networking, presentation, and other industry-specific processes.

The team will also assist small and diverse business enterprises during the construction, close-out, and warranty phase of any given project by:

- Providing flexible insurance limit requirements
- Helping to ensure that all safety and administration requirements are met
- Providing joint checks to material suppliers
- Providing fast and flexible payment options
- · Providing fast project close-out and release of retainage
- Providing references for future clients and projects
- Guaranteed payment on the 10th of every month










SAMPLE SCHEDULE





CURRENT + PROJECTED WORKLOADS

Outlined here is our firm's current and projected workload. Based on the information provided regarding these upcoming projects for the City, the proposed team members will be available to serve in the capacity required for a successful delivery, devoting the time and resources required. Scorpio has an exceptionally qualified team available to support the City of Gainesville for each of the New Public Safety Facilities. By proposing two dedicated teams for the City of Gainesville ensures our ability to meet the demands of multiple projects. Should additional resources be necessary, we have the team members and the availability to deliver.

Project Name	Contract Value	Stage of Completion	Owner/Phone/Email
UF Multiple Continuing CM Services Projects	\$5,008,010	varies by project	University of Florida - Frank Javaheri (352) 273-4027 fjavahe@ufl.edu
Santa Fe College Multiple Continuing CM Services Projects	\$1,011,032	varies by project	Santa Fe College - Rebecca Rogers (352) 395-5174 rebecca.rogers@sfcollege.edu
State of Florida Department of Juvenile Justice Multple Continuing Services Projects	\$843,867	varies by project	State of Florida Department of Juvenile Justice - Robert Bass (850) 717-2756 Robert.bass@djj.state.fl.us
Clay County District Schools Keystone Heights Elementary School New Cafetetorium and Classrooms	\$22,000,000	90%	Clay County District Schools - Bryce Ellis (904) 336-6853 bryce.ellis@myoneclay.net
School Board of Alachua County Westwood Middle School Redesign and Redevelopment	\$30,000,000	20%	School Board of Alachua County - Richard Rucker (352) 318-6603 ruckerrl@gm.sbac.edu
Marion County Public Schools New Central Warehouse	\$7,501,578	10%	Marion County Public Schools - Robert Knight (352) 671-6903 Robert.Knight@marion.kl2.fl.us
Oak Hall School New Learning and Enrichment Center	\$3,343,721	10%	Oak Hall School - Jeff Malloy (352) 332-3609 jmalloy@oakhall.org
Alachua County Fire Station #80	\$5,935,276	60%	Alachua County Purchasing - Ramon Gavarrett (352) 374-5202 rgavarrete@alachuacounty.us
Radiant Credit Union New Lake City Branch	\$2,800,000	85%	Radiant Credit Union - Kelly Chesser (386) 462-3151 kelly@sunstatefcu.org
Clay County Department of Health-Flemming Island New Office Build Out	\$5,800,000	25%	Clay County - Gene R. Price (904) 529-4108 Gene.Price@ClayCountyGov.com
Clay County District Schools Bannerman Learning Center Site Work and Parking Renovation	\$800,000	10%	Clay County District Schools - Bryce Ellis (904) 336-6853 bryce.ellis@myoneclay.net
City of Tavares New Public Works Complex	\$19,300,000	10%	City of Tavares - John Rumble (352) 742-6209 jrumble@tavares.org
City of Brooksville New Public Works Facility	\$3,600,000	0%	City of Brooksville -Ron Snowberger (352) 540-3810 rsnowberger@cityofbrooksville.us
City of Fruitland Park New Public Safety Facility	\$9,200,000	0%	City of Fruitland Park - Gary LaVenia (352) 360-6727 glavenia@fruitlandpark.org
City of Newberry New City Hall	\$5,000,000	0%	City of Newberry - Mike New MNew@NewberryFL.gov



SCORPIO COMPLETED PROJECT LIST 2018 - TO DATE

Scorpio Completed Projects List 2018 - 2023								
		alue of Work	Date		B.			
Market and Project Name	-	Performed	Completed	Contact Name	Phone			
CIVIC								
City of Gainesville and Trimark 9th St Urban Walkway	\$	1,829,625	3/5/2018	Bryan Harrington	(352) 376-6223			
District 8 New Medical Examiners Office	\$	2,021,335	9/28/2018	Ricardo Camacho	(352) 627-2217			
City of Gainesville Pavement Project	\$	1,121,236	7/23/2019	Jeff Norman	(352) 393-5115			
City of Gainesville CRA GTEC Renovation	\$	276,519	2/19/2021	Mo Deel	(352)393-8200			
City of Wildwood New Municipal Services Bldg.	\$	3,680,956	4/31/2023	Jeremy Hockenbury	(352)330-1343			
EDUCATION								
UF VetMed Parking Lot	\$	895,162	1/29/2018	Francisco Oquendo	(352) 273-4012			
UF Vet Med Bldg 217 Renovation	\$	1,372,313	3/20/2018	Francisco Oquendo	(352) 273-4012			
SFC International Student Center	\$	547,643	4/13/2018	Rebecca Rogers	(352) 395-5174			
UF Clinical and Translational Research Building	\$	269,224	5/5/2018	Francisco Oquendo	(352) 273-4012			
SFC New Police Station	\$	931,389	5/31/2018	Rebecca Rogers	(352) 395-5174			
UF 603 Reitz Union CRC Addition	\$	6,945,512	7/2/2018	Cydney McGlothlin	(352) 393-3174			
SFC Classroom Renovation	\$	294,525	7/15/2018	Rebecca Rogers	(352) 395-5174			
SBAC Buchholz HS Chiller Replacemnt	\$	351,389	8/2/2018	Richard Rucker				
UF-221 Norman Hall Library Renovation	\$			Frank Javaheri	(352) 318-6603			
UF Architecture Bldg Renovations	\$	2,504,452 474,856	8/17/2018 8/27/2018	Mark Humbert	(352) 273-4027 (352) 273-4014			
SFC Blgd.A-B Transformers	\$,			
UF Gamma Phi Beta New Sorority House	\$	368,791	11/6/2018	Rebecca Rogers	(352) 395-5174			
UF BSB Lab Renovation II	_	7,038,451	11/10/2018 11/21/2018	Woody Ratterman	(303) 799-1874			
UF Whitney Lab Research Village	\$	439,258	<u> </u>	Francisco Oquendo	(352) 273-4012			
,	\$	1,571,673	11/28/2018	Francisco Oquendo	(352) 273-4012			
UF Business Affairs Renovation	\$	982,592	11/30/2018	Mark Humbert	(352) 273-4014			
UF Comm Basement FA Upgrade	\$	394,471	12/10/2018	Scott Whiddon	(352) 273-4031			
UF UAA Katie Seashole Stadium Expansion/ Renovation	\$	9,383,928	1/24/2019	Bill Smith	(352) 273-4030			
UF MBI Ground Floor Renovation	\$	1,191,676	5/28/2019	Robert Hatker	(352) 273-4000			
UF Reitz Union Auditorium Renovation	\$	1,578,725	6/11/2019	Francisco Oquendo	(352) 273-4012			
UF Holland Law Renovation	\$	383,828	6/14/2019	Francisco Oquendo	(352) 273-4012			
SFC Learning Commons Renovation	\$	1,037,597	7/8/2019	Rebecca Rogers	(352) 395-5174			
UF Delta Gamma New Sorority House	\$	7,933,424	7/15/2019	Susan Scannella	(904) 233-0787			
UF Reitz Legal Services Renovations	\$	222,706	7/15/2019	Francisco Oquendo	(352) 273-4012			
UF Human Resource Services Building Renovation	\$	1,854,666	8/7/2019	Robert Hatker	(352) 273-4000			
UF HUB Academic Tech Renovation	\$	246,214	8/19/2019	Francisco Oquendo	(352) 273-4012			
UF UAA BHG Stadium Seating Renovation	\$	314,500	8/30/2019	Bill Smith	(352) 273-4030			
SBAC Stephen F. Parking Lot	\$	236,143	9/23/2019	Richard Rucker	(352) 318-6603			
UF-615 SS#2 Cable & Switchgear Replacement	\$	4,063,171	12/2/2019	Tom Feather	(352) 273-4681			
UF Ayers Medical Plaza Renovations	\$	499,607	12/4/2019	Robert Hatker	(352) 273-4000			
SFC Bldg S Student Healthcare Renovation	\$	238,306	2/7/2020	Rebecca Rogers	(352) 395-5174			
UF Peabody 3rd Floor Renovation	\$	429,022	4/10/2020	Marie Brown	(352) 273-4000			
Clay County District Schools KHS Site Improvements	\$	498,619	4/14/2020	David Kramer	(904) 336-6849			
UF Alpha Delta Pi New Sorority House	\$	8,981,674	7/1/2020	Lohse Beeland	(352) 375-7436			
UF Turlington Firehouse & JJ Renovations	\$	329,911	8/7/2020	Francisco Oquendo	(352) 273-4012			
UF-221 Norman Hall Expansion/Renovation	\$	24,877,864	8/7/2020	Keith Humphreys	(352) 273-1479			
SBAC Irby Elem Roof & HVAC	\$	781,344	8/10/2020	Richard Rucker	(352) 318-6603			
SBAC New Transition School	\$	3,981,181	8/17/2020	Richard Rucker	(352) 318-6603			
SFC Building B West Classrooms Renovations	\$	230,115	10/6/2020	Rebecca Rogers	(352) 395-5174			
UF College of Nursing Lab Renovation	\$	1,358,114	10/16/2020	Anna Suggs Hoffman	(352) 273-6395			
SBAC BHS Roof/HVAC Bldg 05 Renovation	\$	1,287,206	10/20/2020	Richard Rucker	(352) 318-6603			
UF Whitney Lab Cistern & FG Renovation	\$	435,041	3/22/2021	Francisco Oquendo	(352) 273-4012			
SBAC SFHS Auditorium Renovation	\$	1,071,933	4/1/2021	Dennis Griffith	(352) 955-7400			
UF 649 BSB 1st Floor Renovation	\$	3,848,725	6/10/2021	Robert Hatker	(352) 273-4000			



SCORPIO COMPLETED PROJECT LIST 2018 - TO DATE

### DECATION CONTINUED UF MSB 4-440 Lab Renovation \$ 1,095,203 6/14/2021 Gordon Burnham (352) 273 MCSB Osceola Middle School New Cafeteria \$ 4,292,219 7/16/2021 Robert Knight (352) 273 MCSB Osceola Middle School New Cafeteria \$ 4,292,219 7/16/2021 Robert Knight (352) 273 SBAC Howard Bishop Middle School Redesign and Redevelopment \$ 29,168,496 7/30/2021 Suzanne Wynn (352) 273 SBAC Howard Bishop Middle School Redesign and Redevelopment \$ 29,168,496 7/30/2021 Suzanne Wynn (352) 273 UF New Alpha Gamma Rho Fraternity House \$ 6,345,805 8/20/2021 Francisco Oquendo (352) 273 UF MSB M-240 Lab Renovation \$ 632,010 10/22/2021 Francisco Oquendo (352) 273 UF MSB M-240 Lab Renovation \$ 3,158,395 3/14/2022 Marie Brown (352) 273 UF Peabody Hall Dean of Students Renovation \$ 3,158,395 3/14/2022 Marie Brown (352) 273 MCP3 - Liberty MS Fuel Tank \$ 303,391 5/9/2022 Robert Knight (352) 673 UF WBI L5-135 Renovation \$ 1,017,858 \$5/12/2022 Gordon Burnham (352) 273 UF WBI L5-135 Renovation \$ 972,166 6/1/2022 Robert Bass (850) 717 UF WBI L5-135 Renovation \$ 972,166 6/1/2022 Robert Bass (850) 717 UF WBI L5-135 Renovation \$ 1,427,000 8/1/2022 Richard Rucker (352) 318 UF WBI			alue of Work	Date Completed	Contact Name	Phone
UF MSB 4-440 Lab Renovation	Market and Project Name	Performed				
UF MSB 4-440 Lab Renovation						
MCSB Oscoola Middle School New Cafeteria \$ 4,292,219 7/15/2021 Robert Knight (352) 671 UF Chick-Fil-A at Sun Terrace Renovation \$ 29,177 7/21/2021 Greg Roberts (352) 294 SBAC Howard Bishop Middle School Redesign and Redevelopment \$ 29,168,496 7/30/2021 Suzranne Wynn (352) 295 UF New Alpha Gamma Rho Fraternity House \$ 6345,805 8/20/2021 Mark Humbert (352) 273 UF MSB M-240 Lab Renovation \$ 632,010 10/22/2021 Francisco Oquendo (352) 273 UF GAZC-SW Campus Transportation Improvements \$ 341,384 1/21/2022 Francisco Oquendo (352) 273 UF GAZC-SW Campus Transportation Improvements \$ 341,384 1/21/2022 Robert Knight (352) 273 UF GAZC-SW Campus Transportation Improvements \$ 341,384 1/21/2022 Robert Knight (352) 273 MCPS - Liberty MS Fuel Tank \$ 303,391 5/9/2022 Robert Knight (352) 273 MCPS - Liberty MS Fuel Tank \$ 1,017,858 5/12/2022 Robert Knight (352) 273 MCPS - Liberty MS Fuel Tank \$ 1,017,858 5/12/2022 Robert Knight			4 005 303	6/44/2024	Control Dominion	(252) 272 4000
UF Chick-Fil-A at Sun Terrace Renovation		_				(352) 273-4009
SBAC Howard Bishop Middle School Redesign and Redevelopment S 29,168,496 7/30/2021 Suzanne Wynn (352) 955 S0 New Alpha Gamma Rho Fraternity House S 6,345,805 8/20/2021 Mark Humbert (352) 273 SUE MSB M-240 Lab Renovation S 632,010 10/22/2021 Francisco Oquendo (352) 273 UF MSB M-240 Lab Renovation S 341,384 1/21/2022 Mark Humbert (352) 273 UF Peabody Hall Dean of Students Renovation S 3,158,395 3/14/2022 Marie Brown (352) 273 MCPS - Liberty MS Fuel Tank S 303,391 S/9/2022 Robert Knight (352) 673 MCPS - Liberty MS Fuel Tank S 303,391 S/9/2022 Robert Bass (850) 717 Cank Hall School New Guard House S 10,17,885 S/12/2022 Gordon Burnham (352) 273 Gordon Burnham (352)		_				(352) 671-6903
Redevelopment \$ 29,168,496		\$	292,717	7/21/2021	Greg Roberts	(352) 294-3574
UF New Alpha Gamma Rho Fraternity House \$ 6,345,805 8/20/2021 Mark Humbert (352) 273 UF MSB M-240 Lab Renovation \$ 632,010 10/22/2021 Francisco Oquendo (352) 273 UF MSB M-240 Lab Renovation \$ 341,384 1/21/2022 Francisco Oquendo (352) 273 UF Peabody Hall Dean of Students Renovation \$ 31,58,395 3/14/2022 Marie Brown (352) 273 MCP3 - Liberty MS Fuel Tank \$ 303,391 5/9/2022 Robert Knight (352) 273 MCP3 - Liberty MS Fuel Tank \$ 303,391 5/1/2022 Gordon Burnham (352) 273 DJI Redwood Youth Center Renovations \$ 972,166 6/1/2022 Robert Bass (850) 717 Clay County Public Schools KHES Playground/Court \$ 489,308 8/1/2022 Richard Rucker (352) 338 Clay County Public Schools KHES Playground/Court \$ 889,398 8/31/2022 Bill Smith (352) 273 UF-357 CTRB 1st /2nd Floor Renowation \$ 1,427,000 3/30/2023 Reith Humphreys (352) 273 UF-357 CTRB 1st /2nd Floor Renovation \$ 1,000,397 2/23/2018 John Gerhold (352) 333	,					
UF MSB M-240 Lab Renovation \$ 632,010 10/22/2021 Francisco Oquendo (352) 273 UF 642C-SW Campus Transportation Improvements \$ 341,384 1/21/2022 Frank Javehari (352) 273 MCPS - Liberty MS Fuel Tank \$ 303,391 5/9/2022 Robert Knight (352) 671 MCPS - Liberty MS Fuel Tank \$ 303,391 5/9/2022 Robert Knight (352) 671 DJR Redwood Youth Center Renovation \$ 1,017,858 5/12/2022 Rodord Burnham (352) 273 Oak Hall School New Guard House \$ 419,305 8/1/2022 Jeff Malloy (352) 331 SAC CAT 2-3 EHS Band-Chorus Renovation \$ 407,180 8/1/2022 Richard Rucker (352) 318 Clay County Public Schools KHES Playground/Court \$ 889,398 8/31/2022 Mike Griffis (904) 336 UF JAS New Student Heasth Center \$ 19,780,000 3/2/2022 Bill Smith (352) 273 UF-357 CTRB 1st /2nd Floor Renovation \$ 1,884,839 4/4/2023 Keith Humphreys (352) 233 UF-357 CTRB 1st /2nd Floor Renovation \$ 1,000,397 2/2/3/2018 John Gerhold (352) 333	<u> </u>	_				(352) 955-7760
UF Peabody Hall Dean of Students Renovation \$ 341,384 1/21/2022 Frank Javehari (352) 273		_				(352) 273-4014
UF Peabody Hall Dean of Students Renovation \$ 3,158,395 3/14/2022 Marie Brown (352) 273 MCPS - Liberty MS Fuel Tank \$ 303,391 5/9/2022 Robert Knight (352) 671 UF MBI LS-138 Renovation \$ 1,017,888 5/12/2022 Gordon Burnham (352) 671 UF MBI LS-138 Renovation \$ 1,017,888 5/12/2022 Robert Rnight (352) 671 UF MBI LS-138 Renovation \$ 1,071,702 Robert Bass (850) 717 Oak Hall School New Guard House \$ 419,305 8/1/2022 Jeff Malloy (352) 332 SBAC CAT 2-3 Eth S Band-Chorus Renovation \$ 407,180 8/1/2022 Jeff Malloy (352) 332 RSAC CAT 2-3 Eth S Band-Chorus Renovation \$ 407,180 8/1/2022 Mike Griffis (904) 336 LIP UAA M 3 -Swim Dive Locker Room Renovation \$ 1,427,000 9/2/2022 Mike Griffis (904) 336 UF UAA M 3 -Swim Dive Locker Room Renovation \$ 1,427,000 9/2/2022 Mike Griffis (904) 336 UF UAA M 3 -Swim Dive Locker Room Renovation \$ 1,827,000 9/2/2022 Mike Griffis (904) 336 UF UAA M 3 -Swim Dive Locker Room Renovation \$ 1,884,839 4/4/2023 Keith Humphreys (352) 273 UF -357 CTRB 1st /2nd Floor Renovation \$ 1,884,839 4/4/2023 Keith Humphreys (352) 273 UF -357 CTRB 1st /2nd Floor Renovation \$ 1,000,397 2/23/2018 Jeff Garcia (352) 955 HEALTHCARE HAC Florida Emergency Room Renovation \$ 1,000,397 2/23/2018 John Gerhold (352) 333 HCA Florida Emergency Room Renovation \$ 544,525 5/31/2022 John Gerhold (352) 333 HCA Florida Phase 1 Renovation \$ 544,525 5/31/2022 John Gerhold (352) 333 HCA Florida 2Nd Phase 1 Renovation \$ 2,271,180 2/28/2020 John Gerhold (352) 333 HCA Florida 2Nd Phase 3 Renovation \$ 2,271,180 2/28/2020 John Gerhold (352) 333 HCA Florida 2Nd Phase 3 Renovation \$ 2,333,437 2/14/2020 John Gerhold (352) 333 HCA Florida 2Nd Phase 3 Renovation \$ 2,333 4/2022 John Gerhold (352) 333 HCA Florida 2Nd Phase 3 Renovation \$ 38,494 4/23/2022 John Gerhold (352) 333 HCA Florida 2Nd Phase 3 Renovation \$ 38,494 4/23/2022 John Gerhold (352) 333 HCA Florida 2Nd Phase 3 Renovation \$ 3,34,307 10/28/2022 John Gerhold (352) 333 HCA Florida 2Nd Flore Renovation \$ 3,34,307 10/28/2022 John Gerhold (352) 333 HCA Florida 2Nd Flore Renovation \$ 5,34,35	**	_	-		· · · · · · · · · · · · · · · · · · ·	(352) 273-4012
MCPS - Liberty MS Fuel Tank		-	-			(352) 273-4000
UF MBI LS-135 Renovation	<u> </u>	_				(352) 273-4000
DJJ Redwood Youth Center Renovations	· · · · · · · · · · · · · · · · · · ·	_			U	(352) 671-6903
Oak Hall School New Guard House \$ 419,305 8/1/2022 Jeff Malloy (352)332-88AC CAT 2-3 EHS Band-Chorus Renovation \$ 407,180 8/1/2022 Jief Malloy (352)332-88AC CAT 2-3 EHS Band-Chorus Renovation \$ 889,398 8/31/2022 Mike Griffis (904) 336 UF UAA M 3 - Swim Dive Locker Room Renovation \$ 1,427,000 9/2/2022 Bill Smith (352) 273 UF-638 New Student Heath Center \$ 19,780,000 3/30/2023 Keith Humphreys (352) 273 UF-638 New Student Heath Center \$ 19,780,000 3/30/2023 Keith Humphreys (352) 273 SBAC Sivia Center Renovation \$ 1,884,839 4/4/2023 Keith Humphreys (352) 273 SBAC Sivia Center Renovation \$ 1,000,397 2/23/2018 John Gerhold (352) 333 HCA Florida Emergency Room Renovation \$ 1,000,397 2/23/2018 John Gerhold (352) 333 HCA Florida 2N Phase 1 Renovation \$ 544,525 5/31/2022 John Gerhold (352) 333 HCA Florida 2nd Floor 19-Bed Obs Renovation \$ 2,271,180 2/28/2020 John Gerhold (352) 333 HCA Florida 2nd Floor 19-Bed Obs Renovation \$ 20,5		_				(352) 273-4009
SBAC CAT 2-3 EHS Band-Chorus Renovation \$ 407,180 8/1/2022 Richard Rucker (352) 318						(850) 717-2756
Clay County Public Schools KHES Playground/Court \$889,398 8/31/2022 Mike Griffis (904) 336 UF UAA M 3 - Swim Dive Locker Room Renovation \$1,427,000 9/2/2022 Bill Smith (352) 273						(352)332-3609
UF UAA M 3 - Swim Dive Locker Room Renovation \$ 1,427,000 9/2/2022 Bill Smith (352) 273 UF-638 New Student Heath Center \$ 19,780,000 3/30/2023 Keith Humphreys (352) 273 UF-638 New Student Heath Center \$ 1,884,839 4/4/2023 Keith Humphreys (352) 273 SBAC Sivia Center Renovation \$ 816,332 5/10/2023 Jeff Garcia (352) 955 HEALTHCARE HCA Florida Emergency Room Renovation \$ 1,000,397 2/23/2018 John Gerhold (352) 333 HCA Florida 2N Phase 1 Renovation \$ 544,525 5/31/2022 John Gerhold (352) 333 HCA Florida Ambulance Canopy \$ 363,905 2/10/2109 John Gerhold (352) 333 HCA Florida Piorida Pior 19-Bed Obs Renovation \$ 1,337,437 2/144/2020 Ray Hopkins HCA Florida 2N Phase 3 Renovation \$ 20,85,07 5/27/2020 John Gerhold (352) 333 HCA Florida 2N Phase 3 Renovation \$ 996,213 3/4/2022 John Gerhold (352) 333 HCA Florida 2N Fl. Renovations \$ 1,627,819 \$ 7/30/2021 John Gerhold (352) 333		_				(352) 318-6603
UF-638 New Student Heath Center \$ 19,780,000 3/30/2023 Keith Humphreys (352) 273 UF-357 CTRB 1st /2nd Floor Renovation \$ 1,884,839 4/4/2023 Keith Humphreys (352) 273 SBAC Sivia Center Renovation \$ 816,332 5/10/2023 Jeff Garcia (352) 955 HEALTHCARE *** *** *** *** *** Jeff Garcia (352) 933 HCA Florida Emergency Room Renovation \$ 1,000,397 2/23/2018 John Gerhold (352) 333 HCA Florida 2N Phase 1 Renovation \$ 544,525 5/31/2022 John Gerhold (352) 333 HCA Florida Ambulance Canopy \$ 363,905 2/10/2109 John Gerhold (352) 333 HCA Florida 2nd Floor 19-Bed Obs Renovation \$ 1,337,437 2/14/2020 John Gerhold (352) 333 HCA Florida 2nd Floor Phase 3 Renovation \$ 2,271,180 2/28/2020 John Gerhold (352) 333 HCA Florida 2nd Flore Renovations \$ 996,213 3/4/2022 John Gerhold (352) 333 HCA Florida 5th La 5 Renovation \$ 987,428 6/10/2018 Rob Krakenburg (352) 333		_				(904) 336-6829
Second Processing Services Second Processing Second Processi						(352) 273-4030
SBAC Sivia Center Renovation S 816,332 5/10/2023 Jeff Garcia (352) 955						(352) 273-1479
HEALTHCARE HCA Florida Emergency Room Renovation \$ 1,000,397 2/23/2018 John Gerhold (352) 333 HCA Florida 2N Phase 1 Renovation \$ 544,525 5/31/2022 John Gerhold (352) 333 HCA Florida Ambulance Canopy \$ 363,905 2/10/2109 John Gerhold (352) 333 HCA ORMC Ozala Heart Renovation \$ 1,337,437 2/14/2020 Ray Hopkins HCA Florida 2N & 3N Nurse Stations Renovation \$ 2,271,180 2/28/2020 John Gerhold (352) 333 HCA Florida 2N & 3N Nurse Stations Renovation \$ 208,507 5/27/2020 John Gerhold (352) 333 HCA Florida 2N & 3N Nurse Stations Renovation \$ 338,494 4/23/2022 John Gerhold (352) 333 HCA Florida Cath Lab 5 Renovation \$ 996,213 3/4/2022 John Gerhold (352) 333 HCA Florida Cath Lab 5 Renovation \$ 2,959,011 5/1/2022 John Gerhold (352) 333 HCA Florida Cath Lab 6 Renovation \$ 3,413,307 10/28/2022 John Gerhold (352) 333 HCA Florida Cath Lab 6 Renovation \$ 987,428 6/10/2018 Rob Krakenburg (352) 333 HCA Florida Cath Lab 6 Renovation \$ 987,428 6/10/2018 Rob Krakenburg (352) 373 HCA Florida Cath Cascades Apartments \$ 11,237,603 7/30/2018 Bryan Harrington (352) 373 HCA Florida Cath Cascades Apartments \$ 5,192,855 8/16/2018 Reid Fogler (352) 374 HCA Florida Cath Cascades Apartments \$ 5,192,855 8/16/2018 Reid Fogler (352) 375 HCA Florida Cath Cascades Apartments \$ 5,192,855 8/16/2018 Reid Fogler (352) 375 HCA Florida Cascades Apartments \$ 5,192,855 8/16/2018 Reid Fogler (352) 375 HCA Florida Cascades Apartments \$ 5,192,855 8/16/2018 Reid Fogler (352) 375 HCA Florida Cascades Apartments \$ 5,192,855 8/16/2018 Reid Fogler (352) 375 HCA Florida Cascades Apartments \$ 5,192,855 8/16/2018 Reid Fogler (352) 375 HCA Florida Cascades Apartments \$ 5,192,855 8/16/2018 Reid Fogler (352) 375 HCA Florida Cascades Apartments \$ 5,192,855 8/16/2018 Reid Fogler (352) 375 HCA Florida Cascades Apartments \$ 5,192,855 8/16/2018 Reid Fogler (352) 375 HCA Florida Cascades Apartments \$ 5,192,855 8/16/2018 Reid Fogler (352) 375 HCA Florida Cascades Apartments \$ 5,192,855 8/16/2018 Reid Fogler (352) 375 HCA Florida Cascades Apartments \$ 5,192,855 8/16/2018 Reid Fog	,				' '	(352) 273-1479
HCA Florida Emergency Room Renovation \$ 1,000,397 2/23/2018 John Gerhold (352) 333 HCA Florida 2N Phase 1 Renovation \$ 544,525 5/31/2022 John Gerhold (352) 333 HCA Florida Ambulance Canopy \$ 363,905 2/10/2109 John Gerhold (352) 333 HCA Florida Ambulance Canopy \$ 363,905 2/10/2109 John Gerhold (352) 333 HCA Florida 2nd Floor 19-Bed Obs Renovation \$ 1,337,437 2/14/2020 John Gerhold (352) 333 HCA Florida 2nd Floor 19-Bed Obs Renovation \$ 2,271,180 2/28/2020 John Gerhold (352) 333 HCA Florida 2N & 3N Nurse Stations Renovation \$ 208,507 5/27/2020 John Gerhold (352) 333 HCA Florida 2N Phase 3 Renovation \$ 338,494 4/23/2022 John Gerhold (352) 333 HCA Florida Cath Lab 5 Renovation \$ 996,213 3/4/2022 John Gerhold (352) 333 HCA Florida 5th FL Renovations \$ 2,959,011 5/1/2022 John Gerhold (352) 333 HCA Florida 2nd Floor Renovations \$ 3,413,307 10/28/2022 John Gerhold (352) 333 HCA Florida 2nd Floor Renovations \$ 3,413,307 10/28/2022 John Gerhold (352) 333 HCA Florida 2nd Floor Renovations \$ 3,413,307 10/28/2022 John Gerhold (352) 333 HCA Florida 2nd Floor Renovations \$ 11,237,603 7/30/2018 Bryan Harrington (352) 376 Horizontal Cath Cath Cath Cath Cath Cath Cath Cath	SBAC Sivia Center Renovation	\$	816,332	5/10/2023	Jeff Garcia	(352) 955-7618
HCA Florida 2N Phase 1 Renovation	HEALTHCARE					
HCA Florida Ambulance Canopy	HCA Florida Emergency Room Renovation	\$	1,000,397	2/23/2018	John Gerhold	(352) 333-4160
HCA ORMC Ocala Heart Renovation \$ 1,337,437 2/14/2020 Ray Hopkins	HCA Florida 2N Phase 1 Renovation	\$	544,525	5/31/2022	John Gerhold	(352) 333-4160
HCA Florida 2nd Floor 19-Bed Obs Renovation \$ 2,271,180 2/28/2020 John Gerhold (352) 333 HCA Florida 2N & 3N Nurse Stations Renovation \$ 208,507 5/27/2020 John Gerhold (352) 333 HCA Florida 2N Phase 3 Renovation \$ 338,494 4/23/2022 John Gerhold (352) 333 HCA Florida 2N Phase 3 Renovation \$ 996,213 3/4/2022 John Gerhold (352) 333 HCA Florida Cath Lab 5 Renovations \$ 2,959,011 5/1/2022 John Gerhold (352) 333 HCA Florida 2nd Floor Renovations \$ 3,413,307 10/28/2022 John Gerhold (352) 333 HCA Florida 2nd Floor Renovations \$ 3,413,307 10/28/2022 John Gerhold (352) 333 HCA Florida 2nd Floor Renovations \$ 11,237,603 7/30/2018 Bryan Harrington (352) 376 Horizontal Cascades Apartments \$ 11,237,603 7/30/2018 Bryan Harrington (352) 376 Horizontal Cascades Apartments \$ 11,237,603 7/30/2018 Bryan Harrington (352) 376 Horizontal Cascades Apartments \$ 11,237,603 7/30/2018 Bryan Harrington (352) 376 Horizontal Cascades Apartments \$ 11,237,603 7/30/2018 Bryan Harrington (352) 376 Horizontal Cascades Apartments \$ 11,237,603 7/30/2018 Bryan Harrington (352) 376 Horizontal Cascades Apartments \$ 11,237,603 7/30/2018 Bryan Harrington (352) 376 Horizontal Cascades Apartments \$ 11,237,603 7/30/2018 Horizontal Cascades Apartments \$ 11,237,603 7/30/2018 Bryan Harrington (352) 375 Horizontal Cascades Apartments \$ 333,962 4/22/2019 Larry Goodall (386) 418 Horizontal Cascades Apartments \$ 1,627,189 4/17/2020 Jeannette Baer (352) 333 Horizontal Cascades Apartments \$ 1,627,189 4/17/2020 Horizontal Cascades Apartme	HCA Florida Ambulance Canopy	\$	363,905	2/10/2109	John Gerhold	(352) 333-4160
HCA Florida 2N & 3N Nurse Stations Renovation \$ 208,507 5/27/2020 John Gerhold (352) 333 HCA Florida 2N Phase 3 Renovation \$ 338,494 4/23/2022 John Gerhold (352) 333 HCA Florida Cath Lab 5 Renovation \$ 996,213 3/4/2022 John Gerhold (352) 333 HCA Florida 5th FL Renovations \$ 2,959,011 5/1/2022 John Gerhold (352) 333 HCA Florida 2nd Floor Renovations \$ 3,413,307 10/28/2022 John Gerhold (352) 333 HCA Florida 2nd Floor Renovations \$ 3,413,307 10/28/2022 John Gerhold (352) 333 HCA Florida 2nd Flo	HCA ORMC Ocala Heart Renovation	\$	1,337,437	2/14/2020	Ray Hopkins	
HCA Florida 2N Phase 3 Renovation \$ 338,494 4/23/2022 John Gerhold (352) 333 HCA Florida Cath Lab 5 Renovation \$ 996,213 3/4/2022 John Gerhold (352) 333 HCA Florida 5th FL Renovations \$ 2,959,011 5/1/2022 John Gerhold (352) 333 HCA Florida 2nd Floor Renovations \$ 3,413,307 10/28/2022 John Gerhold (352) 333 HCA Florida 2nd Floor Renovations \$ 3,413,307 10/28/2022 John Gerhold (352) 333 HCA Florida 2nd Floor Renovations \$ 3,413,307 10/28/2022 John Gerhold (352) 333 HCA Florida 2nd Floor Renovations \$ 987,428 6/10/2018 Rob Krakenburg (352) 373 HCA Florida 2nd Floor Renovation \$ 987,428 6/10/2018 Rob Krakenburg (352) 373 HCA Florida 2nd Floor Renovation \$ 987,428 6/10/2018 Rob Krakenburg (352) 373 HCA Florida 2nd Floor Renovation \$ 987,428 6/10/2018 Rob Krakenburg (352) 373 HCA Florida 2nd Floor Renovation \$ 11,237,603 7/30/2018 Bryan Harrington (352) 376 HCA Florida 2nd Floor Renovation \$ 332,389 10/1/2018 Rob Krakenburg (352) 376 HCA Florida 2nd Floor Renovation \$ 332,389 10/1/2018 Rob Krakenburg (352) 375 HCA Florida 2nd Floor Renovation \$ 333,3962 4/22/2019 Larry Goodall (386) 418 HCA Florida 2nd Floor Renovation \$ 1,627,189 4/17/2020 Helanie Shore (352) 333 HCA Florida 2nd Floor Renovation \$ 886,778 9/14/2020 Melanie Shore (352) 375 HCA Florida 2nd Floor Renovation \$ 1,809,208 2/1/2021 Lynn Noffsinger (352) 375 HCA Florida 2nd Floor Renovation \$ 1,809,208 2/1/2021 Lynn Noffsinger (352) 375 HCA Florida 2nd Floor Renovation \$ 1,809,208 2/1/2021 Lynn Noffsinger (352) 375 HCA Florida 2nd Floor Renovation \$ 1,809,208 2/1/2021 Lynn Noffsinger (352) 375 HCA Florida 2nd Floor Renovation \$ 1,809,208 2/1/2021 Lynn Noffsinger (352) 375 HCA Florida 2nd Floor Renovation \$ 1,809,208 2/1/2021 Rob Renovation (352) 375 HCA Florida 2nd Floor Renovation \$ 3,390,889	HCA Florida 2nd Floor 19-Bed Obs Renovation	\$	2,271,180	2/28/2020	John Gerhold	(352) 333-4160
HCA Florida Cath Lab 5 Renovation \$ 996,213 3/4/2022 John Gerhold (352) 333 HCA Florida 5th FL Renovations \$ 2,959,011 5/1/2022 John Gerhold (352) 333 HCA Florida 2nd Floor Renovations \$ 3,413,307 10/28/2022 John Gerhold (352) 333 HCA Florida 2nd Floor Renovations \$ 3,413,307 10/28/2022 John Gerhold (352) 333 HCA Florida 2nd Floor Renovations \$ 3,413,307 10/28/2022 John Gerhold (352) 333 HCA Florida 2nd Flo	HCA Florida 2N & 3N Nurse Stations Renovation	\$	208,507	5/27/2020	John Gerhold	(352) 333-4160
HCA Florida 5th FL Renovations \$ 2,959,011 5/1/2022 John Gerhold (352) 333 HCA Florida 2nd Floor Renovations \$ 3,413,307 10/28/2022 John Gerhold (352) 333 HCA Florida 2nd Floor Renovations \$ 3,413,307 10/28/2022 John Gerhold (352) 333 HCA Florida 2nd Floor Renovation \$ 987,428 6/10/2018 Rob Krakenburg (352) 378-75 Rel Station \$ 987,428 6/10/2018 Bryan Harrington (352) 378-75 Rel Station \$ 11,237,603 7/30/2018 Bryan Harrington (352) 376 Reid Fogler (352) 576 Reid Fogler (352) 576 Reid Fogler (352) 576 Reid Fogler (352) 576 Reid Fogler (352) 378-75 Reid Fogler (352) 378-75 Reid Fogler (352) 378-75 Reid Fogler (352) 379 Reid Fogler (352) 3	HCA Florida 2N Phase 3 Renovation	\$	338,494	4/23/2022	John Gerhold	(352) 333-4160
COMMERCIAL/PRIVATE S 987,428 6/10/2018 Rob Krakenburg (352) 378- Trimark Cascades Apartments \$ 11,237,603 7/30/2018 Bryan Harrington (352) 376- Woodbury Apartments \$ 5,192,855 8/16/2018 Reid Fogler (352) 376- Woodbury Apartments \$ 5,192,855 8/16/2018 Reid Fogler (352) 514- Koss Olinger Office Renovation \$ 332,389 10/1/2018 Will Olinger III (352) 373- RTI BioPac Renovations \$ 333,962 4/22/2019 Larry Goodall (386) 418- Frankel Media Group New Corporate Office \$ 793,883 3/31/2020 Jeannette Baer (352) 331- Sharp Spring New Corporate Office \$ 1,627,189 4/17/2020 Bill Varner (352) 375- Seacoast Bank Building (Formerly Drummond Bank) \$ 4,942,570 7/24/2020 Melanie Shore (352) 375- Selow Gainesville Plaza \$ 886,778 9/14/2020 Melanie Shore (352) 375- Gainesville Airport Hangar Renovation \$ 1,809,208 2/1/2021 Lynn Noffsinger (352) 373- Radiant CU-Live Oak Renovation \$ 2,503,809 9/30/2021 Kelly Chesser (386) 462- Pressure Technology Warehouse \$ 3,390,889 3/2/20/2021 David Bowles (215) 628- Gainesville High Field MRI Renovation \$ 613,314 1/17/2022 Tom Brown (404) 434- Radiant CU - Chiefland Renovation \$ 463,147 8/18/2022 Relly Chesser (386) 462- The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376-	HCA Florida Cath Lab 5 Renovation	\$	996,213	3/4/2022	John Gerhold	(352) 333-4160
COMMERCIAL/PRIVATE PFG Fuel Station \$ 987,428 6/10/2018 Rob Krakenburg (352)378- Trimark Cascades Apartments \$ 11,237,603 7/30/2018 Bryan Harrington (352) 376 Woodbury Apartments \$ 5,192,855 8/16/2018 Reid Fogler (352) 514 Koss Olinger Office Renovation \$ 332,389 10/1/2018 Will Olinger III (352) 373 RTI BioPac Renovations \$ 333,3962 4/22/2019 Larry Goodall (386) 418 Frankel Media Group New Corporate Office \$ 793,883 3/31/2020 Jeannette Baer (352) 331 Sharp Spring New Corporate Office \$ 1,627,189 4/17/2020 Bill Varner (352) 333 Seacoast Bank Building (Formerly Drummond Bank) \$ 4,942,570 7/24/2020 Melanie Shore (352) 375 Seacoast Bank 37th Blvd Improvements \$ 504,007 7/24/2020 Melanie Shore (352) 375 Gainesville Airport Hangar Renovation \$ 1,809,208 2/1/2021 Lynn Noffsinger (352) 375 Radiant CU-Live Oak Renovation \$ 557,788 4/16/2021 Kelly Chesser (386) 462 Radiant CU Operations Bldg \$ 2,503,809 9/30/2021 Kelly Chesser (386) 462 Pressure Technology Warehouse \$ 3,390,889 12/20/2021 David Bowles (215) 628 Gainesville High Field MRI Renovation \$ 463,147 8/18/2022 Kelly Chesser (386) 462 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376	HCA Florida 5th FL Renovations	\$	2,959,011	5/1/2022	John Gerhold	(352) 333-4160
PFG Fuel Station \$ 987,428 6/10/2018 Rob Krakenburg (352)378-Trimark Cascades Apartments \$ 11,237,603 7/30/2018 Bryan Harrington (352) 376 Woodbury Apartments \$ 5,192,855 8/16/2018 Reid Fogler (352) 514 Koss Olinger Office Renovation \$ 332,389 10/1/2018 Will Olinger III (352) 373 RTI BioPac Renovations \$ 333,962 4/22/2019 Larry Goodall (386) 418 Frankel Media Group New Corporate Office \$ 793,883 3/31/2020 Jeannette Baer (352) 331 Sharp Spring New Corporate Office \$ 1,627,189 4/17/2020 Bill Varner (352) 333 Seacoast Bank Building (Formerly Drummond Bank) \$ 4,942,570 7/24/2020 Melanie Shore (352) 375 Seacoast Bank 37th Blvd Improvements \$ 886,778 9/14/2020 Matt Reilly (334) 399 Seacoast Bank 37th Blvd Improvements \$ 504,007 12/28/2020 Melanie Shore (352) 375 Gainesville Airport Hangar Renovation \$ 1,809,208 2/1/2021 Lynn Noffsinger (352) 375 Radiant CU-Live Oak Renovation \$ 557,788 4/16/2021 Kelly Chesser (386) 462 Rediant CU Operations Bldg \$ 2,503,809 9/30/2021 Kelly Chesser (386) 462 Pressure Technology Warehouse \$ 3,390,889 12/20/2021 David Bowles (215) 628 Gainesville High Field MRI Renovation \$ 613,314 1/17/2022 Tom Brown (404) 434 Radiant CU - Chiefland Renovation \$ 463,147 8/18/2022 Kelly Chesser (386) 462 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harring	HCA Florida 2nd Floor Renovations	\$	3,413,307	10/28/2022	John Gerhold	(352) 333-4160
PFG Fuel Station \$ 987,428 6/10/2018 Rob Krakenburg (352)378-Trimark Cascades Apartments \$ 11,237,603 7/30/2018 Bryan Harrington (352) 376 Woodbury Apartments \$ 5,192,855 8/16/2018 Reid Fogler (352) 514 Koss Olinger Office Renovation \$ 332,389 10/1/2018 Will Olinger III (352) 373 RTI BioPac Renovations \$ 333,962 4/22/2019 Larry Goodall (386) 418 Frankel Media Group New Corporate Office \$ 793,883 3/31/2020 Jeannette Baer (352) 331 Sharp Spring New Corporate Office \$ 1,627,189 4/17/2020 Bill Varner (352) 333 Seacoast Bank Building (Formerly Drummond Bank) \$ 4,942,570 7/24/2020 Melanie Shore (352) 375 Seacoast Bank 37th Blvd Improvements \$ 886,778 9/14/2020 Matt Reilly (334) 399 Seacoast Bank 37th Blvd Improvements \$ 504,007 12/28/2020 Melanie Shore (352) 375 Gainesville Airport Hangar Renovation \$ 1,809,208 2/1/2021 Lynn Noffsinger (352) 375 Radiant CU-Live Oak Renovation \$ 557,788 4/16/2021 Kelly Chesser (386) 462 Rediant CU Operations Bldg \$ 2,503,809 9/30/2021 Kelly Chesser (386) 462 Pressure Technology Warehouse \$ 3,390,889 12/20/2021 David Bowles (215) 628 Gainesville High Field MRI Renovation \$ 613,314 1/17/2022 Tom Brown (404) 434 Radiant CU - Chiefland Renovation \$ 463,147 8/18/2022 Kelly Chesser (386) 462 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harring	COMMERCIAL /PRIVATE					
Trimark Cascades Apartments \$ 11,237,603 7/30/2018 Bryan Harrington (352) 376		Ś	987.428	6/10/2018	Rob Krakenburg	(352)378-8844
Woodbury Apartments \$ 5,192,855 8/16/2018 Reid Fogler (352) 514 Koss Olinger Office Renovation \$ 332,389 10/1/2018 Will Olinger III (352) 373 RTI BioPac Renovations \$ 333,962 4/22/2019 Larry Goodall (386) 418 Frankel Media Group New Corporate Office \$ 793,883 3/31/2020 Jeannette Baer (352) 331 Sharp Spring New Corporate Office \$ 1,627,189 4/17/2020 Bill Varner (352) 333 Seacoast Bank Building (Formerly Drummond Bank) \$ 4,942,570 7/24/2020 Melanie Shore (352) 375 5 Below Gainesville Plaza \$ 886,778 9/14/2020 Matt Reilly (334) 399 Seacoast Bank 37th Blvd Improvements \$ 504,007 12/28/2020 Melanie Shore (352) 375 Gainesville Airport Hangar Renovation \$ 1,809,208 2/1/2021 Lynn Noffsinger (352) 373 Radiant CU-Live Oak Renovation \$ 557,788 4/16/2021 Kelly Chesser (386) 462 Pressure Technology Warehouse \$ 3,390,889 12/20/2021 David Bowles (215) 628 Gainesville High Field MRI	Trimark Cascades Apartments					(352) 376-6223
Koss Olinger Office Renovation \$ 332,389 10/1/2018 Will Olinger III (352) 373 RTI BioPac Renovations \$ 333,962 4/22/2019 Larry Goodall (386) 418 Frankel Media Group New Corporate Office \$ 793,883 3/31/2020 Jeannette Baer (352) 331 Sharp Spring New Corporate Office \$ 1,627,189 4/17/2020 Bill Varner (352) 333 Seacoast Bank Building (Formerly Drummond Bank) \$ 4,942,570 7/24/2020 Melanie Shore (352) 375 5 Below Gainesville Plaza \$ 886,778 9/14/2020 Matt Reilly (334) 399 Seacoast Bank 37th Blvd Improvements \$ 504,007 12/28/2020 Melanie Shore (352) 375 Gainesville Airport Hangar Renovation \$ 1,809,208 2/1/2021 Lynn Noffsinger (352) 373 Radiant CU-Live Oak Renovation \$ 557,788 4/16/2021 Kelly Chesser (386) 462 Pressure Technology Warehouse \$ 3,390,889 12/20/2021 David Bowles (215) 628 Gainesville High Field MRI Renovation \$ 613,314 1/17/2022 Tom Brown (404) 434 Radiant CU -	•					(352) 514-5128
RTI BioPac Renovations \$ 333,962 4/22/2019 Larry Goodall (386) 418 Frankel Media Group New Corporate Office \$ 793,883 3/31/2020 Jeannette Baer (352) 331 Sharp Spring New Corporate Office \$ 1,627,189 4/17/2020 Bill Varner (352) 333 Seacoast Bank Building (Formerly Drummond Bank) \$ 4,942,570 7/24/2020 Melanie Shore (352) 375 5 Below Gainesville Plaza \$ 886,778 9/14/2020 Matt Reilly (334) 399 Seacoast Bank 37th Blvd Improvements \$ 504,007 12/28/2020 Melanie Shore (352) 375 Gainesville Airport Hangar Renovation \$ 1,809,208 2/1/2021 Lynn Noffsinger (352) 373 Radiant CU-Live Oak Renovation \$ 557,788 4/16/2021 Kelly Chesser (386) 462 Radiant CU Operations Bldg \$ 2,503,809 9/30/2021 Kelly Chesser (386) 462 Pressure Technology Warehouse \$ 3,390,889 12/20/2021 David Bowles (215) 628 Gainesville High Field MRI Renovation \$ 613,314 1/17/2022 Tom Brown (404) 434 Radiant CU - Chie	· · ·					(352) 373-3337
Frankel Media Group New Corporate Office \$ 793,883 3/31/2020 Jeannette Baer (352) 331 Sharp Spring New Corporate Office \$ 1,627,189 4/17/2020 Bill Varner (352) 333 Seacoast Bank Building (Formerly Drummond Bank) \$ 4,942,570 7/24/2020 Melanie Shore (352) 375 5 Below Gainesville Plaza \$ 886,778 9/14/2020 Matt Reilly (334) 399 Seacoast Bank 37th Blvd Improvements \$ 504,007 12/28/2020 Melanie Shore (352) 375 Gainesville Airport Hangar Renovation \$ 1,809,208 2/1/2021 Lynn Noffsinger (352) 373 Radiant CU-Live Oak Renovation \$ 557,788 4/16/2021 Kelly Chesser (386) 462 Radiant CU Operations Bldg \$ 2,503,809 9/30/2021 Kelly Chesser (386) 462 Pressure Technology Warehouse \$ 3,390,889 12/20/2021 David Bowles (215) 628 Gainesville High Field MRI Renovation \$ 613,314 1/17/2022 Tom Brown (404) 434 Radiant CU - Chiefland Renovation \$ 463,147 8/18/2022 Kelly Chesser (386) 462 The Ne	3	_				(386) 418-8888
Sharp Spring New Corporate Office \$ 1,627,189 4/17/2020 Bill Varner (352) 333 Seacoast Bank Building (Formerly Drummond Bank) \$ 4,942,570 7/24/2020 Melanie Shore (352) 375 5 Below Gainesville Plaza \$ 886,778 9/14/2020 Matt Reilly (334) 399 Seacoast Bank 37th Blvd Improvements \$ 504,007 12/28/2020 Melanie Shore (352) 375 Gainesville Airport Hangar Renovation \$ 1,809,208 2/1/2021 Lynn Noffsinger (352) 373 Radiant CU-Live Oak Renovation \$ 557,788 4/16/2021 Kelly Chesser (386) 462 Radiant CU Operations Bldg \$ 2,503,809 9/30/2021 Kelly Chesser (386) 462 Pressure Technology Warehouse \$ 3,390,889 12/20/2021 David Bowles (215) 628 Gainesville High Field MRI Renovation \$ 613,314 1/17/2022 Tom Brown (404) 434 Radiant CU - Chiefland Renovation \$ 463,147 8/18/2022 Kelly Chesser (386) 462 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376		_			· · · · · · · · · · · · · · · · · · ·	(352) 331-5558
Seacoast Bank Building (Formerly Drummond Bank) \$ 4,942,570 7/24/2020 Melanie Shore (352) 375 5 Below Gainesville Plaza \$ 886,778 9/14/2020 Matt Reilly (334) 399 Seacoast Bank 37th Blvd Improvements \$ 504,007 12/28/2020 Melanie Shore (352) 375 Gainesville Airport Hangar Renovation \$ 1,809,208 2/1/2021 Lynn Noffsinger (352) 373 Radiant CU-Live Oak Renovation \$ 557,788 4/16/2021 Kelly Chesser (386) 462 Radiant CU Operations Bldg \$ 2,503,809 9/30/2021 Kelly Chesser (386) 462 Pressure Technology Warehouse \$ 3,390,889 12/20/2021 David Bowles (215) 628 Gainesville High Field MRI Renovation \$ 613,314 1/17/2022 Tom Brown (404) 434 Radiant CU - Chiefland Renovation \$ 463,147 8/18/2022 Kelly Chesser (386) 462 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376		<u> </u>				(352) 333-9333
5 Below Gainesville Plaza \$ 886,778 9/14/2020 Matt Reilly (334) 399 Seacoast Bank 37th Blvd Improvements \$ 504,007 12/28/2020 Melanie Shore (352) 375 Gainesville Airport Hangar Renovation \$ 1,809,208 2/1/2021 Lynn Noffsinger (352) 373 Radiant CU-Live Oak Renovation \$ 557,788 4/16/2021 Kelly Chesser (386) 462 Radiant CU Operations Bldg \$ 2,503,809 9/30/2021 Kelly Chesser (386) 462 Pressure Technology Warehouse \$ 3,390,889 12/20/2021 David Bowles (215) 628 Gainesville High Field MRI Renovation \$ 613,314 1/17/2022 Tom Brown (404) 434 Radiant CU - Chiefland Renovation \$ 463,147 8/18/2022 Kelly Chesser (386) 462 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376		-				(352) 375-1819
Seacoast Bank 37th Blvd Improvements \$ 504,007 12/28/2020 Melanie Shore (352) 375 Gainesville Airport Hangar Renovation \$ 1,809,208 2/1/2021 Lynn Noffsinger (352) 373 Radiant CU-Live Oak Renovation \$ 557,788 4/16/2021 Kelly Chesser (386) 462 Radiant CU Operations Bldg \$ 2,503,809 9/30/2021 Kelly Chesser (386) 462 Pressure Technology Warehouse \$ 3,390,889 12/20/2021 David Bowles (215) 628 Gainesville High Field MRI Renovation \$ 613,314 1/17/2022 Tom Brown (404) 434 Radiant CU - Chiefland Renovation \$ 463,147 8/18/2022 Kelly Chesser (386) 462 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376	<u> </u>					(334) 399-2883
Gainesville Airport Hangar Renovation \$ 1,809,208 2/1/2021 Lynn Noffsinger (352) 373 Radiant CU-Live Oak Renovation \$ 557,788 4/16/2021 Kelly Chesser (386) 462 Radiant CU Operations Bldg \$ 2,503,809 9/30/2021 Kelly Chesser (386) 462 Pressure Technology Warehouse \$ 3,390,889 12/20/2021 David Bowles (215) 628 Gainesville High Field MRI Renovation \$ 613,314 1/17/2022 Tom Brown (404) 434 Radiant CU - Chiefland Renovation \$ 463,147 8/18/2022 Kelly Chesser (386) 462 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376					· · · · · · · · · · · · · · · · · · ·	(352) 375-1819
Radiant CU-Live Oak Renovation \$ 557,788 4/16/2021 Kelly Chesser (386) 462 Radiant CU Operations Bldg \$ 2,503,809 9/30/2021 Kelly Chesser (386) 462 Pressure Technology Warehouse \$ 3,390,889 12/20/2021 David Bowles (215) 628 Gainesville High Field MRI Renovation \$ 613,314 1/17/2022 Tom Brown (404) 434 Radiant CU - Chiefland Renovation \$ 463,147 8/18/2022 Kelly Chesser (386) 462 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376	•	+-	-			(352) 373-1813
Radiant CU Operations Bldg \$ 2,503,809 9/30/2021 Kelly Chesser (386) 462 Pressure Technology Warehouse \$ 3,390,889 12/20/2021 David Bowles (215) 628 Gainesville High Field MRI Renovation \$ 613,314 1/17/2022 Tom Brown (404) 434 Radiant CU - Chiefland Renovation \$ 463,147 8/18/2022 Kelly Chesser (386) 462 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376						1
Pressure Technology Warehouse \$ 3,390,889 12/20/2021 David Bowles (215) 628 Gainesville High Field MRI Renovation \$ 613,314 1/17/2022 Tom Brown (404) 434 Radiant CU - Chiefland Renovation \$ 463,147 8/18/2022 Kelly Chesser (386) 462 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376					· ·	
Gainesville High Field MRI Renovation \$ 613,314 1/17/2022 Tom Brown (404) 434 Radiant CU - Chiefland Renovation \$ 463,147 8/18/2022 Kelly Chesser (386) 462 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376						
Radiant CU - Chiefland Renovation \$ 463,147 8/18/2022 Kelly Chesser (386) 462 The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376	<u> </u>	_				_
The New Swamp Restaurant \$ 3,490,781 8/19/2022 Bryan Harrington (352) 376		_				-
		_				
Seacoast Bank 3rd Floor Renovation \$ 803,260 4/10/2023 Melanie Shore (352) 375	<u>_</u>	_			-	(352) 376-6223









Why two teams? PROJECT MANAGEMENT FIELD SUPERVISION Scorpio is proposing two specific teams Ryan Stroh Matthew Clark TEAM 1 so that the City of Gainesville is confident Senior Project Field Manager when awarding multiple projects. Should Manager projects be released simultaneously, we have planned and dedicated the resources necessary to achieve success. Jenna Hollingsworth Justin Zambelli Our intention is to be able to balance Field Manager the City's work with our operations and Assistant Project Manager incorporate into our annual planning to ensure the City of Gainesville's projects are the top priority. PROJECT MANAGEMENT FIELD SUPERVISION Since each team presented here can handle two to three projects, depending on the size and complexity, we are Tracy Koller Richard Solana TEAM 2 confident in saying that we can manage Senior Project Field Manager up to six projects at a time. This strategy, Manager if desired, will allow the City to release projects concurrently which can provide added savings in time and money. The Maverick Maensivu Troy Underhill City will not have to wait on any a team Field Manager Assistant to become available to perform the Project Manager necessary work.



Education & Certifications

Master of Science in Building Construction, UF

Bachelor of Design in Architecture, UF

FL Certified General Contractor, License #CGC061834

GA Certified General Contractor, License #GCOA002489

LEED Accredited Professional BD+C USGBC

UF BCN Executive Committee

Builders Association of North Central FL - Board of Directors

CPR & First Aid Certification

City of Residence Gainesville, FL

Years of Experience Scorpio: 10 Other Firms: 18

Domenic Scorpio PRINCIPAL-IN-CHARGE

Domenic's Construction Management experience in local government and institutional projects is unparalleled and gives him the insight to overcome any project challenge. Over nearly three decades, he has led his companies in providing Construction Management Services for multiple government agencies throughout Central and North Central Florida. He ensures that decisions and commitments made in the preconstruction phase of the process are brought to fruition during construction. His history in this region, strong local craft and trade relationships, integrity, and open communication will ensure the successful delivery of the City of Gainesville for the Public Safety Facilities. Domenic is available to devote the necessary time required to this project.

- ACFR New Fire Station #23
- ACFR New Fire Station #40
- ACFR 2 New Fire Stations (with Lunz)
- City of Gainesville GTEC Renovations
- SFC Police Station
- UF New Student Health Care Center
- City of Fruitland New Public Safety Facility
- City of Wildwood New Public Works Facility (Lunz)
- City of Brooksville New Public Works Facility (Lunz)
- City of Tavares New Public Works Operations Center
- Marion County Schools New Central Warehouse
- City of Groveland New Empowerment Center
- Clay County Department of Health Renovations
- Clay County New Economic Development Facility
- Lake County New Emergency Operations Center
- Flagler County New Emergency Operations Center







Education & Certifications

Bachelor of Science in Building Construction, UF

LEED Accredited Professional, USGBC

OSHA 30 Hour Safety Certification

ABC Florida First Coast Chapter-Board Member 2014-2017

ABC Next Gen Graduate

ABC Project Eagle Awards 2013, 2014, 2016

USF Sunshine State Safety Award 2009 & 2010

City of Residence

Gainesville, FL

Years of Experience Scorpio: 7 Other Firms: 12



Chris Gregory has 19 years of Construction Management experience leading efforts in both preconstruction and construction. Chris leads the estimating team through preconstruction, ensuring the client's tight timelines are met, and high standards are exceeded. A constant study of industry costs and trends, Chris offers the unique perspective of having estimated a majority of the projects that he was responsible for managing. Chris approaches every project with a partnership perspective. He provides the ability to navigate complex building challenges cost-effectively and is equipped to respond to a fast-paced environment. Chris is available to devote the necessary time required to this project.

PROJECT EXPERIENCE

- ACFR New Fire Station #23
- ACFR New Fire Station #40
- ACFR 2 New Fire Stations (with Lunz)
- City of Gainesville GTEC Renovations
- SFC Police Station
- UF New Student Health Care Center
- City of Fruitland New Public Safety Facility
- City of Wildwood New Public Works Facility (Lunz)
- City of Brooksville New Public Works Facility (Lunz)
- City of Tavares New Public Works Operations Center
- Marion County Schools New Central Warehouse
- City of Groveland New Empowerment Center
- Clay County Department of Health Renovations
- Clay County New Economic Development Facility



Education & Certifications Bachelor of Science in Journalism, UF

CPR & First Aid Certification

Jennifer Denault COMMUNITY ENGAGEMENT & OUTREACH

Jenn has successfully managed the marketing, communications, and media relations for highprofile projects in partnership with owners and clients. She is accustomed to and effective in curating content, planning and executing events, and enhancing communication with external and internal audiences. With over 20 years of non-profit management, administration, fundraising, and communications experience, Jenn will oversee strategic components of clients and user engagement throughout the project's lifecycle. She has unique expertise in coordinating efforts with multiple stakeholders, both public and private, to achieve common goals. Jenn is available to devote the necessary time required to this project.

PROJECT EXPERIENCE

- ACFR New Fire Station #23
- ACFR New Fire Station #40
- ACFR 2 New Fire Stations (with Lunz)
- SFC Police Station
- UF New Student Health Care Center
- City of Fruitland New Public Safety Facility
- City of Wildwood New Public Works Facility (Lunz)
- City of Brooksville New Public Works Facility (Lunz)
- City of Gainesville GTEC Renovations
- City of Tavares New Public Works Operations Center
- Marion County Schools New Central Warehouse
- City of Groveland New Empowerment Center
- Clay County Department of Health Renovations
- Clay County New Economic Development Facility



City of Residence Gainesville, FL

Years of Experience Scorpio: 6 Other Firms: 14





Education & Certifications

Bachelor of Science in Building Construction, UF

FL Certified General Contractor, License #CGC1517397

OSHA 30 Hour Safety Certification

LEED Accredited Professional BD+C, USGBC

Green Globes Professional

Asbestos Awareness Class IV Training

CPR & First Aid Certification

Builder's Association of North Central FL - Board of Directors

City of Residence

Newberry, FL

Years of Experience Scorpio: 9 Other Firms: 11

Don Kellogg PROJECT OPERATIONS TEAM LEADER

Don has 20 years of broad and varied Construction Management experience focused primarily on projects of this size and scope. He has delivered many local government and civic-related projects and has worked with the directly with the City of Gainesville. Years of experience have provided Don with proficiency in every phase of construction, ensuring the successful delivery of each project. He is detail-oriented and a team player who ensures client expectations are exceeded. Don is available to devote the necessary time required to this project.

PROJECT EXPERIENCE

- ACFR New Fire Station #23
- ACFR New Fire Station #40
- ACFR 2 New Fire Stations (with Lunz)
- City of Gainesville GTEC Renovations
- SFC Police Station
- UF New Student Health Care Center
- City of Fruitland New Public Safety Facility
- City of Wildwood New Public Works Facility (Lunz)
- City of Brooksville New Public Works Facility (Lunz)
- City of Tavares New Public Works Operations Center
- Marion County Schools New Central Warehouse
- City of Groveland New Empowerment Center
- Clay County Department of Health Renovations
- Clay County New Economic Development Facility



Education & Certifications

Construction Training Courses, Santa Fe College

OSHA 30 Certification

CPR and First Aid Certification

Excavation and Trenching Safety Certification

City of Residence

Gainesville, FL

Years of Experience Scorpio: 9 Other Firms: 17

Aaron Rogers FEILD OPERATIONS TEAM LEADER

AaronRogersoverseesallfieldoperationsactivities, including sitelogistics, safety, schedule, and quality control. His 27 years of experience working on large projects throughout Central and North Florida gives him a high degree of appreciation for the requirements of the City of Gainesville New Public Safety Facilities. His keen attention to detail ensures that the projects he assists in supervising are on time and of the highest quality. Aaron is a valuable resource with experience delivering over \$500M of construction. He is adept at working on all structures, systems, and finishes. He has developed the trust of industry professionals throughout Central and North Florida and is well respected as a team leader. Aaron is available to devote the necessary time required to this project.

- Alachua County Fire Rescue Fire Station #80
- Alachua County Fire Rescue Fire Station #23
- Alachua County Fire Rescue Fire Station #40
- City of Groveland Design Build Elese Tomlin Empower Center
- City of Tavares New Public Works Operations Complex
- City of Fruitland New Public Safety Facility
- City of Wildwood Municipal Services Building
- City of Brooksville Public Works Facility
- City of Gainesville GTEC Renovations
- City of Newberry New City Hall
- Marion County Schools New Central Warehouse





Education & Certifications

Master of Science in Building Construction, UF

Bachelor of Science in Building Construction, UF

OSHA 30 Hour Safety Certification

CPR & First Aid Certification

City of Residence

Newberry, FL

Years of Experience Scorpio: 7 Other Firms: 11

Ryan Stroh SENIOR PROJECT MANAGER

Ryan Stroh has 18 years of Construction Management experience. He has successfully completed millions of dollars worth of construction projects for state and local government agencies throughout north central Florida. Throughout his career, he has managed projects from preconstruction through closeout and warranty while maintaining communication between all partners. He is experienced in additions, new commercial construction, and renovations, emphasizing high-tech and office spaces. In addition, Ryan has delivered multiple LEED-certified and Green Globes-certified projects. Ryan is available to devote 50% to this project.

PROJECT EXPERIENCE

- Alachua County Fire Rescue Fire Station #80
- Alachua County Fire Rescue Surplus Warehouse Renovations
- City of Gainesville GTEC Building Renovations
- City of Wildwood Municipal Services Building
- City of Newberry New City Hall
- HCA Florida North Florida Hospital Multiple Projects
- University of Florida Multiple Projects
- Santa Fe College Multiple Projects
- Alachua County Fairgrounds New Pre-Engineered Metal Building
- Alachua County Civil Courthouse Renovations
- Alachua County Public Works Facility Renovations ca MacLaren



Education & CertificationsBachelor of Science in Building Construction, UF

OSHA 30 CPR/First Aid

City of Residence High Springs, FL

Years of Experience Scorpio: 3 Other Firms: 0

Jenna Hollingsworth Assistant Project Manager

Jenna is a resourceful, energetic, and detail-oriented building construction professional. She is routinely recognized for her exceptional organizational and communication skills. Jenna assists primarily with project documents, reviewing for completeness and accuracy. Her dedicated efforts keep projects moving in the right direction. Jenna is adept at creating efficiencies and is an excellent overall team player. Jenna is available to devote 100% to this project.

- Alachua County New Fire Station #80
- City of Gainesville GTEC Building Renovations
- · City of Wildwood New Public Works Facility
- Radiant Credit Union Multiple Branch Renovations
- Radiant Credit Union Operations Building Renovation
- Radiant Credit Union New Lake City Branch
- SBAC Buchholz High School Gymnasium Renovations- New Roof and HVAC
- SBAC Santa Fe High School Auditorium Renovations
- Santa Fe College Building W Classroom Renovations
- Santa Fe College Building E Digital Media Renovations
- Santa Fe College Fine Arts Hall Renovation
- Santa Fe College S Building S Renovation
- Santa Fe College Building W Multiple Renovations
- HCA Florida-North Florida Hospital 2nd Floor Renovations
- HCA Florida- North Florida Hospital 3rd Floor Renovation





TEAM1

Education & Certifications
OSHA 30-Hour Safety
Certification
CPR and First Aid Certification

City of Residence Newberry, FL

Years of Experience Scorpio: 7 Other Firms: 19

Matthew Clark FIELD MANAGER

Matthew expertly manages subcontractors to maximize daily production in the field. He has over 19 years of experience in the construction industry and always advocates for the City of Gainesville's interest. Matthew is an excellent communicator and keeps a safe, clean work environment while delivering an exceptional quality product. He has extensive experience working for local municipalities and is currently working on a new Fire Station for Alachua County. Matthew is highly conscientious in communicating with the design team, City of Gainesvilles, and building occupants adjacent to his project sites. Matthew is available to devote 100% to this project.

PROJECT EXPERIENCE

- Alachua County New Fire Station #80
- City of Gainesville GTEC Building Renovation
- · School Board of Alachua County Oak View Middle School New Classroom Building
- School Board of Alachua County Buchholz High School Gymnasium Renovations
- Santa Fe College Learning Commons and Library Renovation
- Santa Fe College Building B Classroom Renovations
- Santa Fe College Science Classroom and Chemistry Lab Renovations
- Santa Fe College Classroom Buildings A, B & K Renovations
- Santa Fe College Fine Arts Hall Renovation
- Santa Fe College Buildings A&B Transformer Replacement



Education & Certifications

Bachelor of Science in Building Construction, UF

OSHA 30 Hour Safety Certification

CPR and First Aid Certification

City of Residence Gainesville, FL

Years of Experience Scorpio: 7 Other Firms: 0

Justin Zambelli FIELD MANAGER

Justin is an energetic and hands-on Field Manager with 7 years of experience. Justin assisted on the construction of two local Fire Stations. He is currently completing the reconstruction of Westwood Middle School and was instrumental in the supervision of the UF New Student Healthcare Center. He is engaged in all aspects of daily on-site construction activity. His awareness of each activity in and around his projects and attention to jobsite organization is superb. Justin is customer focused, consistently exceeds client expectations, always seeking to creating win-win situations throughout the course of a project. Justin is available to devote 100% to this project.

- Alachua County New Fire Station #33
- Alachua County New Fire Station #40
- SBAC Westwood Middle School Redesign and Redevelopment
- UF New Student Health Care Center
- UF College of Education Expansion and Renovation
- UF Turlington Plaza Dining Services Renovations
- UF Keys Residential Complex Renovations
- UF Gamma Phi Beta New Sorority House
- UF Tri-Delta Sorority House Renovations
- Santa Fe College International Student Center Renovation





Education & Certifications
Saint Stanislaus School
OSHA 30 Hour Safety
Certification
CPR & First Aid Certification

City of Residence Thomasville, GA

Years of Experience Scorpio: 4 Other Firms: 27

Tracy Koller SENIOR PROJECT MANAGER

Tracy has 30 years of Construction Management experience. Over the course of his career, he has supervised and provided valuable leadership and direction for Preconstruction and Construction. With wide-ranging experience in design, development, planning, and construction, Tracy's comprehensive appreciation and understanding for each facet of the process is a desirable asset. Tracy has successfully managed over \$260M worth of development and construction throughout his career. He is dedicated team player, who promotes frequent and transparent communication with the design team, owners and clients, as well as craft and trade professionals.. Tracy is available to devote 50% to this project.

PROJECT EXPERIENCE

- City of Gainesville Pavement Project
- City of Tavares New Public Works Operations Facility
- Clay County Department of Health Renovations
- Clay County District School Keystone Heights Elementary New Cafetorium and Classrooms
- SBAC Howard Bishop Middle School Redesign and Redevelopment
- SBAC Oak View Middle School New Classroom Building
- SBAC New Transition School
- Marion County Public Schools Osceola Middle School New Cafeteria
- UF Center for Instructional Technology and Training Renovation
- UF Peabody Hall Renovation
- Santa Fe College Laboratory Renovations



Education & Certifications

Bachelor of Science in Building
Construction, UF

OSHA 30-Hour Safety
Certification Solidworks

Professional 3D Modeling

City of Residence Winter Park, FL

Years of Experience Scorpio: 4 Other Firms: 1

Maverick Maensivu Assistant Project Manager

Maverick's experience in the field and the office provide a well-rounded approach to project management. As Assistant Project Manager, he will assist the Senior Project Manager and the Field Management team in all facets and phases of construction. Maverick is a construction professional who excels at relationship-building while providing additional leadership for the team. He is detail-oriented and quick to respond, offering exceptional technical oversight to the administration and coordination of projects. His time management skills and holistic approach to a project schedule make him an asset to the team. Maverick is available to devote 100% to this project.

PROJECT EXPERIENCE

- City of Tavares New Public Works Operations Center
- City of Groveland Elese Tomlin Community Empowerment Center (Preconstruction)
- School Board of Alachua County Howard Bishop Middle School Redesign and Redevelopment
- School Board of Alachua County New Transition School Board
- UF New Student Health Care Center
- UF Reitz Union Auditorium Renovation
- Santa Fe College International Student Center
- HCA- ORMC Ocala Heart Center Medical Office Renovation
- Frankel Media Group New Office Build-out
- Sharp Spring New Office Build-out





EAIWI Z

Education & Certifications

US Navy Veteran
HTA Welding School
North Marion High School
CPR & First Aid Certification
OSHA 30 Hour Safety
Certification

City of Residence

Ocala, FL

Years of Experience Scorpio: 4 Other Firms: 14

Rick Solana FIELD MANAGER

Rick Solana is a safety conscious and detail-oriented project superintendent who provides clear direction to subcontractors on a daily basis. In addition to his 18 years of experience as a Field Manager, Rick is a skilled welder who served four years in the US Navy. He has delivered numerous large municipal projects in North Central Florida. Richard is regarded by many as steady and fair with an unparalleled work ethic. Rick is available to devote 100% to this project.

PROJECT EXPERIENCE

- St. Lucie County Fire Station #16
- St. Lucie County Fire Station #15
- City of Wildwood Municipal Services Building
- Marion County Public Schools New Central Warehouse
- Marion County Public School Osceola Middle School New Cafeteria
- Marion County Lowell Correctional Institution
- Marion County Marion County Courthouse Expansion
- Marion County Marion County Jail Expansion
- Marion Co Public Schools Ward-Highlands Elementary School Renovation
- Citrus County Public Schools Crystal River High School
- Marion Co Public Schools S. Ocala Elementary
- Broward County Hollywood Boardwalk Renovation



TEAM:

Education & Certifications
Associate of Arts,
Santa Fe College
Red Cross First Aid & CPR
Certified OSHA 30

City of Residence Lake Butler, FL

Years of Experience Scorpio: 5 Other Firms: 20

Troy Underhill FIELD MANAGER

Troy is the "boots on the ground" general of the project, ensuring all daily on-site construction activities are ex- ecuted as planned. He is directly responsible for logistics, safety, scheduling, and quality control. Troy is exceptional at building lasting relationships with owners, architects, subcontractors and suppliers. He examines all project documents to establish a detailed understanding of the entire project. His hands-on approach ensures nothing is overlooked during construction.

Troy is available to devote 100% to this project.

PROJECT EXPERIENCE

- City of Gainesville & Drummond Bank 37th Blvd Roadway and Site Improvements
- City of Alachua Operations Center
- District Eight New Medical Examiner's Office
- Department of Juvenile Justice Multiple Projects
- Oak Hall School New Enrichment Center
- UF College of Education Expansion and Renovation
- UF Dean of Students Peabody Hall Renovations
- UF UAA Swim & Dive Locker Room Renovations
- UF Communicore Research Lab Renovation
- SFC Bldg W Health Sciences Advisement Offices Renovation





Education & Certifications

Bachelor of Science in Accounting, UF

Construction Financial Management Association Certification

City of Residence

Ft. White, FL

Years of Experience Scorpio: 9 Other Firms: 10

Jessica MacLaren PROJECT ADMINISTRATOR/ACCOUNTANT

Jessica is a highly detail-oriented and cost-conscious accounting professional with over 19 years of experience. Her daily functions include accurate and timely reporting of job cost, client, trade contractor, and vendor requisition management, management of lien waivers and notices to owners, and trade contractor insurance verification. Jessica is also responsible for managing and reconciling the Owner Direct Purchase (ODP) of material and equipment for tax savings. Jessica manages every project with a level of organization focused on the details required should the job require an audit. Jessica is available to devote the necessary time required to this project.

PROJECT EXPERIENCE

- ACFR New Fire Station #23
- ACFR New Fire Station #40
- ACFR 2 New Fire Stations (with Lunz)
- SFC Police Station
- UF New Student Health Care Center
- City of Fruitland New Public Safety Facility
- City of Wildwood New Public Works Facility (Lunz)
- City of Brooksville New Public Works Facility (Lunz)
- City of Gainesville GTEC Renovations
- City of Tavares New Public Works Operations Center
- Marion County Schools New Central Warehouse
- City of Groveland New Empowerment Center
- Clay County Department of Health Renovations
- Clay County New Economic Development Facility

HAVE HAHE

PEOPLE
RELATIONSHIPS
EXPERIENCE
QUALIFICATIONS
STRATEGY
KNOWLEDGE
CONFIDENCE



Ron DeSantis, Governor

Melanie S. Griffin, Secretary



STATE OF FLORIDA **DEPARTMENT OF BUSINESS AND PROFESSIONAL REGULATION**

CONSTRUCTION INDUSTRY LICENSING BOARD

THE GENERAL CONTRACTOR HEREIN IS CERTIFIED UNDER THE PROVISIONS OF CHAPTER 489, FLORIDA STATUTES

SCORPIO, DOMENICO EMILIO

D E SCORPIO CORPORATION 3911 WEST NEWBERRY ROAD GAINESVILLE FL 32607

LICENSE NUMBER: CGC061834

EXPIRATION DATE: AUGUST 31, 2024

Always verify licenses online at MyFloridaLicense.com



Do not alter this document in any form.

This is your license. It is unlawful for anyone other than the licensee to use this document.

State of Florida Department of State

I certify from the records of this office that D.E. SCORPIO CORPORATION is a corporation organized under the laws of the State of Florida, filed on April 24, 2013.

The document number of this corporation is P13000037247.

I further certify that said corporation has paid all fees due this office through December 31, 2023, that its most recent annual report/uniform business report was filed on January 3, 2023, and that its status is active.

I further certify that said corporation has not filed Articles of Dissolution.

Given under my hand and the Great Seal of the State of Florida at Tallahassee, the Capital, this the Third day of January, 2023



ervices.sunbiz.org/Filings/CertificateOfStatus/Certif



ACORD'

DESCORP-01

KWHITMAN

CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY) 5/30/2023

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must have ADDITIONAL INSURED provisions or be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate holder to confer inthis to the certificate holder in lieur of such andresement(s)

this certificate does not confer rights to the certificate holder in lieu of su	ch endorsement(s).						
PRODUCER	CONTACT NAME:						
Hub International Florida 2811 NW 41st Street Gainesville, FL 32606	PHONE (A/C, No, Ext): (352) 377-2002	FAX (A/C, No): (352)	376-8393				
	E-MAIL ADDRESS:						
	INSURER(S) AFFORDING COVERAGE		NAIC#				
	INSURER A: Valley Forge Insurance Company	/	20508				
INSURED	INSURER B : The Continental Insurance Company 35289						
D. E. Scorpio Corporation 3911 Newberry Rd Gainesville, FL 32607	INSURER C : Bridgefield Employers Insurance	10701					
	INSURER D : Westchester Surplus Lines Insur	ance Co.	10172				
	INSURER E : Peleus Insurance Company		34118				
	INSURER F:						

COVERAGES CERTIFICATE NUMBER: REVISION NUMBER:

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EYAL LISTONS AND CONDITIONS OF SIGNIFICATION OF ANY CONTRACT OR OTHER DOCUMENT OF THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EYAL LISTONS AND CONDITIONS OF SIGNIFICATION OF ANY CONTRACT OR OTHER DOCUMENT.

	KCLUSIONS AND CONDITIONS OF SUCH						
INSR LTR	TYPE OF INSURANCE	ADDL:	SUBR WVD POLICY NUMBER	POLICY EFF (MM/DD/YYYY)	POLICY EXP (MM/DD/YYYY)	LIMITS	;
Α	X COMMERCIAL GENERAL LIABILITY					EACH OCCURRENCE	s 1,000,000
	CLAIMS-MADE X OCCUR	x	7033952057	5/30/2023	5/30/2024	DAMAGE TO RENTED PREMISES (Ea occurrence)	\$ 100,000
						MED EXP (Any one person)	_{\$} 15,000
						PERSONAL & ADV INJURY	s 1,000,000
	GEN'L AGGREGATE LIMIT APPLIES PER:					GENERAL AGGREGATE	\$ 2,000,000
	POLICY X PRO-						s 2,000,000
	X OTHER: 5,000,000						\$ 2,000,000
A	AUTOMOBILE LIABILITY					COMBINED SINGLE LIMIT (Ea accident)	s 1,000,000
	X ANY AUTO		7033952043	5/30/2023	5/30/2024	BODILY INJURY (Per person)	\$
	OWNED SCHEDULED AUTOS					BODILY INJURY (Per accident)	\$
	HIRED ONLY NON-SWINED					PROPERTY DAMAGE (Per accident)	\$
							\$
В	X UMBRELLA LIAB X OCCUR					EACH OCCURRENCE	\$ 5,000,000
	EXCESS LIAB CLAIMS-MADE	1 1	7033952012	5/30/2023	5/30/2024	AGGREGATE	s 5,000,000
	DED X RETENTION \$ 10,000						\$
С	WORKERS COMPENSATION AND EMPLOYERS' LIABILITY					X PER OTH-	
	ANY PROPRIETOR/PARTNER/EXECUTIVE N	N/A	830-52716	5/30/2023	5/30/2024	E.L. EACH ACCIDENT	_{\$} 1,000,000
	(Mandatory in NH)					E.L. DISEASE - EA EMPLOYEE	
	If yes, describe under DESCRIPTION OF OPERATIONS below						_{\$} 1,000,000
D	Pollution Liability		G73527521 003	5/30/2023	5/30/2024	1,000,000/2,000,000	
E	Professional Liabili		121 CTR 0200001-02	5/30/2023	5/30/2024	1,000,000/2,000,000	
-	1					1	

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required)
Certificate Holder is listed as an Additional Insured with regard to the General Liability policy.

CERTIFICATE HOLDER	CANCELLATION
CITY OF GAINESVILLE 200 E UNIVERSITY AVE. GAINESVILLE. FL 32601	SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS.
GAINESVILLE, FL 32001	AUTHORIZED REPRESENTATIVE

ACORD 25 (2016/03)

© 1988-2015 ACORD CORPORATION. All rights reserved.

The ACORD name and logo are registered marks of ACORD



BOND LETTER



June 29, 2023

City of Gainesville Public Works PO Box 490 MS 58 Gainesville, FL 32627-0490

RE: D.E. Scorpio Corporation Letter of Bondability

To Whom It May Concern:

It is the privilege of Hatcher Insurance and Swiss Re Corporate Solutions America Insurance Corporation to provide surety credit to D.E. Scorpio Corporation, with single project limits of \$70,000,000 and an aggregate uncompleted backlog of \$120,000,000. D.E. Scorpio Corporation has an impressive construction "track record", an impeccable reputation, and are generally regarded as being one of the finest construction firms in the State of Florida. Swiss Re Corporate Solutions America Insurance Corporation has an "A+" (Superior) Rating, a financial size category of XV (\$2 billion or greater) by AM Best and has US Treasury Limit of \$95,164,000.

If D.E. Scorpio Corporation is awarded a contract and requests that we provide the necessary Performance and/or Payment Bonds, we will be prepared to execute the bonds subject to our acceptable review of the contract terms and conditions, bond forms, appropriate contract funding and any other underwriting considerations at the time of the request.

Our consideration and issuance of bonds is a matter solely between D.E. Scorpio, and ourselves, and we assume no liability to third parties or to you by the issuance of this letter.

We trust that this information meets with your satisfaction. If there are further questions, please feel free to contact our office.

Sincerely,

William J. Palmer Attorney-in-Fact Florida Resident Agent

WJP/aw

1411 Edgewater Drive, Suite 104 • P.O. Box 540689 • Orlando, FL 32854-0689 Phone (407) 841-2686 • Fax (407) 841-2688

Commercial Insurance • Surety Bonds • Personal Insurance • Employee Benefits • PEO





Building Trust

Scorpio was founded on the principal of implementing old-fashioned values and innovative solutions in delivering cost effective, quality construction projects. Sharing in this philosophy is our dedicated team of well-respected industry professionals – some of whom have worked with our founder, Domenic Scorpio, for decades. Our responsibility is to advocate in your interest throughout project delivery. Our team is loyal in achieving your project's objectives. We have a unique understanding of the intricacies of local and state regulatory agencies, and offer the knowledge and trusted relationships to navigate every challenge expeditiously. We conduct business with professionalism and continually set the bar high for ourselves, resulting in a proven project delivery process.

Construction Industry Leaders

Scorpio fosters a culture of highly motivated professionals that are passionate about the communities we serve and the relationships we develop. We maintain a collaborative approach to service which ensures the unique expertise of each individual is brought to bear on your project with one collective goal –

EXCEEDING YOUR EXPECTATIONS IN EVERY PHASE OF PROJECT DELIVERY.

Our Story

After earning a Bachelor's Degree in Architecture and a Master's Degree in Building Construction from the University of Florida, Domenic Scorpio began his professional career in construction, in 1995.

In June of 2001, Domenic accepted a partnership offer from a prominent Gainesville contractor, quickly working his way into the role of Chief Operating Officer and qualifying agent of the company. Under Domenic's leadership the company grew and expanded into seven locations in Florida and South Georgia, reaching gross revenues of \$250 Million annually.

In early 2013, while proud of the accomplishments of his prior partnership, the combination of Domenic's entrepreneurial spirit and his desire to cultivate a culture focused on relationship-based management, Domenic established Scorpio. He, along with the loyal following of construction professionals, quickly proved the value of this philosophy to the community delivering challenging projects of varying size, scope, complexity, and budgets for some of the most well-respected and experienced clients in the area.

Over the last 10 years Scorpio has grown in size and reputation, while maintaining an intense focus on its core values and principals. Team members are added not only for their skill and experience but their ability to embrace and further our mission of bringing exceptional buildings to life, for life.







Scorpio. 2023 TEAM



Regarding Scorpio's size, resources, and capabilities, our firm is an exceptional choice to deliver this project. We are an extremely experienced team with a depth of resources that will serve the City of Gainesville to a successful completion. We have a vast network of subcontractors and consultants in Gainesville and neighboring counties ready to serve on this project.





Alachua County Fire Station #33

Construction Management New Construction

Owner (Rep/Facility Mgr)

Alachua County Fire Rescue Gainesville, FL Harold Theus, Chief p: 352.384.3132

Architect (Contact)

Strollo Architects Jim Strollo, President, p: 407.423.5355

Size

7,754 sf

Final Construction Cost

\$2,281,427

Completion Date

Fire Station #33 is a one-story concrete new construction facility approximately 7,754 sf that houses 28 fire fighters and EMS personnel. Along with a fourbay apparatus area, the building is comprised of four dorm rooms and 3 full bathrooms, (1 ADA). The floor plan includes a full kitchen with commercial grade appliances, a living / dining area, an exterior covered patio, a fitness room, a shop area, a laundry room, a locker room, a decontamination room, a watch room with IT area above, and watch commander's office with a future officer dorm area. It was designed as an energy efficient structure meeting current Alachua County green standards and will be certified as Green and Sustainable under the guidelines established by the Green Building Initiative (Green Globes).















Alachua County Fire Station #40

Construction Management
New Construction

Owner (Rep/Facility Mgr)

Alachua County Fire Rescue Gainesville, FL Harold Theus, Chief p: 352.384.3132

Architect (Contact)

Brame Heck Architects Billy Brame, Architect, p: 352.372.0425

Size

5,684 sf

Final Construction Cost \$1,526,124

Completion Date 2017

Key Personnel



Fire Station #40 is a one-story new construction facility of approximately 5,684 SF located in Waldo FL that houses approximately 18 or more fire fighters and EMS personnel operating on three continuous shifts 7 days a week. Along with a two-bay apparatus area, the building is comprised of 7 dorm rooms and 4 full bathrooms (1 ADA accessible). The floor plan includes a full kitchen with commercial grade appliances, a living area, fitness and locker room, laundry/ janitorial room, decontamination room, a maintenance workshop, storage rooms, and a covered outdoor patio area. The station was built with expansion in mind as room for a third bay in the future was a factor in all decisions. Fire Station #40 was designed as an energy efficient structure meeting current Alachua County green standards for structural as well as MEP, with zone driven HVAC supplying the heating and cooling throughout with state of art low energy consumption units. There is an intercom and paging system included for communication throughout the building and an emergency generator to integrate a backup power system. Interior finishes include plaster finishes, ceramic tiled bathrooms, acoustical ceilings, polished concrete floors and solid wood doors. The exterior of the building is protected by an asphalt shingled roof, cement plaster finish on walls with an accent band and color scheme that blends nicely into the rural area. Exterior windows are protected from catastrophic weather events by aluminum storm panels. A new parking area, paved driveway and landscaping compliments the exterior of the property.













Alachua County Two New Fire Stations

Construction Management

New Construction

Owner (Rep/Facility Mgr)

Alachua County Gainesville, FL Ramon Gavarrete Project Manager p. 352.374.5202

Architect (Contact)

The Lunz Group Brad Lunz, Principal p. 407.930.9389

Size

11,540 sf

Estimated Construction Cost

\$13.6 M - for two in progress

Substantial Completion Date

2023 (In Progress)

With growth comes the need for services. Additional fire stations offer increased access to emergency responders, reduced response times, and lower insurance rates for the growing number of Alachua County residents. This prototype approach for the four new fire stations planned reduced design fees and demonstrated fiscal responsibility.

The buildings are considered a 50-year facility with a metal roof, a sizeable three-vehicle apparatus bay, and all LED lighting. Clearly demarcated zones separate 'hot' carcinogen areas from decontamination zones and firefighter residential quarters. Exterior aesthetics include intentional touches such as hip roofs with gables and a brick, stone and metal panel finishes that will help the station blend in better near residential neighborhoods.

Stress reduction for our emergency responders is a top consideration inside the building. The residential area features a large day room, all gas appliances, a separate dining area, and can sleep up to ten. The fire alarm system has been updated to a 'ramping' alarm to reduce the shock of a sudden siren.

The station also features community spaces, including a training room that seats 30-40 and a lobby left unlocked as a safe haven for infant drop-offs.









MAKE BUILDINGS FOR LIFE.









Santa Fe College Police **Department Expansion** and Renovation



Expansion, Renovation

Owner (Rep/Facility Mgr)

Santa Fe College Facilities Services, Gainesville Rebecca Rogers, Director of Facilities p. 352.395.5174

Architect (Contact)

Kail Partners Danny Kail, Principal p. 352.871.4935

3,276 sf

Final Construction Cost

\$931.389

Substantial Completion Date April 2018

Key Personnel





The Santa Fe College Police Station Renovation and Expansion required the efforts of a large team consisting of the college's administration, police department, architects, engineers and Scorpio. The building was designed to incorporate an existing facility and allow expansion into the future. It is a single-story building consisting of offices, a lobby, a break room, a secure detention area, and state of the art communications center. Surrounding the facility site, improvements included the construction of ADA parking areas, ADA sidewalks, landscaping, signage and connection to an on-site generator. The most challenging aspect of the project was to complete all work alongside the police department as they operate 24/7 and did not relocate during the project.

This Renovation and Expansion was a part of Scorpio's Continuing Services Contract with Santa Fe College which includes services for a large variety of projects in new construction, as well as expansions and renovations throughout campus including lab buildings, auditoriums, classrooms, faculty offices, athletic fields and facilities, and utility infrastructure projects. This provides experience with varying building systems for structure, exterior cladding, and roof assemblies as well as technologically advanced security systems, IT systems, equipment, and interior spaces. These systems provide cutting-edge learning environments and enhance the students' overall college experience campus-wide.













Community Reinvestment Area GTEC Building Office Renovation

Construction Management

Renovation

Owner (Rep/Facility Mgr)

City of Gainesville Mo Deel, Operations Coordinator p. 352.393.8212

Architect (Contact)

Walker Architects Joe Walker, President p. 352.672.6448

Size

2,000 sf

Final Construction Cost

\$299,007

Substantial Completion Date

February 2021

A department within the City of Gainesville, the Gainesville Community Reinvestment Area offers a suite of incentive programs designed to encourage beautification, economic development, and community partnerships within the designated redevelopment districts.

The Gainesville Technology Enterprise Center (GTEC) Building is located in East Gainesville on a 13.6-acre campus. The campus was created to be the area's first high-tech incubator, to provide early-stage technology start-up companies with the resources to help them grow and develop.

Designed by Walker Architects, the 2,000 s/f GTEC Building Renovation provides updated offices and a collaborative workspace with improved technology and communication infrastructure. New modern finishes, flooring, light fixtures, and furniture were installed to create a welcoming environment for the staff and community.







Scorpio. MAKE BUILDINGS FOR LIFE.

Key Personnel



Preconstruction Team Leader



Aaron Rogers
Field Operations
Team Leader



Project Operation Team Leader



Senior Project Manager



Jenna Hollingsworth Assistant Project Manager





Municipal Services Building

Construction Management

New Construction

Owner (Rep/Facility Mgr)

City of Wildwood Jeremy Hockenbury, Public Works Director p. 352.330.1343

Architect (Contact)

The Lunz Group Mark McLean p. 407.930.9389

Size

26,500 sf

Final Construction Cost \$3.8M

Substantial Completion Date

November 2022

The City of Wildwood new Municipal Services Complex is located on approximately 10.7 acres on the City of Wildwood's Public Works occupied compound. This project consisted of the construction of a new 6250 sf pre-engineered Fleet Maintenance building with 4 bays and office space, fueling station and a 2500 square feet equipment storage building. The project also includes the renovation of three existing buildings formerly used for school classrooms and cafeteria.


The renovated building houses the City's Utility Department and associated storage needs. The renovation of the three buildings included approximately 17,742 square feet of interior space. Other site improvements include the construction of secured parking areas, drives, landscaping, stormwater, signage, and on-site generators.

















Marion County Public Schools Central Warehouse

Construction Management

New Construction

Owner (Rep/Facility Mgr)

Marion County Public Schools Robert Knight, Facilities Department Supervisor P. 352.671.6903

Architect (Contact)

Level Architecture Adam Gayle P. 352.448.7788

Size

65,000 SF

Estimated Construction Cost

\$7.5M

Estimated Completion Date

Scheduled October 2023

Construction of a new central warehouse for the Marion County Public Schools District. The project will be used to consolidate the central receiving and storage services in one facility.

It consists of a new 65,000 sft metal building with loading docks for incoming and outgoing shipments, conditioned storage, and build-out of an approx, 3,400 sft of office space. The project is located at the old phoenix center site in NE Ocala and will require extensive grading, paving, and utility upgrades including new water mains and stormwater retention.





Key Personnel



Chris Gregory
Preconstruction
Team Leader



Senior Project Manager



Aaron Rogers Field Operations Team Leader



Project Operation





Field Manager







City of Tavares New Public Works Operations Center

Construction Management

New Construction

Owner (Rep/Facility Mgr)

City of Tavares 201 E Main Street Tavares, FL 32778 John Rumble Purchasing Manager p. 352.742.6209

Architect (Contact)

GatorSktch Mike Latham, Principal p. 407.608.5677

Size 30,000 sf

Estimated Budget

Estimated Completion Date

May 2024

The City of Tavares will construct a regional workforce training and innovation center in partnership with Lake Technical College in what is considered one of the most innovative projects combining government and education resources that have ever been created.

The Public Works Operations Center will accommodate the complete operations of the Public Works division and serve as the new training location of Lake Tech's Diesel Systems Technology programs. Utilizing this innovative model, students can train in an authentic environment as they work alongside the City's technicians.

The project includes the following, which will be built on city-owned land: An 8,532-square-foot public works facility for the City. A combined 28,980-square-foot building includes a 9,350-square-foot vehicle fleet storage space, a 12,670-square-foot space for Lake Technical College's diesel mechanic program, and 6,960 square feet for the college's automotive program. Additionally, this complex will include a 10,540-square-foot operations building.

PARTNERSHIP WITH













Key Personnel



Preconstruction Team Leader




Aaron Rogers
Field Operations
Team Leader



Maverick Maensivu Assistant Project Manager







City of Fruitland Park New Public Safety Facility

Construction Management

New Construction

Owner (Rep/Facility Mgr)

City of Fruitland 506 W. Berckman St. Fruitland Park, FL 34731 Gary Lavenia City Manager p. 352.360.6727

Architect (Contact)

GatorSktch Mike Latham, Principal p. 407.608.5677

Size

20,707 sf

Estimated Budget

\$9.2M

Estimated Completion Date

September 2024

The City of Fruitland Park is building a new Public Safety Facility to meet the growing demands of the community. The new building will be situated between Fruitland Park City Hall and the Fruitland Park Library. The new building will be a two-story CMU Building that will house both Law Enforcement and the Fire Department. Site work will require the demolition of the existing Fire Station.

The new Police Station portion is designed for sixteen Law Enforcement Officers with offices for the Police Chief, a CID Captain, and Detectives. Additional space will be allocated for the Squad room, Shift Sergeants, an EOC Training Room, Intake and Interview rooms, Evidence Processing, and an Armory, along with an accreditation, training, and records room, CID Conference Room, a breakroom, storage, restrooms, showers, lockers, and a Sally Port.

The Fire Station side is designed to house eight Firefighters and accommodate three Apparatus Bays, including Gear Turnout and a Decontamination Room. A Galley Kitchen and Dining area will accommodate three shifts with "kitties" for food with refrigerators and pantries. There will be a Day Room, a shared Fitness Center with Law Enforcement, bunk room(s), restrooms, showers, and a laundry facility.




















Brooksville Public Works Facility

Construction Management

New Construction

Owner (Rep/Facility Mgr)

Jon Dow City of Brooksville Assistant Public Works Director p. 352.540.3810

Architect (Contact)

The Lunz Group James Pendley, Architect p. 407.930.9389

Size

12,500 sf

Estimated Construction Cost

\$3.6M

Estimated Completion Date

July 2024

This project consists of site development and new construction of a 12,500-sf pre-engineered metal building for the City of Brooksville. This new facility will house offices for the City of Brooksville public works department and utility department as well as a conference/training room, lockers and showers, vehicle shop space, small engine repair, welding shop, sign shop, and warehouse space.

The site development includes new stormwater retention basins, a perimeter fence, site utilities, parking areas for the public, and vehicles to be serviced in one of the three service bays. The building is designed to allow for an additional 2,500 sf bay to be added onto the back of the building in a future phase. Construction is scheduled to begin fall of 2023 and be completed by the summer of 2024.



















New Economic Development Facility

Construction Management

New Construction

Owner (Rep/Facility Mgr)

Clay County Gene Price Deputy Director of Facilities p. 352.327.0765

Architect (Contact)

Walker Architects Joe Walker President p. 352.672.6448

Size

30,000 sf

Estimated Construction Cost

\$12M

Estimated Completion Date

TBD

The County and the Economic Development Corporation are seeking to build a new facility to accommodate the work of these organizations and the continued growth of the county. Clay County Economic Development Corporation's mission is to create initiatives for sustainable economic growth by creating job opportunities.

The Clay County Building/Economic Development Services Facility will be a 2-story building, estimated up to 30,000 sq. $\,$ ft. consisting of office spaces, conference rooms, storage, and a gym. This new facility is planned for the 1.4 acre site $\,$ located at 633 N. Orange Ave. Green Cove Springs adjacent to the existing County Administration Building. The existing facility on the site, a former used car dealership, will need to be demolished. Environmental surveys indicate the site appears to be clean of any hazardous materials. This presents as a relatively straightforward build with ample area for laydown.

The goal will be to provide a comfortable and engaging space for employees and visitors, while maintaining a thoughtful and careful eye on the budget. Scorpio will join alongside Walker Architects to ensure a design that achieves the goals of quality and finish, while maintaining budget and schedule.




















Elese Tomlin Empowerment Center

Construction Management

New Construction

Owner (Rep/Facility Mgr)

City of Groveland Chris Coghill 156 S Lake Ave Groveland, FL 34736 p. 352.429.2141 x2014

Architect (Contact)

Walker Architects Joe Walker, President p. 352.672.6448

Size

4,000 sf

Estimated Construction Cost

\$2M

Substantial Completion Date

TBD

With our Design Partner Walker Architects have developed an early Empowerment Center building design concept that pulls from a hybrid of traditional Florida vernacular styles, including Florida Cracker, Craftsman, Colonial and southern Victorian.

Crowned with a Colonial-style clock tower and metal cupola, and adorned by Victorian trim and Craftsman accents, the Main Entry to the Empowerment Center serves not only as the building's focal point, but also as a prominent and visual landmark to the surrounding city blocks. Exposed structural elements are feature components in our design. A mix of stained Cypress brackets, arches and columns anchored in battered Limestone bases and handcrafted southern brick provide the framework for the exterior facades. Close attention to proportions, distribution of claddings and subtle detailing help the new Empowerment Center to reference other Groveland structures, while remaining prominent within its surroundings. Finally, a second story covered outdoor balcony provides a scenic view of it all, and provides a convenient, semi-private outdoor amenity to the building's users.

The Empowerment Center interior features multiple zones which provide varying degrees of access to administrative staff and citizens. A bubbling fountain encourages visitors to enter a public foyer area that leads to heavily-trafficked zones like the small business incubator hub, game room/library, and computer labs. More private administrative offices and meeting rooms are accessed from secured corridors that span the length of the building, while a back staircase and ADA-lift provide access to the second floor balcony. Optional second floor offices, which house quieter rooms for the Director and other staff members are easily incorporated into the upper roof line of this design with additional dormer windows and accessible attic trusses.





Key Personnel



y Aaron Field C Team



Don Kellogg Project Operations



| PREVIOUS FIRM EXPERIENCE

University of Central Florida

HIGHER EDUCATION







PREVIOUS FIRM EXPERIENCE

This project is representative of key Scorpio Co. personnel experience and not Scorpio Co. firm experience.

UCF Public Safety Center

UCF built its new Public Safety Center to replace the outdated police station that was located in the heart of an extremely active campus. This three-story building houses several offices, lecture halls, and a fitness center to be utilized by the officers. The 34,000 square foot complex was awarded with silver LEED accreditation and can now accommodate all the storage space needed for evidence and record keeping. The building also has three holding cells and a dispatch call center to ensure the highest level of safety for the students.

Construction Management

New Construction

Owner (Rep/Facility Mgr)

University of Central Florida, Orlando Gary Ameral p. 407.823.1566

Architect (Contact)

Ponikvar & Associates, Jack Ponikvar, President p. 352.372.1378

Size

34,000 sf

Final Construction Cost

\$8,000,000

Substantial Completion Date

July 2011



| PREVIOUS FIRM EXPERIENCE

Lake County Government







PREVIOUS FIRM EXPERIENCE

This project is representative of key Scorpio Co. personnel experience and not Scorpio Co. firm experience.

Emergency Operations Center

The new Emergency Operations Center was built to replace the existing EOC in order to sufficiently withstand natural disasters, providing critical systems to ensure facility sustainability. This project features reinforced concrete roof envelope systems, and designed to withstand 160 mph winds and the 500 year flood plain. Specifically designed for jointuse to accommodate the Communications Department for the Sheriff, Fire and EMS as well as the Department of Emergency Management to include vehicular setbacks, CCTV surveillance cameras, and advanced security access systems. The EOC section of the facility contains an Incident Command Center with all associated support rooms, food service facilities, dormitories, and offices/conference areas for all elected officials.

Construction Management

New Construction

Owner (Rep/Facility Mgr)

Lake County Government, Tavares, FL

Architect (Contact)

Architects Design Group

Size

28,415 sf

Final Construction Cost

\$6,600,000

Substantial Completion Date

March 2013



| PREVIOUS FIRM EXPERIENCE

Flagler County Government







PREVIOUS FIRM EXPERIENCE

This project is representative of key Scorpio Co. personnel experience and not Scorpio Co. firm experience.

Emergency Operations Center

Designed to replace an existing, obsolete center, this state-of-the-art 26,000 square foot facility features a self-sufficient GSF hurricane-safe facility, serving as the heart of county government operations under emergency conditions. The entire building envelope was constructed efficiently via tiltwall construction, and can endure hurricane winds in excess of 140 mph. The facility also houses the Central Data Center, 911 operations, training rooms, staff offices and additional support areas. The facility contains all necessary systems to house staff 24 hours a day, 7 days weekly during emergency situations. It includes sleeping quarters to kitchen facilities, and includes a 24-hour emergency backup power and communications system.

Construction Management New Construction

Owner (Rep/Facility Mgr) Flagler County Government,

Flagler County Government, Bunnel, FL

Architect (Contact)

DJ Design, Inc

Size

26,000 sf

Final Construction Cost

\$3,571,083

Substantial Completion Date

. April 2006





VERIFICATION FORM

CONSULANT VERIFICATION FORM REGISTERED TO DO BUSINESS IN THE STATE OF FLORIDA Is Proposer registered with Florida Department of State's, Division of Corporations, to do business in the State of Florida? YES NO (refer to Part 1, 1.6, last paragraph) If the answer is "YES", provide a copy of SunBiz registration or SunBiz Document Number (#P13000037247 If the answer is "NO", please state reason why: _ **DIVERSITY AND INCLUSION** (Applies to solicitations above \$50,000) Does your company have a policy on diversity and inclusion? YES NO If yes, please attach a copy of the policy to your submittal. Note: Possessing a diversity and inclusion policy will have no effect on the City's consideration of your submittal, but is simply being requested for information gathering purposes. Domenic Scorpio Proposer's Name Domenic Scorpio - President and CEO Printed Name/Title of Authorized Representative \ 7-14-23 Signature of Authorized Representative LOCAL PREFERENCE (Check one) (YES Local Preference requested: A copy of the following documents must be included in your submission if you are requesting Local Preference: • Business Tax Receipt Zoning Compliance Permit QUALIFIED SMALL BUSINESS AND/OR SERVICE DISABLED VETERAN BUSINESS STATUS (Check one) Is your business qualified, in accordance with the City of Gainesville's Small Business Procurement Program, as a local Small Business? YES NO Is your business qualified, in accordance with the City of Gainesville's Small Business Procurement Program, as a local Service-Disabled Veteran Business? YES (NO) This page must be completed and uploaded to DemandStar.com with your Submittal. E-Bidding Document - RFQ (CCNA) - Page 88 of 113



BUSSINESS TAX STATEMENT 2023

Your payment was processed. Print this tax receipt for your records. It was also sent to domenic@scorpioco.com



Online Business Tax Receipt(1)

D.E. SCORPIO CORPORATION
Business Name DOMENIC E SCORPIO -

DOMENIC E SCORPIO - CONTRACTOR

Business Tax ID 40280

This constitutes your business tax receipt for 10/1/2022 - 9/30/2023.

Your business tax(es) for the fiscal year 10/1/2022 - 9/30/2023 are as follows:

Business Categories

ID	Service Name	Tax Amount	Explanation of Calculations
1000	STATE LICENSE/CERTIFICATION REQUIRED	\$0.00	
1360	CONTRACTOR-GENERAL-UNLIMITED	\$131.25	Business category flat fee of \$131.25
6801	COMMERCIALLY ZONED	\$0.00	
****	Payment	(\$131.25)	Posted on 9/1/2022
	TOTAL DUE:	\$0.00	

Please note that the maximum charge for any single service is \$525

Amount Due on *Thursday, September 22, 2022* is \$0.00

(1) This page will serve as your business tax receipt for the fiscal year 10/1/2022 - 9/30/2023.

Payments must be time-stamped by 11:59 pm on Monday, October 03, 2022 in order to avoid late fees.

Please, note that a home occupation permit may be required for this location, someone will contact you upon review of the information



DRUG-FREE WORKPLACE FORM

The undersigned bidder in accordance with Florida Statute 287.087 hereby certifies that

Domenic Scorpio		does
	Name of Proposer)	

- 1. Publish a statement notifying employees that the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance is prohibited in the workplace and specifying the actions that will be taken against employees for violations of such prohibition.
- 2. Inform employees about the dangers of drug abuse in the workplace, the business's policy of maintaining a drug-free workplace, any available drug counseling, rehabilitation, and employee assistance programs, and the penalties that may be imposed upon employees for the drug abuse violations.
- 3. Give each employee engaged in providing the commodities or contractual services that are under bid a copy of the statement specified in subsection (1).
- 4. In the statement specified in subsection (1), notify the employees that, as a condition of working on the commodities or contractual services that are under bid, the employee will abide by the terms of the statement and will notify the employer of any conviction of, or plea of guilty or nolo contendere to, any violation of Chapter 893 or of any controlled substance law of the United States or any state, for a violation occurring in the workplace no later than five (5) days after such conviction.
- 5. Impose a sanction on, or require the satisfactory participation in a drug abuse assistance or rehabilitation program if such is available in the employee's community, by any employee who is so convicted.
- 6. Make a good faith effort to continue to maintain a drug-free workplace through implementation of this section.

As the person authorized to sign the statement, I certify that this bidder complies fully with the above requirements.

Proposer's Signature

7-14-23

Date

12/2019

E-Bidding Document - RFQ (CCNA) - Page 89 of 113



W-9

Request for Taxpayer

Give Form to the

partment of the Treasury	1			er and Certifi					- 1	seno	to	the	IRS	ŝ.
ernal Revenue Service				structions and the late		rmati	on.							
		um). Name is red	quired on this line; o	do not leave this line blank.										
D.E. Scorpio (Corporation 'disregarded entity name	if different from	abovo										_	
Scorpio	disregarded entity fiame	s, ii dinerent itori	above											
mi 2 Chook appropri	ate hox for federal tax cl	assification of th	e nerson whose na	me is entered on line 1. Ch	eck only	one (of the	4 Fy	emptio	ons (co	des s	annly	only	to
following seven		abomoution of th	o porson whose na	ino io dinorda dir inio 1. di	iook omy	OIIO (JI 1110	certa	in enti	ties, no	t indi	ividua		
5 Individual/so	le proprietor or	C Corporation	S Corporation	n Partnership	□т	rust/es	state	Instr	uctions	on pa	ge 3)	:		
single-memb		o corporation	_ 0 00.po.u					Exen	npt pay	ree cod	e (if a	iny)		
Following seven following seven following seven single-member single-member that the following seven following	ity company. Enter the ta	ax classification	(C=C corporation, S	S=S corporation, P=Partne	rship) ▶							-		
Note: Check				on of the single-member o				Exen	nption	from F	ATCA	repo	ortin	3
another LLC				from the owner unless the ourposes. Otherwise, a sin				code	(if any	<i>/</i>)				
is disregarde		d check the appr	opriate box for the	tax classification of its owr	ner.									
Other (see in	structions) > er, street, and apt. or suit	te no.) See instru	ictions.		Reques	ster's	name :			ontion		outside	2 609 (18.)
e videres (vidinis	or, stroot, and apt. or san	10 110., 000 1110111	iotiono.		1 loque.	3(0) 3	iiaiio i	ina aa	u1033	(Option	49			
6 City, state, and	ZIP code													
7 List account nur	mber(s) here (optional)													
	yer Identificatio					0-	.1.1							
				me given on line 1 to av mber (SSN). However, 1		500	ial se	unty	ump	al.		т—	7-	ī
ident alien, sole prop	orietor, or disregarded	d entity, see th	e instructions for	Part I, later. For other				-		-				
ities, it is your emplo /, later.	yer identification nun	nber (EIN). If yo	ou do not have a	number, see How to ge	eta	or						1	_	_
	in more than one nam	ne, see the inst	ructions for line	1. Also see What Name	and	_	ployer	identi	featio	n num	ber			1
mber To Give the Re	quester for guidelines	s on whose nu	mber to enter.						П		T	T		1
						1 4 1		2	1 4 1	2 4		7		
						4	6	- 2	6	2 1	7	7	3	
100	ication					4	6	- 2	6	2 1	7	7	3	
der penalties of perju	ury, I certify that:		-							_	7	7	3	_
der penalties of perju The number shown o	ury, I certify that: on this form is my con		dentification num	ober (or I am waiting for		per to	be is:	sued t	o me)	; and		_		-
der penalties of perju The number shown of I am not subject to b Service (IRS) that I ar	ury, I certify that: on this form is my corr ackup withholding be m subject to backup	ecause: (a) I an withholding as	dentification num	nber (or I am waiting for ackup withholding, or (b ure to report all interest) I have	per to	be is:	sued t	o me)	; and	ernal	Rev	enu	
der penalties of perju The number shown o am not subject to b Service (IRS) that I an no longer subject to	ury, I certify that: on this form is my corr ackup withholding be m subject to backup withholding; a	ecause: (a) I am withholding as and	dentification num n exempt from ba a result of a failu	ackup withholding, or (b) I have	per to	be is:	sued t	o me)	; and	ernal	Rev	enu	
der penalties of perju The number shown of I am not subject to b Service (IRS) that I am no longer subject to I I am a U.S. citizen or	ury, I certify that: on this form is my con ackup withholding be m subject to backup w backup withholding; other U.S. person (de	ecause: (a) I an withholding as and efined below);	dentification num n exempt from ba a result of a failu and	ackup withholding, or (b ure to report all interest) I have or divid	per to e not b ends,	be iss	sued t	o me)	; and	ernal	Rev	enu	
der penalties of perju The number shown of I am not subject to b Service (IRS) that I an no longer subject to I I am a U.S. citizen or The FATCA code(s) e	ury, I certify that: on this form is my contackup withholding be m subject to backup withholding; a backup withholding; a other U.S. person (de entered on this form (i	ecause: (a) I an withholding as and efined below); if any) indicatin	dentification num n exempt from ba a result of a failu and g that I am exem	ackup withholding, or (bure to report all interest appropriate the report all interest appropriate from FATCA reporting the report and reporting the report and reporting the report all reports and report and re) I have or divid	per to e not b ends,	be issociation or (c)	sued totified	o me) d by t RS ha	; and he Inte s notif	ernal ied r	Rev	enu nat I	am
der penalties of perju The number shown of am not subject to be Service (IRS) that I am no longer subject to am a U.S. citizen or The FATCA code(s) en tification instruction I have failed to report	ury, I certify that: on this form is my con ackup withholding be m subject to backup ob backup withholding; a other U.S. person (do entered on this form (i ns. You must cross ou all interest and divider	ecause: (a) I am withholding as and efined below); if any) indicatin t item 2 above inds on your tax	dentification num n exempt from ba a result of a failu and g that I am exem if you have been r return. For real e	ackup withholding, or (bure to report all interest apt from FATCA reporting the bushess to the control of the bushess that yes the bushess) I have or divid ng is co ou are c 2 does n	per to e not blends, errect.	be isspeen ri, or (c)	sued to otifier the II	o me) d by ti RS ha	; and ne Inte s notif up wit interes	ernal ied r	Revene the	enu nat I	am
der penalties of perju The number shown of am not subject to b Service (IRS) that I an no longer subject to i am a U.S. citizen or The FATCA code(s) e rtification instruction u have failed to report juisition or abandonm	ury, I certify that: on this form is my con ackup withholding be m subject to backup ob backup withholding; other U.S. person (de entered on this form (ins. You must cross our all interest and divider	ecause: (a) I am withholding as and efined below); if any) indicatin t item 2 above inds on your tax ty, cancellation	dentification num n exempt from ba a result of a failu and g that I am exem if you have been r return. For real e of debt, contribut	ackup withholding, or (bure to report all interest appropriate the property of	ng is con ou are con	per to e not b ends, rrect.	be isspeen not or (c)	sued totified the II	o me) d by ti RS ha back tgage	; and he Inte s notif up wit interes	ernal ied r	Revene the	enunat I	am
der penalties of perju The number shown of I am not subject to b Service (IRS) that I am no longer subject to I I am a U.S. citizen or The FATCA code(s) e rtification instruction u have failed to report quisition or abandonmer than interest and	ury, I certify that: on this form is my con ackup withholding be m subject to backup ob backup withholding; other U.S. person (de entered on this form (ins. You must cross our all interest and divider	ecause: (a) I am withholding as and efined below); if any) indicatin t item 2 above inds on your tax ty, cancellation	dentification num n exempt from ba a result of a failu and g that I am exem if you have been r return. For real e of debt, contribut	ackup withholding, or (bure to report all interest apt from FATCA reporting the bushess to the control of the bushess that yes the bushess	ng is con ou are con	per to e not b ends, rrect.	be isspeen not or (c)	sued totified the II	o me) d by ti RS ha back tgage	; and he Inte s notif up wit interes	ernal ied r	Revene the	enunat I	am
der penalties of perju The number shown of am not subject to b Service (IRS) that I an olonger subject to i am a U.S. citizen or The FATCA code(s) extification instruction u have failled to report puisition or abandonmer than interest and ogn Signature of	ury, I certify that: on this form is my con ackup withholding be m subject to backup ob backup withholding; other U.S. person (de entered on this form (ins. You must cross our all interest and divider tent of secured proper	ecause: (a) I am withholding as and efined below); if any) indicatin t item 2 above inds on your tax ty, cancellation	dentification num n exempt from ba a result of a failu and g that I am exem if you have been r return. For real e of debt, contribut	ackup withholding, or (bure to report all interest apt from FATCA reporting the position of th	ng is co ou are c 2 does n rement a ur corre	per to e not be ends, errect. eurrent not ap arrang ct TIN	be issociated or (c)	sued to otifier the III	o me) d by ti RS ha back tgage , and	; and he Inte s notif up wit interes genera	ernal ied r	Revene the	enunat I	am
der penalties of perju The number shown of am not subject to b Service (IRS) that I am of longer subject to lam a U.S. citizen or The FATCA code(s) ertification instruction I have failed to report juisition or abandonmer than interest and of the pere Signature of U.S. person lambda and the short should be	ury, I certify that: on this form is my con ackup withholding be m subject to backup v backup withholding; a other U.S. person (d) entered on this form (i ns. You must cross ou all interest and divider ent of secured proper ividends, you are not r	ecause: (a) I am withholding as and efined below); if any) indicatin t item 2 above inds on your tax ty, cancellation	dentification num n exempt from ba a result of a failu and g that I am exem if you have been r return. For real e of debt, contribut	ackup withholding, or (bure to report all interest open from FATCA reporting the from FATCA reporting to the from FATCA reporting the from FATCA reporting to the from FATCA reporting the from FATC	or dividing is contained and is containe	per to e not be ends, errect. current not ap arrang ct TIN	be isspeen nor (c)	sued to otified the III	o me) d by ti RS ha	; and he Intes s notif up wit interes genera	ernal ied r hhok st pa llly, p	Revolutions the state of the st	enu hat I	am
der penalties of perju The number shown of am not subject to b Service (IRS) that I am of longer subject to lam a U.S. citizen or The FATCA code(s) ertification instruction I have failed to report juisition or abandonmer than interest and of the pere Signature of U.S. person lambda and the short should be	ury, I certify that: on this form is my con ackup withholding be m subject to backup v backup withholding; a other U.S. person (d) entered on this form (i ns. You must cross ou all interest and divider ent of secured proper ividends, you are not r	ecause: (a) I am withholding as and efined below); if any) indicatin t item 2 above inds on your tax ty, cancellation	dentification num n exempt from ba a result of a failu and g that I am exem if you have been r return. For real e of debt, contribut	ackup withholding, or (bure to report all interest apt from FATCA reporting the interest appears and individual reting the interest appears and	or dividing is contained and is containe	per to e not be ends, errect. current not ap arrang ct TIN	be isspeen nor (c)	sued to otified the III	o me) d by ti RS ha	; and he Intes s notif up wit interes genera	ernal ied r hhok st pa llly, p	Revolutions the state of the st	enu hat I	am
der penalties of perjuite number shown of am not subject to be dervice (IRS) that I are old longer subject to am a U.S. citizen or the FATCA code(s) etification instruction have failed to report uisition or abandonmer than interest and u.S. person the person in the pe	ury, I certify that: on this form is my con ackup withholding be m subject to backup v backup withholding; a other U.S. person (d) entered on this form (i ns. You must cross ou all interest and divider ent of secured proper ividends, you are not r	ecause: (a) I am withholding as and efined below); if any) indicatin t item 2 above inds on your tax ty, cancellation equired to sign	dentification num n exempt from be a result of a failu and g that I am exem if you have been r return. For real e of debt, contribut the certification,	ackup withholding, or (bure to report all interest apt from FATCA reporting the interest appears and individual reting the interest appears and	ng is control of the	per to e not be not be ends, errect. Eurrent apparange ct TIN	be isseen n or (c) thy subtry subtry subtry subtry. For emen is See	sued to otified the III	o me) d by ti RS ha b back ttgage , and structi	y and ne Interest on stock	hhold the pa llly, p r Par	Revolutions the state of the st	becausents	am
der penalties of perju The number shown of am not subject to b Service (IRS) that I am not longer subject to lam a U.S. citizen or The FATCA code(s) ertification instruction and a U.S. distribution or abandonmer than interest and outputs the subject of U.S. person leneral Institution references are ted.	ury, I certify that: on this form is my con ackup withholding be m subject to backup v backup withholding; a other U.S. person (di entered on this form (i ns. You must cross our all interest and divider nent of secured proper indidends, you are not r ructions to the Internal Revent	ecause: (a) I am withholding as and efined below); if any) indicatint titem 2 above inds on your tax ty, cancellation equired to sign	dentification num n exempt from ba a result of a failu and g that I am exem if you have been r return. For real e of debt, contribut the certification,	ackup withholding, or (bure to report all interest apt from FATCA reporting the interest appears and individual reting the interest appears and	ng is control of the	per to e not be not be ends, errect. Eurrent apparange ct TIN	be isseen n or (c) thy subtry subtry subtry subtry. For emen is See	sued to otified the III	o me) d by ti RS ha b back ttgage , and structi	y and ne Interest on stock	hhold the pa llly, p r Par	Revolutions the state of the st	becausents	am
der penalties of perjuiche number shown of am not subject to be Service (IRS) that I also longer subject to I am a U.S. citizen or the FATCA code(s) et itification instruction have failed to report uisition or abandonmer than interest and or u.S. person the person in	ury, I certify that: on this form is my conackup withholding be m subject to backup withholding; other U.S. person (dentered on this form (ins. You must cross our all interest and dividencent of secured proper invidents, you are not rections.	ecause: (a) I am withholding as and efined below); if any) indicatint it item 2 above indoor your tax ty, cancellaring of the code unless ation about de	dentification num n exempt from be a result of a failu and g that I am exem if you have been r return. For real e of debt, contribut the certification,	ackup withholding, or (bure to report all interest opt from FATCA reportinotified by the IRS that yestate transactions, item 2 ions to an individual retire but you must provide yo Form 1099-DIV (difunds) Form 1099-MISC proceeds) Form 1099-B (storestorestorestorestorestorestorestore	ng is controlled and is contro	poer to enot be ends, entreed. A contract appropriate the ends appropria	be isspeen n or (c) thy subply. For ement is See April uuding	sued to otified the III	o me) d by ti RS ha b backstagage , and g afrom	; and the Interest of the Inte	ernal ied r hholk st pa illy, p r Par	Revenue the ding id, payment il, la mute, , or (becausents	am
der penalties of perjiche number shown of am not subject to be Service (IRS) that I also longer subject to I am a U.S. citizen or the FATCA code(s) etification instruction have failed to report justion or abandonmer than interest and u.S. person length of the period o	ury, I certify that: on this form is my con ackup withholding be m subject to backup v backup withholding; a other U.S. person (di entered on this form (i ns. You must cross our all interest and divider nent of secured proper indidends, you are not r ructions to the Internal Revent	ecause: (a) I am withholding as and efined below); if any) indicatint it item 2 above inds on your tax ty, cancellation acquired to sign according to the code unless attion about deth as legislation.	dentification num n exempt from be a result of a failu and g that I am exem if you have been r return. For real e of debt, contribut the certification,	ackup withholding, or (bure to report all interest opt from FATCA reporting the post of th	ng is coopulare coopulare correctividends (various ck or mickers)	poer to enot be enoted and enoted appropriate appropri	be isseen n or (c) tily subply. For emen in See April uuding	sued to otified the III	o me) d by ti RS ha b back tgage , and ti refrom	; and the Interest of the Inte	ernal ied r hholk st pa illy, p r Par	Revenue the ding id, payment il, la mute, , or (becausents	am
der penalties of perjuite penalties of perjuite number shown of am not subject to be of service (IRS) that I also longer subject to I am a U.S. citizen or the FATCA code(s) etification instruction have failed to report unisition or abandonmer than interest and or u.S. person in the penalties of the person in the penalties of th	ury, I certify that: on this form is my conackup withholding be m subject to backup backup withholding; other U.S. person (dentered on this form (ins. You must cross our all interest and dividerent of secured proper ividends, you are not rections. For the latest inform dits instructions, suced, go to www.irs.gov	ecause: (a) I am withholding as and efined below); if any) indicatint it item 2 above inds on your tax ty, cancellation acquired to sign according to the code unless attion about deth as legislation.	dentification num n exempt from be a result of a failu and g that I am exem if you have been r return. For real e of debt, contribut the certification,	property of the second of the	ng is concounted are concounted are concounted are concounted are concounted are correctly are corre	poer to enot be not apparanged to the stype	be isseen n or (c) thy subtry	sued to otified the III per th	o me) d by ti RS ha b back ttgage , and control reference control	; and ne Interest snotifications; and up with interest generations for stock ess, aw	hhold st pa allly, p r Par	Revone the ding id, aaym til, la	becasents	amause
der penalties of perjuite number shown of am not subject to be Service (IRS) that I am to longer subject to it am a U.S. citizen or the FATCA code(s) ettification instruction have failed to report justion or abandonmer than interest and of the longer of	ury, I certify that: on this form is my conackup withholding be m subject to backup backup withholding; other U.S. person (dentered on this form (ins. You must cross our all interest and dividerent of secured proper invidents, you are not received in the Internal Revent of t	ecause: (a) I am withholding as and efined below); if any) indicatint it item 2 above indo to your tax ty, cancellaring a curied to sign action acquired to sign at the code unless ation about de that as legislation.	dentification num n exempt from be a result of a failu and og that I am exem if you have been r return. For real e of debt, contribut the certification,	pt from FATCA reporting the part of the pa	ng is concounted are concounted are concounted are concounted are concounted are concounted are correctly are correctly are concounted are co	oper to not be not apparrangent TIN	be is: oeen n or (c) tily sub ply. For emen i. See April fund s eal es and thi	sued to otifiee the III is ject to or more to (IRA). The instance come ales a state trend paid	o me) d by ti RS ha b backs ttgage , and control e from control e	; and the Interest of the Inte	hhold st pa llly, p r Par	Revone the ding id, aaym til, la mute, or o	enunat I beca	am
der penalties of perjuments. In enumber shown of am not subject to be Service (IRS) that I am not longer subject to larma a U.S. citizen or The FATCA code(s) entification instruction in have failed to report unitered and uniterest and unit	ury, I certify that: on this form is my conackup withholding be m subject to backup withholding; or other U.S. person (dentered on this form (ins. You must cross our all interest and divider nent of secured proper indents, you are not rectally to the Internal Revenut of	ecause: (a) I am withholding as and efined below); of any) indicating titem 2 above inds on your tax by, cancellation equired to sign the Code unless atton about desh as legislation who is required to your correct tax	dentification num n exempt from ba a result of a failu and g that I am exem if you have been r return. For real e of debt, contribut the certification, s otherwise velopments n enacted d to file an xpayer	property of the second of the	ng is concounted are concounted are concounted are concounted are concounted are concounted are correctly are correctly are concounted are co	oper to not be not apparrangent TIN	be is: oeen n or (c) tily sub ply. For emen i. See April fund s eal es and thi	sued to otifiee the III is ject to or more to (IRA). The instance come ales a state trend paid	o me) d by ti RS ha b backs ttgage , and control e from control e	; and the Interest of the Inte	hhold st pa llly, p r Par	Revone the ding id, aaym til, la mute, or o	enunat I beca	am
der penalties of perjuite number shown of am not subject to be Service (IRS) that I am to longer subject to it am a U.S. citizen or the FATCA code(s) ettification instruction have failed to report justicion or abandonmer than interest and of the citizen or the eneral Institution of the citizen or the eneral institution or abandonmer than interest and of the eneral institution or etc. The signature of U.S. person the eneral institution or enerts are the eneral institution or energy were published in the person of the energy were published in the energy were pub	ury, I certify that: on this form is my conackup withholding be m subject to backup backup withholding; other U.S. person (dentered on this form (ins. You must cross our all interest and dividerent of secured proper ividered, you are not record to the Internal Revent of the	ecause: (a) I am withholding as and efined below); if any) indicatint it item 2 above indo to your tax ty, cancellaring a curied to sign action adult de that as legislation in the control of the contro	dentification num n exempt from be a result of a failu and og that I am exem if you have been r return. For real e of debt, contribut the certification, s otherwise velopments n enacted d to file an expayer ity number	eckup withholding, or (bure to report all interest apt from FATCA reporting the following of the property of the following of	i) I have or divid	oper to a not be ends, where the ends, where the ends, or rect. It is stype to the ends of	be isseen n or (c) thy sub-ply. For emen is See April uding so fir funds eal es and thit terest;	ject to tified the III ject to the III ject to the III ject to the III ject to the installation in the III ject to the installation in the III ject to the III	o me) d by ti RS ha b back tgage , and structi e. prize and co ansac ty ne 3-E (s	up wittinteresgenerations) stock	ernal ied r hhold st pa allly, p r Par s or ards other loar	Revone the ding id, payment till, la mute, or question interes	enunat I beca	am
der penalties of perjuite number shown of am not subject to be Service (IRS) that I am to longer subject to am a U.S. citizen or the FATCA code(s) etification instruction have failed to report unisition or abandonmer than interest and u.S. person the subject to U.S. person the tendent of the uniterest and u.S. person the u.S. person the uniterest and u.S. person the u.S. person the u.S. person the u.S. person the u.S. pers	ry, I certify that: on this form is my conackup withholding be m subject to backup withholding; or other U.S. person (dentered on this form (ins. You must cross our all interest and divider nent of secured proper invidents, you are not record its instructions, suced, go to www.irs.gov	ecause: (a) I am withholding as and efined below); of any) indicating titem 2 above inds on your tax ty, cancellation equired to sign the Code unless ation about de that as legislation as legislation for correct tax ur social secur ber (ITIN), adop ployer identific	dentification num n exempt from ba a result of a failu and g that I am exem if you have been r return. For real e of debt, contribut the certification, s otherwise velopments n enacted d to file an expayer ity number potion attion number	eckup withholding, or (bure to report all interest opt from FATCA reporting the property of th	i) I have or divid	per to the not be ends, and the ends, arrect. The ends of the ends, arrect. The ends of	be isseen n or (c) thy subply. For emen I. See a so fir fund seal es nd thit terest;	sued to otified the III otifie	o me) d by ti RS ha b backs ttgage , and structi efform c, prize ansace ansace tty ne 3-E (s'	; and the Interest of the Inte	ernal ied r	Revone the ding id, payment till, la mute, or (becausents ater.	am
the penalties of perjuiche number shown of am not subject to be Service (IRS) that I also longer subject to I am a U.S. citizen or the FATCA code(s) etitication instruction have failed to report unisition or abandonmer than interest and or the Institute of I	ry, I certify that: on this form is my conackup withholding be m subject to backup backup withholding; other U.S. person (dentered on this form (ins. You must cross our all interest and dividerent of secured proper invidered, you are not record to the Internal Revent of the	ecause: (a) I am withholding as and efined below); if any) indicating titem 2 above indicating t	dentification num n exempt from be a result of a failu and og that I am exem if you have been n return. For real e of debt, contribut the certification, s otherwise velopments n enacted d to file an expayer ity number ption aution number n you, or other	eckup withholding, or (bure to report all interest and treest and	i) I have or divid ing is co oo ou are c c does n co ou are considerable in the constant c mortga celed d isistion of the constant c color of the constant c color ou are constant c color ou are color of the color out are color of the color out are	per to enot be not apparately for the stype of the sty	be isseen no or (c) thy subply. For the perment is seen and the terest, and the terest is th	sued to otified the III otifie	o me) d by ti RS ha b backs ttgage , and structi efform c, prize ansace ansace tty ne 3-E (s'	; and the Interest of the Inte	ernal ied r	Revone the ding id, payment till, la mute, or (becausents ater.	am
der penalties of perju The number shown of am not subject to b Service (IRS) that I am not longer subject to b I am a U.S. citizen or the FATCA code(s) of t	ry, I certify that: on this form is my conackup withholding be m subject to backup withholding; or other U.S. person (dentered on this form (ins. You must cross our all interest and divider nent of secured proper invidents, you are not record its instructions, suced, go to www.irs.gov	withholding as and efined below); if any) indicating titem 2 above inds on your tax ty, cancellation adout death as legislation. If any who is required to sign with a segislation. If your social security our correct tax us social security and polyer identification and the sign with the sign wi	dentification num n exempt from be a result of a failu and og that I am exem if you have been n return. For real e of debt, contribut the certification, s otherwise velopments n enacted d to file an expayer ity number ption aution number n you, or other	eckup withholding, or (bure to report all interest and treest and	i) I have or divid	oer to the note the note of th	be isseen n or (c) thy subply. For the seen in or (c) the seen in or (gject to otifier the III ject to otifier the III ject to or more to (IRA) the instance of the	o me) d by ti RS ha b back tigage , and d structi contact ansac ty ne ansac ty	i; and the Interest of the Int	ernal ied r	Revvne the ding id, aaymut II, la mutton, or (enumat I becaentsater. ual grossons)	am ause
der penalties of perjuite number shown of am not subject to be Service (IRS) that I am to longer subject to larm a U.S. citizen or the FATCA code(s) et diffication instruction have failed to report juisition or abandonmer than interest and u.S. person letter of the person of the pe	ry, I certify that: on this form is my conackup withholding be m subject to backup backup withholding; other U.S. person (dentered on this form (ins. You must cross our all interest and dividerent of secured proper ividends, you are not received to the Internal Revent of the IRS must obtain y TiN) which may be your identification numl number (ATIN), or empformation return. not limited to, the fol	withholding as and efined below); if any) indicating titem 2 above inds on your tax ty, cancellation adout death as legislation. If any who is required to sign with a segislation. If your social security our correct tax us social security and polyer identification and the sign with the sign wi	dentification num n exempt from be a result of a failu and og that I am exem if you have been n return. For real e of debt, contribut the certification, s otherwise velopments n enacted d to file an expayer ity number ption aution number n you, or other	eckup withholding, or (bure to report all interest and treest and	i) I have or divid	per to a not be lends, when the lends, we have a lend and a lends are a lend and a lend a len	be isseen n or (c) thy subply. For emending sof ir funds seal es and this terest, N. to the the thickness of the terest of the t	sued to otified the III ject to otified the III ject to or more to (IRA) the instance aleas a state transparent personal	o me) d by ti RS ha b back tgage , and e structi 2023 e from a, prize anand co ansac tty nee 3-E (s'	up witinteres generations stock es, aw ertain of tudent utudent utudent with a stock es, aw ertain of tudent utudent utudent utudent with a stock es, aw ertain of tudent et utudent et utu	hholdst pa allly, p r Par s or ards trans loar	Revvne the ding id, saymet III, la mute, or (enumat I becausents ater. ual grossons) eres	am ause



ADDENDUM 1

ADDENDUM NO. 1



Date: July 11, 2023 Bid Date: July 14, 2023

at 3:00 P.M. (Local Time)

Bid Name Public Safety Facilities Construction Manager at Risk Bid No.: PWDA-230055-DH

NOTE: This Addendum has been issued only to the holders of record of the specifications.

The original Specifications remain in full force and effect except as revised by the following changes which shall take precedence over anything to the contrary:

1. Any questions shall be submitted in writing to the City of Gainesville Purchasing Division by 3:00 p.m. (local time), July 5, 2023. Questions may be submitted as follows:

Email: holderds@gainesville.org

- 2. Please find attached:
 - a. Copy of the cone of silence information (Financial Procedures Manual Section 41-524 Prohibition of Lobbying in Procurement Matters)).

The following are answers/clarifications to questions received:

- 3. Question: Section 3.1 (page 7) provides the Proposal Format and Section 3.2 provides the Content of Proposal. The Content of the Proposal is not included in the instructions for the format. Would you like the proposal to be formatted as section 3.1 with responses to those items and then as Section 3.2 with the responses to the Content? However with this organization:
 - a. 3.2.a RFP Cover Page would be moved ahead of 3.1.
 - b. Licenses would be duplicated under 3.2bb and 3.2.f.
 - c. Qualifications would possibly be duplicated in 3.1 Qualification of Firm and 3.2C. Statement of Qualifications

Answer: Proposals can be assembled as preferred by the vendor provided all items are addressed; vendor should ensure the proposal flows well. Typically, proposals received include a preface with the RFP Cover Page and Opening Letter, followed by the items listed 3.1, followed by a separate section or appendix with forms, licenses and any other supporting documents, however, it is up to the vendor to decide what order to assembly the documents.

4. Question: 3.2.c (page 7) says to Provide a Statement of all Qualifications that will communicate the capabilities of the proposer to successfully complete the project. Is there a specific Statement of Qualifications that is to be completed? Or what is expected to be included in the Statement of Qualifications?

Answer: There is no specific statement of qualifications that is to be completed; vendors must ensure their proposals communicates what qualifications the vendor has to complete the scope of work listed in Part 2 of the RFP.

Addendum #1-1



ADDENDUM 1

Bid Number: PWDA-230055-DH Bid Name: Public Safety Facilities Construction Manager at Risk

ACKNOWLEDGMENT: Each Proposer shall acknowledge receipt of this Addendum No. 1 by his or her signature below, and a copy of this Addendum to be returned with proposal.

CERTIFICATION BY PROPOSER

The undersigned acknowledges receipt of this Addendum No. 1 and the Proposal submitted is in accordance with information, instructions, and stipulations set forth herein.

PROPOSER:

BY: Domenic Scorpio - President and CEO

DATE: 7-14-23

Addendum #1-2



ADDENDUM 1

Bid Number: PWDA-230055-DH Bid Name: Public Safety Facilities Construction Manager at Risk

CITY OF _____ GAINESVILLE

FINANCIAL SERVICES PROCEDURES MANUAL

41-524 <u>Prohibition of Lobbying in Procurement Matters</u>

Except as expressly set forth in Resolution 170116, Section 9, during the Cone of Silence as defined herein no person may lobby, on behalf of a competing party in a particular procurement process, City Officials or employees, except the Procurement Division or the procurement designated staff contact person. Violation of this provision shall result in disqualification of the party on whose behalf the lobbying occurred.

Cone of Silence period means the period between the issue date which allows for immediate submittals to the City of Gainesville Procurement Division in response to an invitation to bid, or a request for proposal, or qualifications, or information, or an invitation to negotiate, as applicable, and the time that City Officials or the Procurement Division, or City Department awards the contract.

Lobbying means when a person seeks to influence or attempt to influence City Officials or employees with respect to a decision of the City, except as authorized by procurement procedures.

Addendum #1-3



Exceptions to the RFP

Scorpio has read entire RFP. We understand there will be no exceptions under this solicitation.

Claims Information

Scorpio, including its Qualifying Agent and Directors, HAS NOT been involved in litigation, claim(s), bid or contract disputes(s) filed by or against the related to the services that the Firm provides in the regular course of business.

Legal Information

Scorpio, including its Qualifying Agent and Directors, HAVE NEVER failed to comply with or have been the subject of an investigation of an alleged violation of state or federal laws to permitting, environmental, or equal employment regulations, safety issues, or contract crime (involving fraud, bribery, collusion, conspiracy or material misrepresentation).

We conduct business in a highly professional manner, treat all participants with respect, and remain committed to building on our legacy of trust-delivering quality construction projects on time and within budget.





City of Gainesville REQUEST FOR PROPOSALS: #PWDA-230055-DH Public Safety Facilities Construction Manager at Risk

Example of Value Analysis

3911 W Newberry Road Gainesville, Florida 32607 o. 352.363.6070 f. 352.363.6071 scorpioco.com

CGC 061834

Make Buildings for Life.



The following document is provided as an example of the extensive nature of Scorpio's investment in assisting with "designing to budget". This Value Analysis report was generated during the Preconstruction Services for Alachua County Fire Rescue Station # 9 that was later renamed #33.

Our team is committed to working with the City of Gainesville, dedicating this same level of energy and effort should we be selected for this project.

FIRE STATION #9, Gainesville

Introduction:

This section summarizes Scorpio's pre-construction services efforts for delivering Fire Station #9, to be located in Gainesville, Florida. As communicated to our firm, the project budget of \$1,350,000 was established approximately two years ago. At the time the budget was established, the site location had yet to be identified. The project plans and specifications provided for pre-construction services are dated October 12, 2015. The Scorpio engaged the project immediately following Alachua County BOCC approval of the CM Services Agreement, which was formally executed on February 24, 2016. The efforts described in this analysis have taken place over the past 60 days.

Summary:

As currently designed, the project consists of approximately 7,750 SF (9,700 under roof). It is a single story structure to be constructed with painted split-face CMU, light gauge metal trusses and a metal roof. Interior partitions are metal stud framing and drywall. Mechanical, Plumbing, Fire Protection and Electrical systems are consistent with requirements of a Fire Station.

Our effort indicates the project will cost significantly more than the intended budget. This can be attributed to excessive site costs, a strong construction economy, and a shortage of workforce in all crafts. The amount of construction activity in Alachua County at present has construction costs trending upwards at a considerable pace. They are projected to continue to do so in the foreseeable future.

The Estimated Cost of Construction for Fire Station #9, as Designed:

Building Cost: \$1,884,503Site Cost: \$512,813

• Total Cost: \$2,397,316 *See Appendix 1A for details

The project design and estimate was reviewed by the project team, inclusive of the architects, engineers, and facilities management personnel. In an effort to reduce the cost of construction without significantly impacting the programmatic needs of the Fire Station, twenty five (25) items were identified for value engineering analysis. Each item was evaluated by its affects on cost, quality, maintenance, life cycle and aesthetics. Each were given a rating of Good, Fair, or Poor. Of the 25 items reviewed, 18 items were recommended to be incorporated into the project, resulting in a combined cost savings of \$399,626.

The Estimated Cost of Construction for Fire Station #9, Value Engineered (VE):

Building Cost: \$1,521,512Site Cost: \$476,178

• Total Cost: \$1,997,690 *See Appendix 1B for details

Value Engineering:

The items presented as acceptable VE Options by the design, construction, and facilities management team are detailed below. A complete list of VE Options Reviewed is presented in Appendix 1C.

VE #7: Cost Savings, \$18,500

Description: Remove Requirement to Scarify/Shave 1/4" Concrete. This process is not necessary if the concrete slab is grinded during the curing process. This is a means and methods process and will not affect the quality of the finished slab.

Cost: Good
Quality: Good
Maintenance: Good
Life Cycle: Good
Aesthetic: Good

VE #8: Cost Savings, \$4,448

Description: Vinyl Base ilo Stained Wood Base. Vinyl base is typical in commercial applications provides a good maintenance alternative to wood.

Cost: Good
Quality: Fair
Maintenance: Good
Life Cycle: Good
Aesthetic: Fair

VE #7: Grinding ilo Scarifying



Vs. Scarifying



VE #8: Vinyl Base ilo Wood Base





VE #10: Cost Savings, \$6,750

Description: Storefront ilo Curtainwall. In a single story application such as this fire station, the more acceptable product is the storefront assembly over the curtainwall system.

Cost: Good
Quality: Good
Maintenance: Good
Life Cycle: Good
Aesthetic: Good

VE #11: Cost Savings, \$3,800

Description: Standard 20 ga Metal Studs ilo 20 ga Structural Studs. For interior partition construction, the standard studs are more than sufficient for long term ware and tare. These are contained within the wall cavity and not viewed in the space.

Cost: Good
Quality: Good
Maintenance: Good
Life Cycle: Good
Aesthetic: NA


VE #10 Store Front



Vs. Curtainwall



VE #11: Standard 20 ga Metal Stud Vs. 20 ga Structural Stud





VE #12: Cost Savings, \$3,200

Description: Alternate Acoustical Ceiling Grid and Tile. The sound absorption characteristics will remain the same. The proposed ceiling tile will lay flush with the grid system in lieu of sitting into the grid system as originally specified.

Cost: Good
Quality: Fair
Maintenance: Good
Life Cycle: Fair
Aesthetic: Fair

VE #13: Cost Savings, \$3,700

Description: Delete Tile Wainscot in Bathrooms. The new finish will be painted drywall with an epoxy based paint, in lieu of ceramic tile on the wet walls. Tile will still be included at the shower enclosures.

Cost: Good
Quality: Fair
Maintenance: Fair
Life Cycle: Fair
Aesthetic: Fair

VE #12 Ceiling Tile Flush with Grid



Vs Ceiling Tile Laid into Grid



VE #13: Epoxy Based Paint on Wet Walls



VE #16: Ceramic Tile Wainescot



VE #16: Cost Savings, \$7,500

Description: Infrared Heaters in Apparatus Bay ilo Heated Hot Water Heaters. Eliminates the need for a hot water tank. Infrared heaters are electric and generally are pretty efficient.

Cost: Good
Quality: Good
Maintenance: Good
Life Cycle: Good
Aesthetic: Fair

VE #17: Cost Savings, \$15,000


Description: Alternate Light Fixtures - maintain LED. This option requires a high level of coordination between the light fixture supplier and project engineer to ensure the alternates perform as well as the basis of design. Light fixtures will remain efficient LED bulbs.


Cost: NA
Quality: Poor
Maintenance: Poor
Life Cycle: Poor
Aesthetic: Poor

VE #16Infratred Heaters



Vs. Heated Hot Waters





VE #21: Cost Savings, \$6,787


Description: Delete Glazing at Apparatus Bay. This option will minimally reduce the amount of natural day-lighting into the apparatus bays. The roll up doors have a significant amount of glazing and should provide an abundance of natural light.

Cost: Good
Quality: Good
Maintenance: Good
Life Cycle: Good
Aesthetic: Fair

VE #22: Cost Savings, \$6,580

Description: Eliminate Job Site Trailer Requirement. The project specifications established a contract requirement for the CM to provide a job site trailer to work out of. While the trailer provides a secure place for the on-site CM staff to perform their office work and conduct meetings, we can also make alternative plans to assist in the cost reduction strategy.

Cost: Good
Quality: Good
Maintenance: Good
Life Cycle: Good
Aesthetic: Good



VE #22: Eliminate Job Trailer



VE #23: Cost Savings, \$243,204

Description: PEMB Entire Structure, CMU at Living Quarters. This proposes to redesign the structure to a pre-engineered metal building. The sides of the apparatus bay and the entire roof structure will be metal, while the living quarters will remain painted CMU.

Cost: Good
Quality: Fair
Maintenance: Fair
Life Cycle: Fair
Aesthetic: Poor

VE #24: Cost Savings, \$2,001

Description: Polished Floor ilo Rubber Flooring. Continue the polished concrete flooring into the weight training room and eliminate rubber flooring. After market rubber matts will be placed around exercise equipment.

Cost: Fair
Quality: Fair
Maintenance: Poor
Life Cycle: Fair
Aesthetic: Fair

VE #23 Pre-Engineered Bldg.




Vs. Split Faced Block



VE #24: Polished Concrete




Vs Rubber Flooring



VE #25: Cost Savings, \$3,600

Description: Shorten Trench Drains By Half. While longer trench drains make for quick work of removing water from within the apparatus bays when necessary, the frequency of this convenience does not substantiate the cost. This reduction will not adversely affect any of the criteria below.

Cost: Good
Quality: Good
Maintenance: Good
Life Cycle: Good
Aesthetic: Good



VE Items of all building elements are labeled and demarcated below



VE #6: Cost Savings, \$3,500


Description: Reduce Sidewalks. This suggestion is to eliminate the sidewalk at the parking lot, and eliminate the sidewalks to the patio. Pedestrians can walk on the asphalt paving until they reach accommodating sidewalks.

Cost: Good
Quality: Fair
Maintenance: Good
Life Cycle: Good
Aesthetic: Fair

VE #14: Cost Savings, \$3,519

Description: One Flag Pole ilo Two Flag Poles. The design currently shows two flag poles. Only one was requested for the project. The second is being eliminated.

Cost: NA
Quality: NA
Maintenance: NA
Life Cycle: NA
Aesthetic: NA



VE #14 One Flag Pole



Vs Two Flag Poles



VE #18: Cost Savings, \$5,000


Description: Asphalt Paving, 1.5" thickness ilo 2". 1.5" is typical by FDOT standards and suitable for this application. 2" would certainly make the parking and drives more durable against long term ware and tare, but not enough to substantiate the higher cost.


Cost: Good
Quality: Fair
Maintenance: Fair
Life Cycle: Fair
Aesthetic: NA

VE #19: Cost Savings, \$4,154

Description: Delete HVAC Wall. This wall was designed to screen the HVAC condensing units from view on the exterior. With surrounding landscaping, the units should be masked appropriately to draw little notice.

Cost: Good
Quality: NA
Maintenance: Good
Life Cycle: NA
Aesthetic: Fair





VE #20: Cost Savings, \$20,000

Description: Reduce Landscaping. The minimum standard requirement for City of Gainesville Landscape Ordinance is costing the project approx. \$73,000. This cost is excessive for a project of this scale. Alternative solutions to achieve the desired outcome must be addressed by the landscape architect.

Cost: Fair
Quality: Fair
Maintenance: Fair
Life Cycle: Fair
Aesthetic: Fair



VE Items of all site elements are labeled and demarcated below




Conclusion:

By incorporating all of the value engineering items presented above, the project is expected to cost approximately \$2,000,000. The associated site cost of \$476,178 represents more than 35% of the originally established budget, with extremely limited opportunities for additional value engineering.


If additional funds are not available to increase the budget to reflect the current cost of construction, the building size will need to be reduced by 50% of the programmed needs for this fire station to maintain the originally established budget of \$1,350,000.

Building Cost: \$873,822Site Cost: \$476,178

Total Cost: \$1,350,000 *See Appendix 1D for a floor plan comparison



REVISED TO ACHIEVE ORIGINAL BUDGET



We hope you find the information contained in this Proposal aligns with your expectations for delivering Construction Management Services.

We look forward to serving you in this capacity.

Thank you.



Make Buildings for Life.