

TOPOGRAPHIC SURVEY
OF CITY HALL PLAZA
TAX PARCEL 14662-005-000
IN SECTION 05 TOWNSHIP 10 SOUTH RANGE 20 EAST
ALACHUA COUNTY, FLORIDA



1. Demolish the two existing concrete ponds and remove of all palm trees and crepe myrtles within the area of work.
2. Remove additional concrete areas as shown on the plans (trip hazards and tree well expansions).
3. Remove and recycle 3 picnic tables, 2 waste receptacles, 4 whiskey barrel wooden planters, 4 existing bike racks, 2 existing concrete planters and all concrete seats and benches.
4. Install approximately 6,029 SF of new 6" thick 4000 PSI concrete (this includes both new and replacement concrete sidewalk).
5. Electrical work. Install a new service to the flag pole and new receptacle at northern pond (to replace the existing).
6. Plumbing work. Install a new 1" irrigation service line utilizing the existing pool water service and backflow preventer. Install irrigation isolation ball valves in valve boxes with river rock (typ.) in each landscape area (4 total).
7. Site Furnishings: Furnish and install 8 new bike racks (Landscape Forms Ring Bike Racks, Metallic Silver), 2 tables (Landscape Forms Mingle 4 backed seat for accessibility, Metallic Silver), and 2 Trash/Recycling Containers (Bigbelly Solar - Smart Max/Smart Double Station with Hopper and Foot Pedal, Bottle/Can Faceplate, Message Panels, Partial Custom Wrap (Front Doors), Bar-Style Lift Bins, Five Year Warranty, and One Year CLEAN Software). Locations for tables and trash/recycling containers are to be determined by staff during construction.
8. Permitting Fees. Apply for and obtain a city demolition permit and electrical permit. A general site review application will be submit by staff in advance of construction. Please note that 5 parking spaces will be available in the City Hall Parking Lot during the project for the contractor's staff, a dumpster and equipment access (the fee will be waived for this use).
9. This project includes lighting improvements as shown on sheets E1 and E2.

