
CITY OF GAINESVILLE ALFRED A. RING PARK

ARCHITECTS MANUEL SYNALOVSKI ASSOCIATES 1800 ELLER DRIVE, SUITE 500 FORT LAUDERDALE, FLORIDA 33316 CONTACT: MICHAEL SALUS PHONE: 954.961.6806 FAX: 954.961.6807

LANDSCAPE ARCHITECT

KIMLEY-HORN AND ASSOCIATES, INC. 2610 CATTLEMEN ROAD, SUITE 200 SARASOTA, FLORIDA 34232 **CONTACT: CHRIS HICE** PHONE: 941.379.7600 FAX: 941.379.4352



LAND PLANNING CONSULTANT

KIMLEY-HORN AND ASSOCIATES, INC. **445 24TH STREET, SUITE 200** VERO BEACH, FLORIDA 32960 **CONTACT: LISA FRAZIER** PHONE: 772.794.4100 FAX: 772.764.4130

STRUCTURAL ENGINEER

DRISCOLL ENGINEERING, INC. P.O. BOX 357577 **GAINESVILLE, FLORIDA 32635 CONTACT: MIKE DRISCOLL** PHONE: 352.331.1513 FAX: 352.505.3366

SVILLE G PARK Y OF RED

CITY OF GAINESVILLE

MANUEL SYNALOVSKI AA0011628

AA 26001863

DATE DESCRIPTION DELIVERABLE: ISSUE TYPE

ISSUE DATE: 01/03/11 PROJECT NUMBER: 1081-100718

DRAWN BY: MS CHECKED BY: MR

COVER SHEET

G-001

PROJECT SCOPE

THE SCOPE OF THIS PROJECT IS REMOVE AND REPLACE THE EXISTING BOARDWALK SYSTEMS LOCATED AT ALFRED A. RING PARK. ALL NEW BOARDWALKS WILL BE REPLACING EXISTING ONES LEAVING THE GROUND COVERAGE SIMILAR AT PROJECT COMPLETION. TREE REMOVAL WILL ALSO BE PART OF THIS SCOPE AS DESCRIBED WITHIN THE DRAWING SET.

1. ALL WOOD MEMBERS TO BE PREDRILLED AND BOLTED THRU. UNLESS

2. NO BOLT HOLES TO BE MORE THAN 2" FROM END OF WOOD MEMBERS.

	15	ELM TREE DIA. IN INCHES (TYP)		EARTHEN TRAIL
	沙 <u>秦</u>	HICKORY TREE		EARTHEN TRAIL TO BE ABONDONED
		MAPLE TREE		NEW EARTHEN TRAIL TO LEAD TO MODIFIED BOARDWALK
See all the see al	A CONTRACTOR OF THE PROPERTY O	MAGNOLIA TREE		NEW WOODEN BOARDWALK
E 23		OAK TREE	רורונונון) אין אואואן) אין אואואן און אואן און און און און און או	EXISITNG WOODEN BOARDWALK TO BE REMOVED
		PINE TREE	~~~~	FENCES
		SWEETGUM TREE	⊠110.55	BOARDWALK SPOT ELEVATION
		MISC. HARDWOOD TREES	(S)	SANITARY MANHOLE
 14	0	ELEVATION CONTOUR LINE		
(12	2	BOARDWALK IDENTIFIER	SAN	SANITARY SEWER LINE
⊿ DI	RAW	ING LEGEND		

3.	BOLTS TO BE PLACED ON CENTERLINE OF WOOD MEMBERS OR 1-1/2" FROM EDGE, AS APPLICABLE.
4.	USE (2) WASHERS AND NUTS AT EACH THRU BOLT. USE (1) WASHER AT EACH CARRIAGE BOLT.
5.	DECK BOARDS TO BE CAREFULLY SELECTED AND PLACED TO A TOLERANCE OF NOT MORE THAT 1/8" VARIATION IN LEVEL SURFACE AT ADJACENT BOARD EDGES.
6.	ALL DECKING SHOULD BE INSTALLED WITH A 3/16" GAP BETWEEN BOARDS.
7.	ALL WOOD SHALL BE INSTALLED WITH THE CROWN OF THE BOARD FACING DOWN.
8.	BEVEL ALL EXPOSED EDGES AND REMOVE SNAG HAZARDS ON TO-RAIL AND BENCH.
9.	THE CONTRACTOR MUST FIELD VERIFY ALL FASTENER TYPES AND SIZES PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.
10	. ALL SCREWS SHALL BE COATED WITH A LIFETIME PROTECTION. DESIGN STANDARD SHALL BE PHILLIPS II HIGH PERFORMANCE DURAFAST CORING WITH LIFETIME GUARANTEE OUTDOOR SCREW.
11	. NAILS SHALL NOT BE USED TO CONNECT WOOD MEMBERS.
12	. ALL AREAS DISTURBED DURING CONSTRUCTION MUST BE MULCHED WITH PINE BARK MULCH.

BDWK	DEMO	NEW	
1	-	-	
2	1/A-201	3/A-201	
3	2/A-201	4/A-201	
4	1/A-202	6/A-202	
5	2/A-201	4/A-201	
6	1/A-203	2/A-203	
7	2/A-202	7/A-202	
8	3/A-202	8/A-202	
9	4/A-202	9/A-202	
10	1/A-204	2/A-204	
11	1/A-204	2/A-204	
12	5/A-202	10/A-202	
13	1/A-205	2/A-205	

	2/A-201	4/A-201	A-301	SPANNING SECTIONS
	1/A-203	2/A-203		
	2/A-202	7/A-202	L-200	TREE MITIGATION INDEX S
	3/A-202	8/A-202	L-201	TREE MITIGATION PLAN
	4/A-202	9/A-202	L-202	TREE MITIGATION PLAN
)	1/A-204	2/A-204	L-203	TREE MITIGATION PLAN
	1/A-204	2/A-204	L-204	TREE MITIGATION PLAN
2	5/A-202	10/A-202	L-205	TREE MITIGATION PLAN
}	1/A-205	2/A-205	S-101	STRUCTURAL DETAILS
			S-101 S-102	STRUCTURAL DETAILS
			S-103	STRUCTURAL DETAILS

G-001

ES-101

A-201

A-202 A-203

A-204

A-205

3 | CONSTRUCTION NOTES 4 DRAWING LEGEND

BOARDWALK INDEX

DRAWING INDEX

COVER SHEET

EROSION CONTROL PLAN

NEW AND DEMO BOARDWALK 6

NEW AND DEMO BOARDWALK 13


NEW AND DEMO BOARDWALKS 1, 3, & 5

NEW AND DEMO BOARDWALKS 10 & 11

NEW AND DEMO BOARDWALKS 4, 7, 8, 9, & 12

SHEET

SURVEY



PATRICK R. DURBIN, PROFESSIONAL SURVEYOR AND MAPPER FLORIDA CERTIFICATION NUMBER 5368

DATE: 9/29/10


ENGINEERING SUPPORT SERVICES

306 NE 6TH AVENUE (THOMAS CENTER) P.O. BOX 490 GAINESVILLE, FL 32602-0490 OFFICE (352) 393-8194 FAX (352) 334-2093

RECONNAISSANCE SURVEY OF EARTHEN PATHS AND BOARDWALKS ALONG NATURE TRAIL

DATE: SEP 23, 201 NOTES: REDESIGNED BASELINE CHECKED BY: PROJECT #: DATE: SEP 27, 2010 NOTES: ADDED ADDITIONAL SURVEY NOTES

SHEET 1 OF 7



1 > CONTRACTOR MUST SECURE SITE DURING CONSTRUCTION WITH TEMPORARY "ORANGE SCREEN" FENCING AND SIGNAGE AT INDICATED LOCATIONS. COORDINATE VERBIAGE WITH OWNER PRIOR TO CREATING SIGN.

TIMING OF SEDIMENT - CONTROL PRACTICES: SEDIMENT CONTROL PRACTICES SHALL BE FUNCTIONAL THROUGHOUT EARTH-

DISTURBING ACTIVITY. SETTLING FACILITIES, PERIMETER CONTROLS, AND OTHER PRACTICES INTENDED TO TRAP

SEDIMENT SHALL BE IMPLEMENTED AS THE FIRST STEP OF GRADING AND WITHIN SEVEN DAYS FROM THE START OF GRUBBING. THEY SHALL CONTINUE TO FUNCTION UNTIL THE UPSLOPE DEVELOPMENT AREA IS RESTABILIZED.

STABILIZATION OF NON STRUCTURAL PRACTICES:

CONTROL PRACTICES SHALL PRESERVE EXISTING VEGETATION WHERE ATTAINABLE AND DISTURBED AREAS SHALL BE MULCHED WITH PINE BARK AS SOON AS PRACTICAL AFTER GRADING OR CONSTRUCTION.

SHEET FLOW RUNOFF FROM DENUDED AREAS SHALL BE INTERCEPTED BY SEDIMENT

SEDIMENT BARRIERS SUCH AS SEDIMENT FENCE OR DIVERSIONS TO SETTLING FACILITIES SHALL PROTECT ADJACENT PROPERTIES AND WATER RESOURCES FROM SEDIMENT TRANSPORTED BY SHEET FLOW.

CONSTRUCTION ACCESS ROUTES:

MEASURES SHALL BE TAKEN TO PREVENT SOIL TRANSPORT ONTO SURFACES OR PUBLIC ROADS WHERE RUNOFF IS NOT CHECKED.

CONSTRUCTION SEQUENCE:

1. INSTALL SEDIMENT CONTROL MEASURES

- 2. REMOVE EXISTING STRUCTURES 3. PLACE PINE BARK ON ALL EXPOSED/DENUDED SURFACES
- 4. INSTALL NEW STRUCTURES 5. REMOVE CONSTRUCTION FENCE
- 6. PERFORM CLEAN UP AND MAINTENANCE

FILTER BARRIERS SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHALL BE MADE

SHOULD THE FABRIC ON A SEDIMENT FENCE OR FILTER BARRIER DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER IS STILL NECESSARY, THE FABRIC SHALL BE REPLACED PROMPTLY.

REMOVED WHEN DEPOSITS REACH APPROXIMATELY ONE-THIRD THE HEIGHT OF THE

SEDIMENT DEPOSITS SHOULD BE REMOVED AFTER EACH STORM EVENT. THEY MUST BE

ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SEDIMENT FENCE OR FILTER BARRIER IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM WITH THE EXISTING GRADE, PREPARED, AND MULCHED.

ADDITIONAL MEASURES:

THIS PLAN AND NARRATIVE REPRESENTS THE MINIMUM AMOUNT OF EROSION AND SEDIMENT CONTROL MEASURES, IN THE OPINION OF THE ENGINEER, THAT MAY BE NECESSARY UNDER FAVORABLE WEATHER CONDITIONS. THE CONTRACTOR IS RESPONSIBLE FOR ANY ADDITIONAL MEASURES OR PRACTICES THAT MAY BE NECESSARY TO CONTROL EROSION, TURBID DISCHARGE, FUGITIVE PARTICULATES, ETC. TO FULLY COMPLY WITH ALL GOVERNMENTAL RULES AND/OR PERMIT REQUIREMENTS. POLLUTION PREVENTION:

THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PROGRAM IS REGULATED THROUGH THE FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION (FDEP). IF YOUR CONSTRUCTION ACTIVITY MEETS THE FOLLOWING CRITERIA:

1. CONTRIBUTES STORMWATER DISCHARGE TO SURFACE WATERS OF THE STATE OR INTO A MUNICIPAL SEPARATE STORM SEWER SYSTEM (MS4); AND/OR

2. DISTURBS ONE OR MORE ACRES OF LAND INCLUDING LESS THAN ONE ACRE IF ACTIVITY IS PART OF A LARGE COMMON PLAN OF DEVELOPMENT OR SALE THAT WILL MEET OR EXCEED A ONE ACRE THRESHOLD. DISTURBANCE INCLUDES CLEARING, GRADING AND EXCAVATING. THEN YOU WILL BE REQUIRED TO SUBMIT A NOTICE OF INTENT (NOI) AND PREPARE A STORMWATER POLLUTION PREVENTION PLAN (SWPPP). FOR MORE INFORMATION PLEASE VISIT FDEP'S WEBSITE AT WWW.DEP.STATE.FL.US/WATER/STORMWATER/NPDES.

CITY OF GAINESVILLE 200 EAST UNIVERSITY AVENUE

GAINESVILLE, FL 32601

MANUEL SYNALOVSKI

AA0011628

AA 26001863

귀X 7 SU Y OF RED

3 EROSION CONTROL NOTES

PRINCIPLE POST POSITION (CANTED POST (OPTIONS 2"x2"x4 1/2" HIGH 20° TOWARD FLOW)-OR 3"`MIN. DIA. WOOD, -STEEL 1.33 LBS/FT. MIN.) OPTIONAL POST POSITION 10' MAX. CONSTRUCTION FENCE SHOULD BE INSTALLED DOWN SLOPE AT EACH BOARDWALK FROM THE START TO FINISH OF THE LIMITS OF CONSTRUCTION DEPICTED ON SHEETS A-201 THROUGH A-205. ALL SOIL REMOVED TO ALLOW FOR NECESSARY STRUCTURAL EXCAVATIONS SHALL BE IMMEDIATELY TRANSPORTED OFF SITE. DEBRIS FLOW ELEVATION -ORANGE PLASTIC TEMPORARY

DATE DESCRIPTION DELIVERABLE: ISSUE TYPE ISSUE DATE: **01/03/11**

PROJECT NUMBER: 1081-100718 DRAWN BY: MS


CHECKED BY: MR


EROSION CONTROL PLAN

ES-101


CONSTRUCTION FENCE, TYP.

CONSTRUCTION FENCING

















NOTES:

- 1. SEE BMP FOR SILT FENCING LOCATIONS & DETAILS.
- 2. CONTRACTOR SHALL COORDINATE PHASING OF TREE MITIGATION / PROTECTION PLANS TO ENSURE THAT TREES TO REMAIN ARE FULLY PROTECTED.
- 3. SEE SHEET L-250 FOR TREE MITIGATION NOTES
- 4. ALL TREES SHALL BE PRESERVED UNLESS OTHERWISE APPROVED BY PROJECT ARBORIST OR CLIENT.
- 5. TREE PROTECTION FENCING SHALL REMAIN ERECTED AT ALL TIMES THROUGHOUT CONSTRUCTION. UPON COMPLETION OF EXISTING TRAIL AND BOARDWALK DEMOLITION, TREE PROTECTION FENCES SHALL BE RELOCATED ACCORDING TO THE PROPOSED BOARDWALK PLANS.
- 6. TREE PROTECTION FENCES ARE TO BE ERECTED AT A MAXIMUM OF THREE FEET (31) OFF OF ONSITE STRUCTURES, BOTH EXISTING AND PROPOSED, FOR DEMOLITION AND CONSTRUCTION OF BOARDWALKS AND TRAILS; EXCEPT FOR DESIGNATED CONSTRUCTION ACTIVITY AREAS. WHERE REGULATED TREES ARE LOCATED WITHIN THREE FEET (31) OF BOARDWALK, THE TREE PROTECTION FENCE SHALL BE ERECTED DIRECTLY ADJACENT TO THE DEMOLITION / PROPOSED BOARDWALK.
- 7. THE LIMITS OF CONSTRUCTION (LOC) SHALL BE A MAXIMUM OF 10 FEET OUTSIDE THE EXISTING ONSITE STRUCTURES SCHEDULED FOR REPLACEMENT. THE LOC WILL BE CLEARLY FLAGGED BY THE PROJECT MANAGER AND STAKED BY THE CONTRACTOR UTILIZING A COMBINATION OF ORANGE TREE BARRIER AND SURROUNDED BY AN ENTRENCHED SILT FENCE BEFORE ANY CLEARING OR REMOVAL ACTIVITY OCCURS.
- 8. NO REGULATED TREES MAY BE DAMAGED OR REMOVED WITHIN THIS BOUNDARY WITHOUT WRITTEN APPROVAL OF THE CITY'S PROJECT
- 9. NON-REGULATED TREES LOCATED WITHIN TREE PROTECTION FENCING SHALL BE PROTECTED FROM DAMAGE. IF SUCH TREES ARE DAMAGED, VERIFICATION OF THE TREE'S HEALTH MUST BE INSPECTED BY PROJECT ARBORIST. IF DAMAGED/DEAD TREES MUST BE REMOVED, REPLACEMENT TREES OF THE SAME SPECIES MUST BE REPLANTED AT CONTRACTORS COST.
- 10. CONTRACTOR IS TO REMAIN WITHIN TREE PROTECTION FENCING AT ALL TIMES. NO WORK IS TO BE DONE OUTSIDE OF THIS ZONE WITHOUT THE COORDINATION OF PROJECT ARBORIST.
- 11. ALL CONSTRUCTION ACTIVITY INCLUDING TRANSPORT OF MATERIALS OR PERSONNEL, MUST BE CONFINED WITHIN THE LOC. A. PRIMARY CONSTRUCTION ACTIVITIES AND MATERIALS TRANSPORT SHOULD BE WITHIN THE EXISTING FOOTPRINT OF THE STRUCTURES TO BE REMOVED.
- 12. AT NO TIME SHALL CONTRACTOR HAVE EQUIPMENT OR MATERIALS OUTSIDE THE EXISTING LIMITS OF THE TRAIL.
- 13. CONTRACTOR TO COORDINATE WITH PROJECT LANDSCAPE ARCHITECT / OWNER FOR APPROVED LOCATION OF REPLACEMENT






<u>Plan View</u>



DETAIL



- 1. 6'H "PERIMETER PLUS" CONSTRUCTION FENCE BY CONWED PLASTICS OR OWNER'S REPRESENTATIVE APPROVED EQUAL SUBMIT PRODUCT INFORMATION FOR APPROVAL PRIOR TO INSTALLATION.
- 2. 8' TALL METAL "T" POSTS OR 2" x 4" X 8' PRESSURE TREATED WOOD POSTS WITH 24" BURIAL BELOW GRADE.

NOTES:

- 1. METAL "T" POSTS OR PRESSURE TREATED 2"X4" WOOD POSTS ARE TYPICALLY USED FOR CONSTRUCTION AND OTHER APPLICATIONS.
- 2. POSTS SHOULD BE DRIVEN INTO THE GROUND TO A DEPTH OF 1/3 OF THE HEIGHT OF THE POST. FOR EXAMPLE, A 6' POST SHOULD BE SET AT LEAST 2' INTO THE GROUND.
- 3. SPACE POSTS EVERY 6' (MIN.) TO 8' (MAX.).
- 4. SECURE FENCING TO POST WITH NYLON CABLE TIES (AVAILABLE FROM CONWED PLASTICS). WOOD STRIPS MAY BE ALSO BE USED TO PROVIDE ADDITIONAL SUPPORT AND PROTECTION BETWEEN TIES AND POSTS.
- 5. IF WIRE TIES ARE USED, AVOID DIRECT CONTACT WITH FENCE. WIRE MAY DAMAGE FENCE OVER TIME.

TREE REMOVAL

REPLACEMENT SCHEDULE

TOTAL TO BE REMAIN

TOTAL TO BE REMOVED

REPLACEMENT RATIO REPLACEMENT QUANTITY

1	124	27	1	21	7
)	2	-	-	-	-
	2:1	1": 1"	2:1	1": 1"	1": 1"
	,				

REQ. TOTAL

ANY ADDITIONAL TREES THAT MAY NEED TO

BE REPLACED TO MEET THE REQUIREMENTS SHOWN IN THIS SCHEDULE.

BE REMOVED DURING CONSTRUCTION SHALL

TWO (2) ULMUS AMERICANA AND TWO (2) ACER SACCHARUM SHALL BE INSTALLED AS REPLACEMENT TREES


ALL REPLACEMENT TREES SHALL BE FIFTEEN (15) GALLON CONTAINER SIZE AND SHALL BE IN ACCORDANCE WITH GRADES AND STANDARDS FOR NURSERY PLANTS, LATEST EDITION, PUBLISHED BY THE FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUMER SERVICES. ALL PLANTS SHALL BE FLORIDA GRADE NO. 1 OR BETTER AS DETERMINED BY THE FLORIDA DIVISION OF PLANT INDUSTRY. ALL PLANTS SHALL BE HEALTHY, VIDOROUS, SOUND, WELL-BRANCHED, AND FREE OF DISEASE AND INSECTS, INSECT AEGGS AND LARVAE, AND SHALL HAVE ADEQUATE ROOT SYSTEMS. ALL MATERIALS SHALL BE SUBJECT TO APPROVAL BY THE OWNER.

MITIGATION LEGEND



EXISTING TREE TO
SAVE IN PLACE

EXISTING TREE
TO BE REMOVED



TREE WITH DBH GREATER THAN 20" DENOTES TREE OUTSIDE OF PROJECT BOUNDARY

--- Existing tree canopy spread


TIGA' SHE MITIG/ EX SHI TREE INDI


RING PARK GAINESVILLE ALFRED CITY OF (


10/27/2010 PROJECT NO. 142237000

SHEET NUMBER

L-200









MITIGATION PLAN


ALFRED RING PARK CITY OF GAINESVILLE DATE


PROJECT NO. 142237000 SHEET NUMBER


L-203











#5 Bars (refer to Table for

number by footing size)

S102

Typical Isolated Concrete Spread Footing

4 Each #5 Bars @ 10" O.C.

Michael E. Driscoll, P.E.

Fl. Reg. #43922

CHECKED BY:

SHEET TITLE:

S-102

#5 Bars @ 16" O.C.

S102

18"

Section at Walkway Transition to Grade

